



ESV Safety Case

MAN-368

APA Victoria Transmission ESV Safety Case

NOTE:

Refer to the National ER&S Plan 320-PL-ER-0001 in the event of an emergency incident. EME-020 VTS ER Manual has been archived. Updated MAN-368 ESV Safety Case reflects this change and is with ESV for review.

Version: 16.1 Issued: 4/12/2014

DOCUMENT CONTROL

Approval

| Summary of Changes | Albert Brovedani Technical Regulations | |
|--------------------|---|-------------|
| Custodian | | |
| Reviewed | Craig Bonar, Manager East Coast Grid Engineering, Infrastructure Strategy & Engineering | Cold bond |
| Approved | Kerryanne Mallitt, General Manager Transmission Operations | L'I Mallett |

Distribution List

| Copies to: | Name / Details | Location |
|------------|---------------------------|-------------------------------|
| 1 | Controlled Copy | Transmission Document Library |
| 2 | Working Copy - Controlled | Plan Room, Dandenong |
| 3 | Working Copy – Controlled | Control Room, Dandenong |

Printed Working Copy

All printed copies of this procedure are to be used as reference copies only. It is the responsibility of those with printed copies to ensure that the procedures are current. Transmission documents and templates are published into the **Transmission Document Site**. Access document templates and all current Transmission documents are available from this site, which includes links to the WA, QLD, NT regional document libraries.

Responsibility

Any amendments to this document will be the responsibility of the document author or custodian. All native copies of published Transmission documents are managed by the Transmission Document Controller. Use the <u>document change</u> request form to initiate a change or to request a controlled document number when creating a new document.



Table of Contents

| 1 | INTRODUCTION | 4 |
|------------|---|---|
| 2 | DOCUMENT SCOPE | 4 |
| 3 | RESPONSIBILITY OF ASSET | 4 |
| 4 | RESPONSIBILITY OF SAFETY CASE | 4 |
| 5 | RECORDS STORAGE | 4 |
| 6 | FACILITY DESCRIPTION | 5 |
| 7 | PIPELINE SAFETY MANAGEMENT STUDY & FORMAL SAFETY ASSESSMENT | 5 |
| 8 | SAFETY MANAGEMENT SYSTEM | 5 |
| 9 | ENVIRONMENTAL MANAGEMENT PLAN | 5 |
| 10 | DOCUMENT MANAGEMENT | 6 |
| 11 | ATTACHMENTS | 7 |
| 12 | DEFINITIONS / ABBREVIATIONS | 7 |
| 1 3 | REFERENCES | 7 |
| 14 | REVISION HISTORY | 7 |

v16.1

1 INTRODUCTION

Under the Gas Safety (Safety Case) Regulations 2008 the Safety Case is a document describing in detail the operating and management practices adopted by a business that seeks to minimise to *"as low as reasonably practicable" (ALARP)*, the non-commercial risks and hazards arising from the operation of the business.

2 DOCUMENT SCOPE

This Policy specifies the documents, which comprise the Safety Case for the licenced pipelines which are collectively known as the Victorian Transmission System (VTS), as accepted by the Energy Safe Victoria in accordance with the Gas Safety Act 1997.

Also identified is the person responsible for the operation of the facility, the person responsible for the Safety Case and the address where the records are kept.

APA GasNet will not commission or operate a facility without an accepted Safety Case in place, and shall at all times comply with the accepted Safety Case.

The Safety Case is revised once every five years, or upon changes to the facilities which would initiate a change in risk profile, and APA shall submit any Safety Case revision to Energy Safe Victoria.

3 RESPONSIBILITY OF ASSET

The title of the position and the name and business address of the person who has management of the facility and is responsible for its safe operation is:

Mick McCormack

Managing Director APA Group, Level 19, HSBC Building 580 George St, Sydney 2000

4 **RESPONSIBILITY OF SAFETY CASE**

The person who is responsible for the preparation and submission of this safety case is:

Albert Brovedani

Technical Regulations Manager APA Group, 180 Greens Rd Dandenong South, Victoria, 3175 Email: <u>Albert.Brovedani@apa.com.au</u>

5 RECORDS STORAGE

All records related to this Safety Case are kept at:

APA Group, Dandenong Office

180 Greens RoadDandenong South, VIC 3175Custodian: Albert Brovedani, Technical Regulations Manager

Email: Albert.Brovedani@apa.com.au

6 FACILITY DESCRIPTION

A detailed description of the structure, assets, function and operation of the pipeline system to which the APA-VT ESV Safety Case applies is specified in MAN-368-ATT01.

The description contains sufficient information to enable the extent and scope of the system, its operations and associated risks to be assessed.

7 PIPELINE SAFETY MANAGEMENT STUDY & FORMAL SAFETY ASSESSMENT

APA GasNet conducts a Pipeline Safety Management Study (SMS) on the VTS in accordance with AS 2885.1 as a minimum once every five years, or as specific changes require a review.

The SMS is a major source of assessing risks to the pipeline and forms the basis for resourcing requirements, protection measures and many of the systems and operational procedures that apply to safe operation of the VTS. This is further described in *MAN-107 "APA VT Safety Management Manual"* and the most recent SMS report is included as an attachment to this Safety Case.

A Formal Safety Assessment of pipeline operational activities is also undertaken and is specified in MAN-368-ATT02 "Formal Safety Assessment".

The assessment is consistent with the Facility Description and provides the following:

- a) A description of the methodology used and the investigations undertaken for the formal safety assessment; and
- b) An identification of all hazards having the potential to cause a gas incident; and
- c) A detailed and systematic assessment of risk, including the likelihood and consequences of a gas incident; and
- d) A description of technical and other measures undertaken, or to be undertaken, to reduce that risk to ALARP.

Results of the SMS are considered when performing the Formal Safety Assessment, with particular focus on "intermediate" risks from the SMS, and also including a review of incidents over the previous 5 years.

Whilst there is a focus on achieving ALARP on the VTS at all times, APA also develops Asset Management Plans which seek to ensure the integrity of the pipeline and mechanical maintenance of facilities are reliable and to a standard that prevents potential gas incidents identified through the SMS and Formal Safety Assessment.

The Pipeline Integrity Management Plan (PIMP) details the specific activities undertaken to ensure integrity issues are dealt with in a systemic manner based upon various data and risk identification sources. The PIMP is submitted as part of the Safety Case and is specified in document 320-PL-AM-0006.

8 SAFETY MANAGEMENT SYSTEM

The safety management system to be followed in relation to the facility is specified in MAN-107 "Safety Management System".

9 ENVIRONMENTAL MANAGEMENT PLAN

Environmental issues and the protection to the environment from the impact of APA GasNet activities is governed by the Environment Management Plan (EMP) and a set of Environmental procedures and work instructions.

APA Group

The EMP was published on the 24th July 2013 and is reviewed once every five years.

The overall purpose of the EMP is to demonstrate how pipeline operations interact with the environment and how consequential environmental risks are reduced to ALARP by:

- Providing information on the environment in which pipeline operations are taking place;
- Identifying environmental risks associated with pipeline operations and their potential consequences;
- Identifying environmental objectives and performance criteria for the VTS;
- Describing the management implementation plan to identify, assess and control environmental risks;
- Defining requirements for environmental reporting to statutory bodies; and
- Describing the program for monitoring and auditing of environmental risks and effects.

APA GasNet also maintains an Environmental Risk Register which is attached to the VTS Safety Case as document number being; MAN-368-ATT03.

10 DOCUMENT MANAGEMENT

All documentation, asset records, MDR's and drawings, including the entire Safety Case and all superseded versions will be securely stored or archived in accordance with APA Group's Document Management Systems' Policy. In some cases, these documents and/or records will be archived for least seven (7) years or as required, for the lifetime of the asset.

"Documentation" also includes all gas incident reports and analysis for the asset/facility; SMS reviews, calibration and repair records and all relative training records.

The records required to be kept under sub-regulation (1) Gas Safety (Safety Case) Regulation 2008-SCT 37 are:

- a) the accepted safety case;
- b) any revisions of the accepted safety case;
- c) any written audit reports of the accepted safety case;
- d) any reports of investigations by the gas company of gas incidents;
- e) a copy of each report given by the gas company to Energy Safe Victoria.

11 ATTACHMENTS

| Reference | Title / Description |
|----------------|--|
| MAN-368-ATT01 | Facility Description |
| MAN-368-ATT02 | Formal Safety Assessment |
| MAN-368-ATT03 | Environmental Risk Register |
| MAN-107 | (APA VT) Safety Management System |
| 320-PL-AM-0006 | VTS Pipeline Integrity Management Plan |
| 320-PL-AM-0008 | Asset Management Plan |

APA Group

12 DEFINITIONS / ABBREVIATIONS

| Abbreviation | Description | |
|--------------|------------------------------------|--|
| ALARP | As Low as Reasonably Practicable | |
| APA Group | Asset owner | |
| APA VTS | APA Victoria Transmission | |
| EMP | Environment Management Plan | |
| ESV | Energy Safe Victoria | |
| MDR | Manufacturers Data Records | |
| PIMP | Pipeline Integrity Management Plan | |
| SMS | Safety Management Study | |
| VTS | Victorian Transmission System | |

13 REFERENCES

| Title |
|---|
| Gas Safety Act 1997 |
| Gas Safety (Safety Case) Regulations 2008 |

14 REVISION HISTORY

| Revision | Date | Amendment | Author |
|----------|---------|-------------|--------|
| 0.1 | 20.4.98 | Draft issue | B. W. |
| | | | · |

APA Victoria Transmission ESV Safety Case

| Revision | Date | Amendment | Author |
|----------|----------|---|--------------|
| 1.0 | 22.4.98 | Initial issue | B. W. |
| 2.0 | 29.4.98 | EME 020 added | B. W. |
| 3.0 | 21.5.98 | Forward by Chairman included | B. W. |
| 4.0 | 19.8.98 | Revised procedure MAN 369 identified | M.M. |
| 5.0 | 14.9.98 | Scope amended, Appendices A and B added | B. W. |
| 6.0 | 18.6.99 | Converted from TPA to GPU GasNet document Appendix C added | B. W. |
| 7.0 | 12.7.99 | Appendix A - Safety Case Forward - resigned | M. M. |
| 8.0 | 18.11.99 | Personal responsibility for the Safety Case amended | B. W. |
| 9.0 | 09.02.00 | Personal responsibility for the Safety Case amended | M.M. |
| 10.0 | 24.05.02 | Changed name to GasNet and heading to OGS Safety Case | B.A. |
| 11.0 | 29.08.03 | Revision of Safety Case | M. Snell |
| 12.0 | 30.05.05 | Change Responsibilities to positions | M. Snell |
| 13.0 | 19.12.08 | Revision of Safety Case | M. Snell |
| 14.0 | 29.05.09 | Revised to meet requirements of 2008 Regulations | M. Snell |
| 15.0 | 17.08.12 | Revised to reflect organisational change | M. Snell |
| 16.0 | 02.12.14 | Revision of Safety Case | A. Brovedani |
| 16.1 | 02.06.15 | Revision following submission to ESV | A. Brovedani |

APA Group





ESV Safety Case

MAN-368-ATT02

ESV Safety Case Formal Safety Assessment

Version: 8.0 Issued: 4/12/2014

DOCUMENT CONTROL

Approval

| Summary of Changes | Full review of emergency plan and update to reflect site requirements attachments. | |
|--------------------|--|------------|
| Custodian | Albert Brovedani, Technical Regulations Manager, Infrastructure | HA BL- |
| Reviewed | Craig Bonar, Manager East Coast Grid Engineering | Cold bond |
| Approved | Kerryanne Mallitt, General Manager Transmission Operations | 24 Mallett |

Distribution List

| Copies to: | Name / Details | Location |
|------------|---------------------------|-------------------------------|
| 1 | Controlled Copy | Transmission Document Library |
| 2 | Working Copy - Controlled | Plan Room, Dandenong |
| 3 | Working Copy – Controlled | Control Room, Dandenong |

Printed Working Copy

All printed copies of this procedure are to be used as reference copies only. It is the responsibility of those with printed copies to ensure that the procedures are current. Transmission documents and templates are published into the **Transmission Document Site**. Access document templates and all current Transmission documents are available from this site, which includes links to the WA, QLD, NT regional document libraries.

Responsibility

Any amendments to this document will be the responsibility of the document author or custodian. All native copies of published Transmission documents are managed by the Transmission Document Controller. Use the <u>document change</u> request form to initiate a change or to request a controlled document number when creating a new document.

APA Group

Table of Contents

| 1 | INTRODUCTION | 4 |
|---|--|----------------|
| 2 | DOCUMENT SCOPE | 4 |
| 3 | OVERVIEW | 4 |
| | 3.1 Risk Assessment Methodology | .4 .5 |
| | 3.1.1.1. 2001/2002 Review 3.1.1.2. 2003 Review 3.1.1.3. 2008 Review 3.1.1.4. 2014 Review | .5 .6 |
| | 3.2 Assessment Model | .7 .7 .8 |
| 4 | ATTACHMENTS | 9 |
| 5 | DEFINITIONS / ABBREVIATIONS | 9 |
| 6 | REFERENCESS | 9 |
| 7 | REVISION HISTORY | 9 |

1 INTRODUCTION

As part of the ESV Safety Case, APA has carried out a formal safety assessment to identify and assess the hazards inherent in its operations. This Procedure sets out the methodology used to conduct the assessment, the models used for assessment, and the results of the process.

2 DOCUMENT SCOPE

This document contains:

- A description of the methodology used and investigations undertaken for the formal safety assessment,
- An identification of all hazards having the potential to cause a gas incident,
- A detailed and systematic assessment of risk, including the likelihood and consequences of a gas incident, and
- A description of technical and other measures undertaken to reduce that risk as far as practicable.

3 OVERVIEW

The initial risk assessment was conducted in 1998 in three stages as follows:

- The systematic identification of all hazards taking an "all risks" approach, identifying all hazards without regard to their nature, cause, or severity. Each hazard was subsequently assessed to eliminate hazards not having potential to cause a gas incident (e.g. occupational health issues).
- 2) Each remaining hazard was subject to a detailed and systematic assessment of the consequences and likelihood to determine the residual risk classification.
- 3) For each of these hazards, all technical, procedural and other measures in place or to be undertaken to reduce or mitigate the risk as far as reasonably practicable were identified.

This methodology complies with the various requirements found in:

- Victorian Gas Safety Act and Gas Safety (Safety Case) Regulations 2008
- AS 2885.1, Pipelines Gas and Liquid Petroleum (specifically Part 1 Section 2 Safety)
- Australian Pipeline Industry Association Inc. (APIA) Companion Document to AS 2885.1
- AS 3931, Risk analysis of technological systems
- AS 4360, Risk Management
- Victorian Gas Industry Act
- Victorian Pipelines Act
- Australian Gas Association (AGA) AG606 Code of Practice for the Preparation of a Safety Case for Gas Networks.

3.1 Risk Assessment Methodology

1.1.1 Hazard Identification Methodology

Hazards were identified through a series of workshops involving technical staff from all disciplines to bring all the available experience to the task.

These workshops followed a structured approach based on segmentation of the business areas along the supply chain model. The supply chain model was established in the first workshop and re-evaluated for its completeness following the identification stage. The business areas that were explored are:

APA Group

| Design – philosophy and brief | Metering and Injection |
|---|--|
| Design – specifications, standards and legal requirements | Quality analysis |
| Design – parameters, criteria and survey | Odorisation |
| Material acceptance | Compression stations |
| Construction | Regulation |
| Project contract management | Heating |
| Acceptance testing | Valve control |
| Integration | Transmission |
| Quality assurance | Offline sampling |
| Commissioning | LNG vaporisation, odorisation, and recompression |
| Information management | Personnel selection and training |
| Operating procedures – development and maintenance | Liquids removal |
| Operating procedures – training | Cathodic protection |
| Warehousing materials | Pipeline security |
| Change management | Commissioning |
| Emergency management | Intelligent pigging |
| Property and asset management | Monitoring and SCADA |
| | |

An "all risks" approach to hazard identification was adopted, in order to document all hazards without regard to their nature or severity. This was a clear and deliberate decision taken to ensure the rigour of the identification process despite the necessity for further assessment to remove non-"gas incident" hazards. Workshop participants were encouraged to think beyond the confines of their current positions in order to fully utilise the wealth of experience represented by the groups.

3.1.1 Review

3.1.1.1. 2001/2002 Review

Minor changes in the risk assessment methodology were adopted with the inclusion of property value as the primary means of assessing "loss of amenity/property damage". Previously, the loss of amenity/property damage assessment was purely qualitative and difficult to assess reliably.

During the review process, the Risk Register was also reviewed in light of incidents reported since the original risk assessment was conducted and after a number of asset-specific risk assessments, such as the valve risk assessment. Where appropriate, changes were made to hazards, consequences, likelihoods and controls. The format of the Risk Register was also modified.

3.1.1.2. 2003 Review

The review started by the development of a cause-effect map. The map links the effects (injury/death, property damage, supply restriction/failure, environmental damage and commercial impacts) through events to hazards or causes. The hazards from the pre-existing risk register were mapped on to the cause effect map and the map reviewed for completeness.

Existing hazards have been rationalised to remove duplication and a number of new hazards added. Commercial impacts were added to cover effects such as metering which has no safety consequences but could result in significant business risk.

Risk process maps were also developed for corrosion, third part protection, overpressure and human effects where further detail of the risk management processes is desirable.

A review of incidents since 2002/2003 identified changes to the consequence, likelihood and risk of hazards 16 inadequate incorrect or outdated operating and maintenance procedures, 45 venting purging blowdown and flaring, 48 intrusion vandalism and theft, 52 communications failure.

The risk review was performed through a consultative process with APA-VT section managers and key personnel. The risk register, cause and effect map and risk process maps were circulated to section managers and GasNet for review and comment.

3.1.1.3. 2008 Review

The Formal Safety Assessment was updated to use the risk matrix from AS2885.1-2007, except that the "Remote" likelihood of the standard was extended to two decades of probability and described as "Remote" and "Improbable" to keep it in line with the APA-VT MHF Safety Case.

The FSA review was performed in a workshop comprising of Manager Transmission Operations, Manager Asset Management and Engineering Victoria, Manager Projects Victoria, Manager Operations Support and Manager Technical Regulations.

The review removed duplication in the "old" hazard register and reassessed the risk levels of all threats.

3.1.1.4. 2014 Review

The FSA was reviewed and updated to comply with the format of ISO AS/NZS 31000, the Risk Management Standard using a tailored database known as CGR. The CGR database provides the flexibility to allow the FSA to become a live document that is regularly updated, although the five yearly reviews will still take place.

The FSA was reviewed in a workshop format comprising a multi-disciplined team across the business and was attended by:

| Craig Bonar, Manager East Coast Engineering | Albert Brovedani, Technical Regulations Manager |
|---|---|
| Alice Rawlinson, Environment Manager | Raymond Tan, Operations Support Manager Group Services |
| Daniel Tucci, Senior Concept Engineer | Carlo Corso, Operations Support Manager Operations Services |
| Lachie Marshall, Land Agent Victoria | Alan Burt, Engineering Manager Development |
| John Rodrigues, Principal Planning Engineer | Ron Lourensz, Engineering Services Manager Victoria |
| Benjamin Foo, Pipeline Services Engineer | Jonathan Bryan, Technical Regulations Manager |

The main requirement is to identify all hazards in the operation and maintenance of the VTS which have the potential to cause a "Gas Incident". A "Gas Incident" means any incident or event relating to the conveyance, supply or use of gas which causes or has the potential to cause—

(a) the death of or injury to a person; or

(b) significant damage to property; or

(c) an explosion;

As a part of this workshop each hazard on the register was reviewed, the results of the most recent VTS SMS considered, and a review of all hazards and incidents reported over the past five years undertaken as a form of being able to identify a comprehensive list of hazards for the FSA.

Each hazard was subject to a detailed and systematic assessment of the consequences and likelihood to determine the risk classification.

For each of these hazards, all technical, procedural and other measures in place or to be undertaken to reduce or mitigate the risk as far as reasonably practicable have been identified and documented to determine the residual risk ranking.

It was determined that some of the hazards from previous assessments would fit better as consequences to a risk, therefore there are now less hazards on the register, consequences are better defined and all controls have been identified.

3.2 Assessment Model

3.2.1 Consequence

Consequence was defined as: "The most realistic outcome expected if the hazardous event occurs. The consequence may take the three forms shown in any combination and where this occurs; the most severe of the realistic outcomes has been used".

| | Safety/People | Security of Supply | Environment |
|--------------|---|--|--|
| Catastrophic | Multiple fatalities | Long term interruption of supply | Effects widespread; viability of ecosystems or species affected; permanent major changes |
| Major | Few fatalities; several people with life threatening injuries | Prolonged interruption; long term restriction of supply | Major off-site impact; long term severe effects; rectification difficult |
| Severe | Hospitalisation injuries | Short term interruption; prolonged restriction of supply | Localised (<1ha) and short term (<2y) effects; easily rectified |
| Minor | Medical attention injuries | Short term interruption; restriction of supply but shortfall met from other sources | Effect localised (<0.1ha) and very short term (weeks); minimal rectification |
| Trivial | Minimal Impact on Health & Safety | No impact; no restriction of supply | No effects; minor on-site effects rectified rapidly with negligible residual effects |

3.2.2 Likelihood

The likely frequency that the hazardous event will occur and result in the expected outcome as noted by Consequence:

| Likelihood | Frequency |
|--------------|--|
| Frequent | Expected to occur at least once per year or more |
| Occasional | May occur occasionally in the life of the pipeline |
| Unlikely | Unlikely to occur in the life of the pipeline, but possible |
| Remote | Not anticipated for this pipeline at this location |
| Hypothetical | Theoretically possible, but has never occurred on a similar pipeline |

3.2.3 Risk Matrix

Based on the likelihood and consequence of a hazardous event, the residual risk is classified into five categories as defined below for the purposes of managing that residual risk. The definitions of management actions for each of the five classes are as follows:

| Likelihood | | Consequence | | | |
|--------------|--------------|--------------|--------------|--------------|------------|
| | Catastrophic | Major | Severe | Minor | Trivial |
| Frequent | Extreme | Extreme | High | Intermediate | Low |
| Occasional | Extreme | High | Intermediate | Low | Low |
| Unlikely | High | High | Intermediate | Low | Negligible |
| Remote | High | Intermediate | Low | Negligible | Negligible |
| Hypothetical | Intermediate | Low | Negligible | Negligible | Negligible |

3.2.4 Risk management actions by risk class

| Extreme Risk | Modify the threat, the frequency or the consequences so that the risk is reduced to intermediate or lower. For an in service pipeline the risk shall be reduced immediately |
|-------------------|---|
| High Risk | Modify the threat, the frequency or the consequences so that the risk is reduced to intermediate or lower. For an in service pipeline the risk shall be reduced as soon as possible, typically within a timescale of not more than a few weeks. |
| | Repeat the risk identification and risk evaluation process to verify and, where possible, quantify the risk estimation; determine the accuracy and uncertainty of the estimation. Where the risk rank is confirmed to be intermediate, if possible modify the threat, the frequency or the consequence to reduce the risk to low or negligible. |
| Intermediate Risk | Where the risk rank cannot be reduced to 'low' or 'negligible', action shall be taken to" remove threats, reduce frequencies and/or reduce severity of consequences to the extent practicable; and demonstrate ALARP |
| | For an in-service pipeline, the reduction to 'low' or 'negligible' or demonstration of ALARP shall be completed as soon as possible; typically within a timescale of not more than a few months. |
| Low Risk | Determine the management plan for the threat to prevent occurrence and to monitor changes which could affect the classification. |
| Negligible Risk | Review at the next review interval. |

4 ATTACHMENTS

| Reference | Title / Description |
|---------------|-----------------------------------|
| MAN-368-ATT03 | ESV-VTS Safety Case Risk Register |
| MAN-368-ATT04 | ESV-VTS Safety Case Bowties |

APA Group

5 **DEFINITIONS / ABBREVIATIONS**

| Abbreviation | Description |
|--------------|---|
| APA Group | Asset owner |
| APA VTS | APA Victoria Transmission |
| FSA | Formal Safety Assessment |
| Regulations | Gas Safety (Safety Case) Regulations 2008 |

6 **REFERENCESS**

| Abbreviation | Description |
|-------------------------------|--------------------|
| [Vic] Gas Safety (Safety Case |) Regulations 2008 |

7 REVISION HISTORY

| Revision | Date | Amendment | Author |
|----------|------------|---|-----------------------------|
| 0.1 | 20/04/1998 | Draft issue | B. W |
| 1.0 | 23/04/1998 | Initial issue | B. W |
| 2.0 | 19/08/1998 | Review of Procedure and Attachments | M. M |
| 3.0 | 20/05/2002 | Complete rewrite of procedure and attachments | M. Snell |
| 4.0 | 29/08/2003 | 2003 Review of Safety Case | M. Snell |
| 5.0 | 13/12/2005 | Changed OGS to ESV | M. Snell |
| 6.0 | 19/12/2008 | Revised Safety Case & renumbered MAN368Att02 | M. Snell |
| 7.0 | 29/05/2009 | Updated to SC Regulations 2009 | M. Snell |
| 8.0 | 20/08/2014 | Safety Case revision, update of risk register and bowties | A. Brovedani I. Shepherd |
| 8.1 | 03/06/2015 | Update following ESV submission | A.Brovedani |



Victorian Transmission System Hazard Register

Workshop Report

Generated: 03 Aug 2015 at 01:52PM +1000 by Albert Brovedani
CONFIDENTIAL

DISCLAIMER

The information contained in this document is confidential and for the use of APA and those with whom it contracts directly and must not be communicated to other persons without the prior written consent of APA. Any unauthorised use of such information may expose the user and the provider of that information to legal action.

Uncontrolled when printed.

L Facilitator Albert Brovedani L Owner Albert Brovedani **Division/Business Unit/Function** Register Location Created at Туре Workshop Transmission Victorian Pipeline Safety Case Victorian Transmission System 18/09/2013 Updated at 13/07/2015 Victorian Transmission System Hazard Register ID #12 Workshop start date 18/09/2013 Workshop Purpose/Goal Review of hazards for Pipeline Safety Case review MAN368 **Review Date (Optional)** 30/09/2018 Safety Case Formal Safety Assessment review **External Participants** Alan Burt

Workshop Risks

| | ID | Inherent Risk | Residual Risk | Target Risk | Title | Approval Status | Division/Business Unit/Function | Register | Risk Owner | Approver |
|---|------|------------------|------------------|----------------|---|--------------------|------------------------------------|---|---------------------|---------------------|
| R | 0221 | High | Interme | not rated | External interference resulting in damage to the pipeline | Approved | Infrastructure Development | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedani |
| R | 1103 | High | Interme | not rated | In-service Live welding / Hot tap & stoppling | Approved | Transmission | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedani |
| R | 1106 | High | Interme | not rated | Pipeline comissioning | Approved | Transmission | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedani |
| R | 1107 | High | Interme | not rated | Venting & flaring | Approved | Transmission Operations | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedani |
| R | 0244 | High | Low | not rated | Corrosion of steel pipeline | Approved | ECG Engineering | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedani |
| R | 1094 | High | Low | not rated | Excavation or trenching works - hazardous task | Approved | Field Services | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedani |

| R | 1086 | | | | Failure of | Approved | Transmission | Victorian | Albert | Albert |
|---|------|---------|-----|-----------|---|----------|--|---|---------------------|--------------------|
| ĸ | 1080 | High | Low | not rated | equipment or materials | Approved | TRAINSTINSSION | Pipeline Safety Case | Brovedani | Brovedan |
| R | 1093 | Interme | Low | not rated | Compressor Failure | Approved | Field Services | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedan |
| R | 1088 | Interme | Low | not rated | Physical damage to above ground infrastructure | Approved | ECG Engineering | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedan |
| R | 0243 | High | Low | not rated | Damage to pipeline caused by environmental factors | Approved | Transmission | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedan |
| R | 1084 | Interme | Low | not rated | Inadequate / Incorrect design input | Approved | Infra Construction | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedar |
| R | 1092 | Interme | Low | not rated | Pipeline leaks | Approved | Infrastructure Construct | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedan |
| R | 1091 | Interme | Low | not rated | Overpressure | Approved | Transmission Operations | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedar |
| R | 1104 | Interme | Low | not rated | Pigging Operations - hazardous task | Approved | Transmission | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedar |
| R | 1085 | Interme | Low | not rated | Legislative / regulatory change - failure to comply | Approved | Infrastructure Strategy & Engineer | Victorian Pipeline Safety Case | Albert Brovedani | Albert Brovedan |

Workshop Review Risks

No items found

Control Recommendations

No items found

👤 Risk Owner Albert Brovedani TYPE RISK ID STATE DIVISION/BUSINESS UNIT/EUNCTION REGISTER RISK REVIEW DATE Victorian Pipeline Safety Case 27/09/2019 Risk 0221 Approved Infrastructure Development CREATED AT UPDATED AT 18/09/2013 04/12/2014 External interference resulting in damage to the pipeline Inherent Residual Control Effectiveness High Intermediate 4-Satisfactory Control Effectiveness People People Target Not vet risk rated DESCRIPTION Direct contact with pipeline from external interference caused by a third party resulting in damage to the pipeline LOCATION APPROVER Victorian Transmission System Albert Brovedani Doc. Control: 193 2 items 19/19 in place controls 6 items 13/13 in place controls Causes + Preventing Controls Consequences + Mitigating Controls 11/11 in 1. Failure of pipeline due to impact, crushing, vibration, point loading, explosives place 1. Asset damage 3/3 in place 1.1 Design standards and risk assessment (safety Pipeline protection as per Safety Management 1.1 management study) Study may minimise damage i.e. wall **Cross Reference / Supporting Documents:** thickness,concrete sleeve, etc. ESD077 Design Management, AS2885.1 sec 2.3 1.2 Spare pipe ~ Safety Management Study **Cross Reference / Supporting Documents:** PIP181 Transmission Pipeline Damage Management **Comments (optional):** material specification, additional wall thickness or **Objectives:** depth in high risk area, separation distance from Availability of spare pipe may minimise outage other underground facilities, concrete slabbing, etc as per AS2885.1 1.3 In Line inspection **Cross Reference / Supporting Documents:** 1.2 Review / approval of works on easements 320-PL-AM-0006 Pipeline Integrity Management Plan; Cross Reference / Supporting Documents: 530-GD-E-0001 Corrosion Management Guide 320-PR-HEL-004 Authorised Third Party **Encroachment Management** 6/6 in place 2. Loss of supply 2.1 **Pipeline repair procedures** OV Security patrols - aerial & road / foot patrol 1.3 **Objectives: Cross Reference / Supporting Documents:** Isolation and repair of the pipeline will minimise time 320-PR-HEL-0001 Aerial Surveillance Procedure: 320-PR-HEL-0003 National Ground Patrol Procedure impact as a temporary by-pass can be constructed to ensure security of supply until a permanent repair is **Objectives:** completed Detection of unauthorised activity within pipeline easement 2.2 Spare pipe Objectives: Pipeline identification signage and hot line 1.4 Rated spare pipe kept in yard at Dandenong and is reporting readily available **Cross Reference / Supporting Documents:** 320-PL-HEL-0001 Land Management Plan 2.3 **Bushfire Management Procedure - Emergency** OV **Objectives:** response plan Signage warning of high pressure gas pipeline in the **Cross Reference / Supporting Documents:** vicinity and contact number to call for advice 320-PR-HS-0007 Bushfire Management Procedure;

Confidential

| 1.5 | Conditions of works imposed on adjacent sites | Image: A second s |
|------|---|--|
| | Cross Reference / Supporting Documents: 320-PR-HEL-0004 Authorised Third Party | |
| | Encroachment Management | |
| 1.6 | Inspector at adjacent works sites | ~ |
| | Cross Reference / Supporting Documents: PPL231 External Interference Protection - Pipelines | |
| 1.7 | Use of "one call" systems DBYD | Ø 🗸 |
| | Cross Reference / Supporting Documents: PPL231 External Interference Protection - Pipelines | |
| 1.8 | Liason with local gas, utilities, shires, contractors | Image: A start of the start of |
| | Cross Reference / Supporting Documents: PIP273 Pipeline Excavation, PPL338 Site Access Notification to AEMO & property owners / occupiers | |
| 1.9 | Work permits for APA work | ~ |
| | Cross Reference / Supporting Documents: OPS166 Safe Work Permit & Facilities Release System | ı |
| 1.10 | Stakeholder awareness program | Image: A start of the start of |
| | Cross Reference / Supporting Documents: 320-PL-HEL-0001 Land Management Plan | |
| | Objectives: Pipeline awareness for residents, Councils and | |
| | businesses within vicinity of the pipeline is a key | |
| | measure for protection of the pipeline | |
| 1.11 | reporting | C 🗸 |
| | Cross Reference / Supporting Documents: PIP300 Pipeline Marking | |
| 2. | Inaccurate or misinterpreted pipeline location 8/8 in information leading to damage to pipelines/underground assets | n place |
| 2.1 | Up to date as-built drawings | ~ |
| | Cross Reference / Supporting Documents: QUA081 Drawing control | |
| 2.2 | Accurate recording/retrieval of information | ~ |
| | Cross Reference / Supporting Documents: MAN232 Change Management | |
| 2.3 | Document control procedures | ~ |
| | Cross Reference / Supporting Documents: MAN079 Preparation & Management of Documentation | |
| 2.4 | Operating procedures / training | Image: A start of the start of |
| 2.5 | Pipeline locator equipment / proving buried assets | ~ |
| | Cross Reference / Supporting Documents: PPL231 External interference protection | |
| 2.6 | Use of "one call" systems DBYD | 0 🗸 |
| | Cross Reference / Supporting Documents: PPL231 External Interference Protection - Pipelines | |
| 2.7 | Engineering assessment of other authorities proposals | ~ |
| | Cross Reference / Supporting Documents: | |
| | PIP034 management of Transmission Pipeline Easements | |
| 2.8 | Pipeline identification signage and hot-line reporting | 0 🗸 |
| | | |

EME020 Emergency Management Manual

| | Objectives: Minimise any consequence of uncontrolled gas release | |
|-----|---|--|
| 2.4 | SCADA monitoring and pipeline control | Image: A second s |
| 2.5 | Interconnection of East Coast grid Objectives: Flexibility in making up shortfall by connection to ot sources | ✔ her |
| 2.6 | Ability to inject LNG into the grid or transport to a Objectives: Dandenong LNG facility is designed as a back up for loss of supply | Ť |
| 3. | Property damage 1/ | 1 in place |
| 3.2 | Liason with emergency services | O 🖌 |
| 4. | Injury or death 1/ Comments: Injury or death | '1 in place |
| 4.2 | Liason with emergency services | Ø 🖌 |
| 5. | Regulatory breach1/Comments: Could result in prosecutions againstthe company / staff and / or fines if safety case orstandards not observed | '1 in place |
| 5.1 | Management system - which includes Policy, procedures, maintenance system, pipeline surveillance systems, 5 yearly safety managemen study, liaison in relation to land use changes and developments, emergency response procedures, safety systems | 1 |
| 6. | Environmental consequence of potential 1/ bushfire | '1 in place |
| 6.1 | Environmental Management Plan & Environmental procedures Cross Reference / Supporting Documents: Bushfire Management Procedure; EME-020 Emergency Response Procedure; MAN-368 Att 03 Environmental Risk Register | I Ø 🗸 |

Cross Reference / Supporting Documents: PIP300 Pipeline Marking

Actions

| No items | found | |
|----------|-------|--|
|----------|-------|--|

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

| ID | Comment/Note | Owner | Created at |
|------|--|------------------|-------------------------|
| 1 | Demonstration of ALARP What else could we do to reduce the risk? Create greater separation of the pipeline from physical interference by; 1. Concrete slab the entire length of VTS pipelines 1,995 km 2. Place physical barriers (fences) on the entire length of the easement 3. Maintain a buffer zone keeping buildings and activities free from the radiation zone of the pipeline along the length of the easement | Albert Brovedani | 03/Jun/2015 16:32 PM |
| | Why have we not done it? 1. It is impractical to slab the entire length of pipelines, it is too costly, and is not a common practice amongst pipeline companies. High risk areas have appropriate physical protections in place which are constantly reviewed via SMS 2. APA does not have rights to place a fence along the length of the easement, the cost would be too great and it could possibly cause maintenance issues. 3. Impractical as there is no legislative basis for doing so. Planning decisions are often made without consultation of the pipeline owner nor without any consideration of the pipeline | | |
| | The cost of the above solutions outweighs the benefit as the pipeline threats are thoroughly analysed during the 5 yearly Safety Management Study for non-location and location specific threats along the entire length of each pipeline. Extra protection is considered specifically where required. | | |
| Atta | chments | | |

| ^{YPE} lisk | RISK ID 1106 | STATE Approved | division/business | | REGISTER Victoria | n Pipeline Safety Case | RISK REVIEW DATE 30/11/2019 | |
|-------------------------------|---|---|---|--|----------------------|--|--|------------------------------|
| | TED AT 07/2014 | UPDATED AT 02/07/2015 | | | | | | |
| Pip | oeline co | omissioning | | | | | | |
| | | | | Inherent | | Residual | Control Effectiven | |
| | | | | Hi | - | Intermediate | 4-Satisfact | - |
| | | | | Peo | pie | People | Control Effectiv | veness |
| | | | | Target | | | | |
| | | | | Not yet r | isk rated | | | |
| ESCI | RIPTION | | | | | | | |
| | | ease - Introducing | as into the nine | line and press | urisina the | pipeline to the Transmissio | n Pipeline System Or | perating |
| | sure | | | | unsing the | | n ipeline System op | Crucing |
| | | | | | | | | |
| | тюм prian Transmi | | ROVER ert Brovedani | | | | | |
| | | ISSION System Alt | ert brovedani | | | | | |
| isk : ctiv | STATUS Ve | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | Doc. Contro |
| | | nting Controls | | in place controls | | Sequences + Mitigating Co Damage to people or prop | | n place contr |
| | Pipeline ru poor quali | nting Controls Ipture during comm ty pipe or weakend ing of pipeline sect | nissioning due te ed joints | | Cons | Sequences + Mitigating Co Damage to people or prop from gas release Site specific emergency p | ontrols perty due to ignition | |
| | Pipeline ru poor quali Hydrotesti constructio | ipture during comm ty pipe or weakend ing of pipeline sect on | nissioning due te ed joints | o 1/1 in place | Cons | Damage to people or prop from gas release | ontrols perty due to ignition rocedures from | n place contr |
| • | Pipeline ru poor quali Hydrotesti constructio Objectives | ipture during comm ty pipe or weakend ing of pipeline sect on : | nissioning due te ed joints ions during | o 1/1 in place | Cons | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan | ontrols perty due to ignition rocedures from | n place contr |
| | Pipeline ru poor quali Hydrotesti constructio Objectives | ipture during comm ty pipe or weakend ing of pipeline sect on | nissioning due te ed joints ions during | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: | ontrols perty due to ignition rocedures from agement Plan | n place contr 2/2 in plac |
| | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments | upture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and wel (optional): | hissioning due t a ad joints ions during ds under design | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |
| • | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments Job specific | upture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and wel (optional): c testing of welds a | hissioning due to ad joints ions during ds under design nd hydro tests fo | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| • | Pipeline ru poor quali Hydrotesti constructio Objectives Test strempressure Comments Job specific and field fa | upture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and wel (optional): | hissioning due t ed joints ions during ds under design and hydro tests for hold point prior to | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments Job specific and field fa consent to | ing of pipe or weakend ing of pipeline sect on : gth of pipe and wel (optional): c testing of welds a brication. This is a l | hissioning due t id joints ions during ds under design and hydro tests for hold point prior to sets | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments Job specific and field fa consent to | ipture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and wel (optional): c testing of welds a brication. This is a l | hissioning due t id joints ions during ds under design and hydro tests for hold point prior to sets | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments Job specific and field fa consent to incomplete & fittings Comments | ipture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and wel (optional): t testing of welds a brication. This is a l operate on VTS as e installation of eq : may cause a gas es | nissioning due to ed joints ions during ds under design nd hydro tests fo hold point prior to sets uipment, valves | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strempressure Comments Job specific and field fa consent to incomplete & fittings Comments ignite during | apture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and well (optional): t testing of welds a brication. This is a l o operate on VTS as e installation of eq : may cause a gas es g commissioning | hissioning due to dioints ions during ds under design ad hydro tests for hold point prior to sets uipment, valves scape that may | 1/1 in place shop 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strempressure Comments Job specific and field fa consent to incomplete & fittings Comments ignite during | Ipture during comm ty pipe or weakend ing of pipeline sectors on : gth of pipe and well (optional): testing of welds a brication. This is a l operate on VTS as e installation of eq : may cause a gas eg g commissioning ssioning procedure | hissioning due to dioints ions during ds under design ad hydro tests for hold point prior to sets uipment, valves scape that may | o 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strempressure Comments Job specific and field fa consent to incomplete & fittings Comments ignite during Pre-commi Objectives Check all fit | apture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and well (optional): t testing of welds a brication. This is a l operate on VTS as is installation of eq : may cause a gas es g commissioning ssioning procedure : ttings, valves & and | hissioning due to digints ions during ds under design and hydro tests for hold point prior to sets uipment, valves scape that may e | 1/1 in place shop 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strempressure Comments Job specific and field fa consent to incomplete & fittings Comments ignite during Pre-commi Objectives Check all fit correctly in | apture during comm ty pipe or weakend ing of pipeline sect on : gth of pipe and well (optional): t testing of welds a brication. This is a l operate on VTS as is installation of eq : may cause a gas es g commissioning ssioning procedure : ttings, valves & and istalled and all end | hissioning due to digints ions during ds under design and hydro tests for hold point prior to sets uipment, valves scape that may e | 1/1 in place shop 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |
| aus | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments Job specific and field fa consent to Consent to Comments ignite during Pre-commi Objectives Check all fi correctly in with flange | Inpture during comments ty pipe or weakened ing of pipeline sectors ing of pipeline sectors ing of pipe and well (optional): c testing of welds a brication. This is a l o operate on VTS as a installation of eq : may cause a gas en g commissioning ssioning procedure : ttings, valves & and isstalled and all end s, caps, or plugs | hissioning due to digints ions during ds under design and hydro tests for hold point prior to sets uipment, valves scape that may e | 1/1 in place shop 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |
| 1 | Pipeline ru poor quali Hydrotest constructio Objectives Test strend pressure Comments Job specific and field fat consent to incomplete & fittings Comments ignite durind pre-commit Objectives Check all fit correctly in with flange | Inpture during comments ing of pipe or weakened ing of pipeline sectors ing of pipe and well (optional): testing of welds a brication. This is a lo operate on VTS as operate on VTS as installation of eq ssioning procedure istalled and all end s, caps, or plugs (optional): | hissioning due to digints ions during ds under design hd hydro tests for hold point prior to sets uipment, valves scape that may e iillary equipment points are comp | 1/1 in place shop 1/1 in place 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |
| .1 | Pipeline ru poor quali Hydrotest constructio Objectives Test strend pressure Comments Job specific and field fa consent to Consent to Comments ignite during Pre-commi Objectives Check all fi correctly in with flange Pre-commi | Inpture during comments ty pipe or weakened ing of pipeline sectors ing of pipeline sectors ing of pipe and well (optional): c testing of welds a brication. This is a l o operate on VTS as a installation of eq : may cause a gas en g commissioning ssioning procedure : ttings, valves & and isstalled and all end s, caps, or plugs | hissioning due to digints ions during ds under design hd hydro tests for hold point prior to sets uipment, valves scape that may e iillary equipment points are comp | 1/1 in place shop 1/1 in place 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| .1 | Pipeline ru poor quali Hydrotest constructio Objectives Test strend pressure Comments Job specific and field fa consent to Consent to Comments ignite during Pre-commi Objectives Check all fi correctly in with flange Pre-commi | Inpture during comments ing of pipe or weakened ing of pipeline sectors if the sectors if | hissioning due to digints ions during ds under design hd hydro tests for hold point prior to sets uipment, valves scape that may e iillary equipment points are comp | 1/1 in place shop 1/1 in place 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr |
| .1 | Pipeline ru poor quali Hydrotesti constructio Objectives Test strend pressure Comments Job specific and field fa consent to incomplete & fittings Comments ignite during Dijectives Check all fi correctly in with flange Pre-commi requireme Manageme | Inpture during comments ing of pipe or weakened ing of pipeline sectors if the sectors if | hissioning due to digints ions during ds under design hd hydro tests for hold point prior to sets uipment, valves scape that may e iillary equipment points are comp | 1/1 in place shop 1/1 in place 1/1 in place | Cons 1. 1.1 | Damage to people or prop from gas release Site specific emergency p Construction Safety Mana Pipeline isolation plan Objectives: Limit the amount of gas flo | ontrols perty due to ignition rocedures from agement Plan wing through that se | n place contr 2/2 in plac |

_ .

| 3.1 | Work instructions | ~ |
|-----|--|---|
| 3.2 | Ensure valves are labelled correctly | Image: A set of the set of the |
| | Cross Reference / Supporting Documents: VLV387 Valve Numbering System | |
| 3.3 | Utilise tagging and isolation procedures | ✓ |
| 4. | Exposure to confined space hazards Comments: Exposure to gas and lack of oxygen during valve operations in a valve pit | 2/2 in place |
| 4.1 | Confined space entry procedure | ✓ |
| 4.2 | Utilise PPE and gas & oxygen analyser | Image: A start of the start of |

Actions

| No it | ems | found | |
|-------|-----|-------|--|
|-------|-----|-------|--|

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

| ID | Comment/Note | Owner | Created at |
|------|--|------------------|-------------------------|
| 1 | Demonstration of ALARP; What else could we do to reduce the risk? No alternative mitigation available when commissioning, pipeline must be pressurised. All testing and safety considerations within best industry practice are followed. Specific commissioning plans are developed upon best engineering technical knowledge including referencing field operations staff who have intimate knowledge of the pipeline system. | Albert Brovedani | 02/Jul/2015 11:33 AM |
| ۸++- | Why have we not done it? Introducing pressurised gas into a pipeline always provides an element of risk, the likelihood is contained to a very low level however the consequence cannot be minimised any further. | | |
| Alla | criments | | |

| TYPE Risł | RISK ID 1103 | state Approve | | ION/BUSINESS | UNIT/FUNCTION n | register Victoria | an Pipeline Safety Case | RISK REVIEW DATE 27/09/2019 | |
|--------------|---|--|--|--|---|--------------------------------|---|--|--|
| | тед ат 07/2014 | UPDATED AT 02/07/2015 | | | | | | | |
| ln- | service | Live weldiı | ng / Ho | t tap & | stopplir، | ng | | | |
| | | | | | Inherent | | Residual | Control Effectiv | veness |
| | | | | | | ligh | Intermediate | 4-Satisfa | |
| | | | | | Pe | ople | People | Control Effe | ctiveness |
| | | | | | Target | | | | |
| | | | | | Not yet | risk rated | | | |
| DESC | RIPTION | | | | | | | | |
| | | tu controlo wa | uld be ene | cific to ind | iuidu al tack p | orformod b | v a ana cialist contractor | | |
| iaz | ardous activ | ity - controis wo | uid be spe | cific to ind | ividual task p | errormed b | y a specialist contractor | | |
| OCA | TION | | APPROVER | | | | | | |
| /icto | orian Transmi | ssion System | Albert Broy | /edani | | | | | |
| | STATUS | | | | | | | | |
| \cti | ve | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | Doc. Control |
| | | | 1 ite | ums 7/7 ir | nlace contro | | | 2 items 3/3 | |
| au | Ses + Preve | nting Controls | 1 ite | ms 7/7 ir | n place contro | | SEQUENCES + Mitigating | | |
| | Weld hot t Comments | ap fitting onto : Exposure to gas | pipeline if pipeline | is | n place contro 7/7 in place | Cor | ISEQUENCES + Mitigating Damage to people or pi gas during task | Controls | 3 in place contro |
| | Weld hot t Comments penetrated | ap fitting onto | pipeline if pipeline nition of gas | is s gas | - | Cor | Damage to people or pr gas during task Project specific emerge | Controls roperty if ignition of ancy procedures deve | in place contro |
| | Weld hot t Comments penetrated present from due to cont | ap fitting onto : Exposure to gas during hot tap Ig n existing valves i act with hot meta | pipeline if pipeline nition of gas n near vicin I, heat & sp | is 5 gas ity. Burns Þarks Fire | | Cor 1. | Damage to people or pi gas during task | Controls roperty if ignition of ancy procedures deve | in place contro |
| | Weld hot t Comments penetrated present from due to cont | ap fitting onto : Exposure to gas during hot tap Ig n existing valves i | pipeline if pipeline nition of gas n near vicin I, heat & sp | is 5 gas ity. Burns Þarks Fire | | Cor 1. | Damage to people or pr gas during task Project specific emerge as part of Construction Objectives: Minimise consequences | Controls roperty if ignition of ncy procedures deve Management plan | in place contro 1/1 in plac eloped |
| | Weld hot t Comments penetrated present from due to cont caused by v trench. Specialist | ap fitting onto : Exposure to gas during hot tap Ig m existing valves i act with hot meta velding or grinding hot tap firm use | pipeline i if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this | is 5 gas ity. Burns barks Fire ollapse of task | | Cor 1. | Damage to people or pr gas during task Project specific emerge as part of Construction Objectives: | Controls roperty if ignition of ncy procedures deve Management plan | in place contro 1/1 in plac eloped |
| ι. | Weld hot t Comments penetrated present fror due to cont caused by v trench. Specialist Cross Refe | ap fitting onto : Exposure to gas during hot tap Ig m existing valves i act with hot meta velding or grinding hot tap firm use rence / Support | pipeline i if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this cing Docum | is s gas ity. Burns barks Fire ollapse of task hents: | 7/7 in place | Cor 1. | Damage to people or pr gas during task Project specific emerge as part of Construction Objectives: Minimise consequences | Controls roperty if ignition of mcy procedures deve Management plan s to surrounding peo | in place contro 1/1 in place eloped Øv ple and |
| ι. | Weld hot t Comments penetrated present from due to cont caused by v trench. Specialist Cross Refe Job specific | ap fitting onto : Exposure to gas during hot tap Ig n existing valves i act with hot meta velding or grinding hot tap firm use procedure dev | pipeline i if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this cing Docum | is s gas ity. Burns barks Fire ollapse of task hents: | 7/7 in place | Cor 1. 1.1 | Damage to people or pr gas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment | Controls roperty if ignition of ency procedures deve Management plan is to surrounding peo- inding sparks | in place contro 1/1 in place eloped $O \sim$ ple and 2/2 in place |
| ι. | Weld hot t Comments penetrated present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives | ap fitting onto : Exposure to gas during hot tap Ig n existing valves i act with hot meta velding or grinding hot tap firm use procedure dev | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co d for this cing Docun eloped wh | is s gas ity. Burns aarks Fire illapse of task hents: en requrie | 7/7 in place | Cor 1. 1.1 | Damage to people or prigas during taskProject specific emerge as part of ConstructionObjectives: Minimise consequences environmentFire from welding or gri Project specific emerge as part of Construction | Controls roperty if ignition of ency procedures deve Management plan s to surrounding peo- inding sparks ency procedures deve | in place contro 1/1 in place eloped Ø v ple and 2/2 in place |
| ι. | Weld hot t Comments penetrated present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives | ap fitting onto : Exposure to gas during hot tap Ig m existing valves if act with hot meta velding or grinding hot tap firm use rence / Support procedure dev : nson, Furmanite | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co d for this cing Docun eloped wh | is s gas ity. Burns aarks Fire illapse of task hents: en requrie | 7/7 in place | Cor 1. 1.1 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: | Controls roperty if ignition of ency procedures deve Management plan s to surrounding peo inding sparks ency procedures deve Management plan | in place contro 1/1 in place eloped Ø ple and 2/2 in place eloped Ø |
| 1 | Weld hot t Comments penetrated present fror due to cont caused by v trench. Specialist Cross Refe Job specific Objectives T.D. William be used for | ap fitting onto : Exposure to gas during hot tap Ig n existing valves if act with hot meta velding or grinding hot tap firm use procedure dev : nson, Furmanite r this task | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this cing Docum eloped wh or anothe | is s gas ity. Burns aarks Fire illapse of task tents: en requrie r specialist | 7/7 in place | Cor 1. 1.1 2. 2.1 | Damage to people or prigas during taskProject specific emerge as part of ConstructionObjectives: Minimise consequences environmentFire from welding or gri Project specific emerge as part of Construction | Controls roperty if ignition of ency procedures deve Management plan s to surrounding peo inding sparks ency procedures deve Management plan | in place contro 1/1 in place eloped |
| 1 | Weld hot t Comments penetrated present fror due to cont caused by v trench. Specialist Cross Refe Job specific Objectives T.D. William be used for | ap fitting onto : Exposure to gas during hot tap Ig m existing valves in act with hot meta velding or grinding hot tap firm use rence / Support procedure dev : nson, Furmanite r this task hot tap machine | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this cing Docum eloped wh or anothe | is s gas ity. Burns aarks Fire illapse of task tents: en requrie r specialist | 7/7 in place | Cor 1. 1.1 2. 2.1 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment | Controls roperty if ignition of ency procedures deve Management plan s to surrounding peo inding sparks ency procedures deve Management plan | in place contro 1/1 in place eloped \mathcal{O} ple and 2/2 in place eloped \mathcal{O} |
| .1 | Weld hot t Comments penetrated present from due to cont caused by v trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives | ap fitting onto : Exposure to gas during hot tap Ig m existing valves in act with hot meta velding or grinding hot tap firm use rence / Support c procedure dev : nson, Furmanite r this task hot tap machine : | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co d for this cing Docum eloped wh or anothe | is s gas ity. Burns aarks Fire illapse of task hents: en requrie r specialist h stopplin | 7/7 in place | Cor 1. 1.1 2. 2.1 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or grider of Construction Objectives: Minimise consequences environment Fire from welding or grider of Construction Objectives: Minimise consequences environment Stopple | Controls roperty if ignition of ency procedures deve Management plan s to surrounding peo inding sparks ency procedures deve Management plan | in place contro 1/1 in place eloped |
| 1 | Weld hot t Comments penetrated present from due to cont caused by v trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives | ap fitting onto : Exposure to gas during hot tap Ig n existing valves if act with hot meta velding or grinding hot tap firm use procedure dev : nson, Furmanite r this task hot tap maching 10 | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co d for this cing Docum eloped wh or anothe | is s gas ity. Burns aarks Fire illapse of task hents: en requrie r specialist h stopplin | 7/7 in place | Cor 1. 1.1 2. 2.1 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i | Controls roperty if ignition of incy procedures deve Management plan is to surrounding peo inding sparks incy procedures deve Management plan is to surrounding peo into the section of pig | in place contro 1/1 in place eloped |
| 1 | Weld hot t Comments present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives Isolation from | ap fitting onto : Exposure to gas during hot tap Ig m existing valves in act with hot meta velding or grinding hot tap firm use rence / Support c procedure dev : nson, Furmanite r this task hot tap machine : om gas source of rocedures, welc | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this ing Docum eloped wh or anothe e used wit luring hot lers and w | is s gas ity. Burns varks Fire illapse of task nents: en requrie r specialist h stopplin tap | 7/7 in place ed t firm to g of | Cor 1. 1.1 2.1 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i remove ignition source as part of construction | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | in place contro 1/1 in place eloped |
| au: 1 | Weld hot t Comments present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives Isolation from | ap fitting onto : Exposure to gas during hot tap Ig m existing valves in act with hot meta velding or grinding hot tap firm use procedure dev : nson, Furmanite r this task hot tap machine : om gas source of | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ed for this ing Docum eloped wh or anothe e used wit luring hot lers and w | is s gas ity. Burns varks Fire illapse of task nents: en requrie r specialist h stopplin tap | 7/7 in place ed t firm to g of | Cor 1. 1.1 2.1 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | eloped of and 2/2 in place eloped of a ple and ve to |
| 1 | Weld hot t Comments penetrated present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives Isolation from Welding pur record must works | ap fitting onto : Exposure to gas during hot tap Ign n existing valves in act with hot meta welding or grinding hot tap firm use rence / Support : procedure dev : nson, Furmanite r this task hot tap maching te pom gas source of rocedures, weld st be provided t | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ad for this ting Docun eloped wh or anothe a used wit luring hot lers and w o ESV for a | is s gas ity. Burns aarks Fire ollapse of task hents: en requrie r specialist h stopplin tap eld qualif | 7/7 in place ed t firm to g of ication | Cor 1. 1.1 2.1 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i remove ignition source as part of construction | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | in place contro 1/1 in place eloped |
| 1 | Weld hot t Comments penetrated present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives I.D. William be used for Specialist gas pipelin Objectives Isolation from Welding pur record must works Objectives Ensure we | ap fitting onto : Exposure to gas during hot tap Ig m existing valves in act with hot meta velding or grinding hot tap firm use rence / Support c procedure dev : nson, Furmanite r this task hot tap machine : com gas source of rocedures, welcond st be provided to | pipeline if pipeline nition of ga: n near vicin l, heat & sp g sparks. Co ad for this ting Docun eloped wh or anothe a used wit luring hot lers and w o ESV for a | is s gas ity. Burns aarks Fire ollapse of task hents: en requrie r specialist h stopplin tap eld qualif approval p | 7/7 in place ed t firm to g of ication | Cor 1. 1.1 2.1 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i remove ignition source as part of construction | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | in place contro 1/1 in place eloped |
| 1 | Weld hot t Comments penetrated present fror due to cont caused by v trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives Isolation fro Welding purecord must works Objectives Ensure we and qualific | ap fitting onto : Exposure to gas during hot tap Ig m existing valves in act with hot meta velding or grinding hot tap firm use rence / Support : procedure dev : nson, Furmanite r this task hot tap maching : procedures, welc st be provided t : Iding safety. Spe cations applied t | pipeline if pipeline nition of gas n near vicin l, heat & sp g sparks. Co ad for this cing Docun eloped wh or anothe a used wit luring hot lers and w o ESV for a co each job | is s gas ity. Burns aarks Fire ollapse of task nents: en requrie r specialist h stopplin tap eld qualif approval p | 7/7 in place ed t firm to g of ication irior to edure | Cor 1. 1.1 2. 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i remove ignition source as part of construction | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | in place contro 1/1 in place eloped |
| 1 | Weld hot t Comments penetrated present from due to cont caused by w trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives Isolation from Welding pur record must works Objectives Ensure we and qualific | ap fitting onto : Exposure to gas during hot tap Ign n existing valves in act with hot meta welding or grinding hot tap firm use rence / Support : procedure dev : nson, Furmanite r this task hot tap maching te pom gas source of rocedures, weld st be provided t : Iding safety. Spe | pipeline if pipeline if pipeline intion of ga: n near vicin l, heat & sp g sparks. Co ed for this ting Docun eloped wh or anothe e used wit during hot lers and w o ESV for a ecific job re o each job | is s gas ity. Burns aarks Fire ollapse of task hents: en requrie r specialist h stopplin tap eld qualif approval p lated proc | 7/7 in place ed t firm to g of ication | Cor 1. 1.1 2. 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i remove ignition source as part of construction | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | in place contro 1/1 in place eloped |
| .1 | Weld hot t Comments penetrated present from due to cont caused by welch trench. Specialist Cross Refe Job specific Objectives T.D. William be used for Specialist gas pipelin Objectives Isolation from Welding pur record must works Objectives Ensure we and qualific Approved for Objectives | ap fitting onto : Exposure to gas during hot tap Ign n existing valves in act with hot meta welding or grinding hot tap firm use rence / Support : procedure dev : nson, Furmanite r this task hot tap maching : pom gas source of rocedures, weld st be provided t : Iding safety. Spe cations applied t | pipeline if pipeline nition of gas l, heat & sp g sparks. Co ed for this ting Docun eloped wh or anothe or anothe during hot lers and w o ESV for a ecific job re o each job | is s gas ity. Burns aarks Fire ollapse of task hents: en requrie r specialist h stopplin tap eld qualif approval p lated proc | 7/7 in place ed t firm to g of ication irior to edure | Cor 1. 1.1 2. 2.2 | Damage to people or prigas during task Project specific emerge as part of Construction Objectives: Minimise consequences environment Fire from welding or gri Project specific emerge as part of Construction Objectives: Minimise consequences environment Stopple Objectives: Restrict the flow of gas i remove ignition source as part of construction | Controls roperty if ignition of Ency procedures deve Management plan is to surrounding peo- inding sparks Ency procedures deve Management plan is to surrounding peo- into the section of pig- and provide isolation | in place contro 1/1 in place eloped |

isolated during activity Objectives: Reduce potential for large volume of gas to light 1.6 Trenching and shoring procedure Objectives: Job specific procedure would be provided as part of Construction Management Plan

1.7 Safe Work Procedures, risk assessment and qualified Permit issuing Officer required for task Cross Reference / Supporting Documents: JHA, Permit to Work, SWMS

Objectives:

Ensure the job is done specific to the conditions and resources available on the day

Actions

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

| What more can be done to reduce the risk? 1. Elimination of the task would be the safest option 2. Purge gas from the section of pipeline being hot-tapped at each closest valve location Why has it not been done? 1. This is not possible as connection onto existing pipelines need to be made from time to time. | ert Brovedani | 02/Jul/2015 11:28 AM |
|--|---------------|-------------------------|
| Interruption of gas supply not practical and stoppling is a proven effective measure of keeping a small section of pipeline as gas free whilst the tap and fittings are made No further mitigation available | | |

 \checkmark

 \checkmark

Attachments

| Risk 1107 | | DIVISION/BUSINESS U Transmission | | REGISTE Victo | R rian Pipeline Safety Case | RISK REVIEW DATI 29/11/2019 | - |
|---|--|--|---|------------------|---|---|--|
| REATED AT 3 0/07/2014 | UPDATED AT 13/07/2015 | | | | | | |
| /enting & | k flaring | | | | | | |
| | | | Inherent High | | Residual Intermediate | Control Effective | |
| | | | People | , , | People | Control Effect | - |
| | | | Target | | | | |
| | | | Not yet risk | rated | | | |
| FCONDELON | | | | | | | |
| ESCRIPTION | k controlled releases | oface | | | | | |
| iazardous tas | k - controlled release | orgas | | | | | |
| | | ROVER | | | | | |
| | nission System Alb | ert Brovedani | | | | | |
| isk status Active | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | Doc. Control |
| auses + Prev | enting Controls | 2 items 8/8 in | n place controls | Cons | equences + Mitigating Contr | 1 items 1/1 rols | |
| . Mechanic to incorre | renting Controls cal failure of flare, fit ect design for Maxim g Pressure | tings, hose due | n place controls 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosio | rols al injury from n | in place contr |
| . Mechanic to incorre Operatin | cal failure of flare, fit ect design for Maxim | tings, hose due um Allowable | 5/5 in place | | Property damage or persona | rols al injury from n | in place contr |
| . Mechanic to incorr Operatin .1 Visual ins | cal failure of flare, fit ect design for Maxim g Pressure | tings, hose due um Allowable s, hoses & conne | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorre Operatin 1 Visual ins 2 Only app | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting | tings, hose due um Allowable s, hoses & conne nall be used | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosio Emergency response and pip procedures | rols al injury from n peline isolation | in place contr |
| Mechanic to incorr Operatin 1 Visual in: 2 Only app 3 Notify fir activity | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl | tings, hose due um Allowable s, hoses & conne nall be used | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contro |
| Mechanic to incorr Operatin Visual ins 2 Only app 3 Notify fin activity .4 Training | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe | tings, hose due um Allowable s, hoses & conne nall be used | 5/5 in place ections v s of v | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | Doc. Control in place contro 1/1 in plac |
| Mechanic to incorr Operatin Visual ins 2 Only app 3 Notify fir activity 4 Training 5 Permit to Objective | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators o work, JHA & SWMS es: | tings, hose due um Allowable s, hoses & conne nall be used r relevant partie: | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contro |
| Mechanic to incorr Operatin Visual ins 2 Only app 3 Notify fin activity 4 Training 5 Permit to Objective Ensure a | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators o work, JHA & SWMS es: controlled environme | tings, hose due um Allowable s, hoses & conne nall be used r relevant parties ent with competer | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorr Operatin Visual ins 2 Only app 3 Notify fin activity 4 Training 5 Permit to Objective Ensure a | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators o work, JHA & SWMS es: | tings, hose due um Allowable s, hoses & conne nall be used r relevant parties ent with competer | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorr Operatin Visual ins Only app Notify fir activity Training Permit to Objective Ensure a operators Flare off | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators work, JHA & SWMS es: controlled environme s according to approv | tings, hose due um Allowable s, hoses & conne nall be used r relevant parties ent with competen red procedures ghting, fire from | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorr Operatin Visual ins Only app Notify fir activity Training Permit to Objective Ensure a operators Flare off gas leaks | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators o work, JHA & SWMS es: controlled environme s according to approv gas - burns during lic | tings, hose due um Allowable s, hoses & conne hall be used r relevant parties ent with competer red procedures ghting, fire from ssive noise | 5/5 in place | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorr Operatin Visual ins Only app Notify fir activity Training Permit to Objective Ensure a operators Flare off gas leaks De-press Objective check co | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators work, JHA & SWMS es: controlled environme s according to approv gas - burns during lie s on flare hose, exce surise / flaring proces es: nnections, use of pilo le combustion and ac | tings, hose due um Allowable s, hoses & conne hall be used r relevant parties ent with competer red procedures ghting, fire from ssive noise lure ot light, continue f | 5/5 in place ections s of s of | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorre Operatin Visual ins Only app Notify fir activity Training Permit to Objective Ensure a operators Flare off gas leaks De-press Objective check co until stab been cor | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators work, JHA & SWMS es: controlled environme s according to approv gas - burns during lie s on flare hose, exce surise / flaring proces es: nnections, use of pilo le combustion and ac | tings, hose due um Allowable s, hoses & conne hall be used r relevant parties ent with competer red procedures ghting, fire from ssive noise lure ot light, continue f | 5/5 in place ections s of s of | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place contr |
| Mechanic to incorre Operatin Visual inst Operatin Visual inst Only app Notify fir activity Training Permit to Objective Ensure a operators Flare off gas leaks De-press Objective check co until stab been cor 2.2 PPE / heat | cal failure of flare, fit ect design for Maxim g Pressure spection of all fitting roved purge stack sl e authority and othe of operators work, JHA & SWMS es: controlled environme s according to approv gas - burns during li s on flare hose, exce surise / flaring proced es: nnections, use of pild le combustion and ac mpleted. | tings, hose due um Allowable s, hoses & conne hall be used r relevant parties ent with competer red procedures ghting, fire from ssive noise fure ot light, continue f dequate purge ha | 5/5 in place ections s of nt 3/3 in place flaring as | 1. | Property damage or persona uncontrolled fire or explosion Emergency response and pip procedures Objectives: | rols al injury from n peline isolation | in place cor |

Actions

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

| ID | Comment/Note | Owner | Created at |
|------|--|------------------|-------------------------|
| 1 | Demonstration of ALARP; What else could have been done to reduce the risk? Elimination of task. | Albert Brovedani | 02/Jul/2015 11:34 AM |
| | Why have we not done it? Venting / flaring is only performed where necessary or in an emergency situation. At times a gas free environment is required for maintenance or alterations to pipe work and facilities. | | |
| | No further mitigation is available. | | |
| Atta | achments | | |

| YPE Risl | RISK ID 0244 | state Approved | DIVISION/BUSINESS | - | register Victoriar | Pipeline Safety Case | RISK REVIEW DATE 30/09/2018 | |
|--------------------|--|--|--|----------------------------------|---------------------------------|---|---|--|
| | TED AT 02/2014 | UPDATED AT 04/12/2014 | | | | | | |
| Co | rrosion | of steel pipe | ine | | | | | |
| | | | | Inherent | | Residual | Control Effectiven | |
| | | | | Hig | - | Low | 4-Satisfact | |
| | | | | Peo | ple | People | Control Effection | veness |
| | | | | Target | | | | |
| | | | | Not yet r | isk rated | | | |
| ECC | RIPTION | | | | | | | |
| | | a to motal less and | noccible less of | containmant | | | | |
| | | ng to metal loss and PI -AM0006 - Pipelir | • | | ontains info | rmation on management o | of corrosion | |
| | | | | | | | | |
| | TION | | ROVER | | | | | |
| ICT | orian Transm | ission System Alb | ert Brovedani | | | | | |
| | | | | | | | | |
| | | | | | | | | Doc. Control: |
| | | | | | | | | |
| | External c | enting Controls oating damage | items 19/19 i | n place controls 8/8 in place | Cons | equences + Mitigating Co Safety of people | | |
| • | External control of the control of t | enting Controls oating damage S Damage to coating be exposed to soil an lements | may cause steel | 8/8 in place | Cons | • | ontrols rce during loss of ignition and fire / heat | |
| • | External of Comments pipeline to corrosive el External P Objectives Provide ro | enting Controls oating damage s: Damage to coating be exposed to soil an lements ipeline Coating | may cause steel d possible oating quality to | 8/8 in place | Cons 1. | Safety of people Comments: An ignition sour containment could result in it radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accour | 2/2 in plac and ht the |
| .1 | External c Comments pipeline to corrosive el External P Objectives Provide ro adequatel factors | enting Controls oating damage Damage to coating be exposed to soil an lements ipeline Coating : bust and resistant co | may cause steel d possible oating quality to om environmenta | 8/8 in place | Cons 1. | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposure surrounding environment | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accour | 2/2 in plac and at the |
| .1 | External c Comments pipeline to corrosive el External P Objectives Provide ro adequatel factors 10 yearly o only) Cross Refe | enting Controls oating damage Damage to coating be exposed to soil an lements ipeline Coating : bust and resistant c y protect the pipe fr | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: | 8/8 in place | L.1 | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requistructures within 3 to 6 m | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accourt es of a pipeline failure ed within easements hire licensee approva- metres of a pipeline. | 2/2 in plac and it the event if for the |
| .1 | External c Comments pipeline to corrosive el External P Objectives Provide rol adequately factors 10 yearly o only) Cross Refe | enting Controls oating damage :: Damage to coating be exposed to soil an lements ipeline Coating :: bust and resistant c y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les | 8/8 in place | L.1 | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requistructures within 3 to 6 m | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accour t es of a pipeline failure ad within easements ire licensee approva- netres of a pipeline. | 2/2 in plac and at the event |
| .1 | External c Comments pipeline to corrosive el External P Objectives Provide rol adequately factors 10 yearly o only) Cross Refe OPS509 M Pipeline in Objectives High tech | enting Controls oating damage s: Damage to coating be exposed to soil an lements ipeline Coating s: bust and resistant c y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu hspections - intellig | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les ent pigging sed to accurately | 8/8 in place | Cons 1. 1.1 1.2 | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requistructures within 3 to 6 m | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accourt es of a pipeline failure ad within easements hire licensee approva- netres of a pipeline. 1 nsee and ministerial ithin 3 metres of a p place to reduce ne incident | 2/2 in plac and at the event |
| .1 | External c Comments pipeline to corrosive el External P Objectives Provide roi adequately factors 10 yearly o only) Cross Refe OPS509 M Pipeline in Objectives High tech location of rates | enting Controls oating damage Damage to coating be exposed to soil an lements ipeline Coating bust and resistant of y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu hspections - intellig coata tool which is us | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les ent pigging sed to accurately | 8/8 in place | Cons 1. 1.1 1.2 | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requires structures within 3 to 6 m Pipeline Act requires licer approval for structures with consequences of a pipelin Objectives: Separation from housing a Property damage | ontrols rce during loss of ignition and fire / heat to people within the ent study provides ed on location class re taking into accourt es of a pipeline failure ad within easements hire licensee approva hetres of a pipeline nsee and ministerial within 3 metres of a p place to reduce ne incident | 2/2 in plac and at the event |
| .1 | External c Comments pipeline to corrosive el External P Objectives Provide roi adequately factors 10 yearly OPS509 M Pipeline in Objectives High tech location of rates Cathodic p Objectives Electrical c structure f | enting Controls oating damage s: Damage to coating be exposed to soil an lements ipeline Coating s: bust and resistant of y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu hspections - intellig s: data tool which is us pipe metal loss and protection systems s: current provides pro from corrosive element | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les ent pigging sed to accurately I track deterioration | 8/8 in place | Cons 1. 1.1 1.2 | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requistructures within 3 to 6 m Pipeline Act requires licent approval for structures with consequences of a pipeline Objectives: Separation from housing a | ontrols rcc during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accourt tess of a pipeline failure ad within easements hire licensee approva- netres of a pipeline. I insee and ministerial vithin 3 metres of a p place to reduce ne incident and population rcc during loss of ignition and fire / heat | 2/2 in plac and at the event i for the ipeline |
| .1 | External c Comments pipeline to corrosive eff External P Objectives Provide ro adequatel factors 10 yearly of OPS509 M Pipeline in Objectives High tech location of rates Cathodic p Objectives Electrical structure f pipeline co | enting Controls oating damage is: Damage to coating be exposed to soil an lements ipeline Coating is: bust and resistant c y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu hspections - intellig idata tool which is us f pipe metal loss and protection systems :: :: | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les ent pigging sed to accurately I track deterioration | 8/8 in place | Cons 1. 1.1 1.2 2. | Safety of people Comments: An ignition sour containment could result in it radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requistructures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Pipeline Act requires licer approval for structures within 3 to 6 m Containment could result in it radiation causing exposure to | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accourt es of a pipeline failure ad within easements hire licensee approva- netres of a pipeline. I nsee and ministerial place to reduce ne incident and population rce during loss of ignition and fire / heat to property in the | 2/2 in plac and and t the event il for the ipeline 1/1 in plac |
| .1 | External c Comments pipeline to corrosive effectives Provide ro adequated factors 10 yearly of only) Cross Refe OPS509 M Pipeline in Objectives High tech location of rates Cathodic p Objectives Electrical of structure f pipeline co 6 monthly | enting Controls oating damage s: Damage to coating be exposed to soil an lements ipeline Coating s: bust and resistant of y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu hspections - intellig s: data tool which is us f pipe metal loss and protection systems s: current provides pro from corrosive elements bating is damaged | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les ent pigging sed to accurately I track deteriorati tection to steel ents in locations d to ensure prote | 8/8 in place | Cons 1. 1.1 1.2 2.1 | Safety of people Comments: An ignition sour containment could result in it radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requires structures within 3 to 6 m Pipeline Act requires licent approval for structures with with control measures in consequences of a pipelin Objectives: Separation from housing a Property damage Comments: An ignition sour containment could result in radiation causing exposure to vicinity Emergency response and procedures Loss of supply Comments: Temporary loss | ontrols rce during loss of ignition and fire / heat ico people within the eent study provides ed on location class re taking into accour es of a pipeline failure ad within easements ire licensee approva hetres of a pipeline. i nsee and ministerial idthin 3 metres of a p place to reduce ne incident and population rce during loss of ignition and fire / heat to property in the of supply could | 2/2 in plac and at the event i for the ipeline |
| .1 | External c Comments pipeline to corrosive eff External P Objectives Provide ro adequated factors 10 yearly of only) Cross Refe OPS509 M Pipeline in Objectives High tech location of rates Cathodic p Objectives Electrical of structure f pipeline co | enting Controls oating damage s: Damage to coating be exposed to soil an lements ipeline Coating s: bust and resistant of y protect the pipe fr coating surveys (un erence / Supporting laintenance Schedu hspections - intellig s: data tool which is us f pipe metal loss and protection systems s: current provides pro from corrosive element bating is damaged s (optional): CP surveys are use | may cause steel d possible oating quality to om environmenta piggable pipelin Documents: les ent pigging sed to accurately I track deteriorations tection to steel ents in locations d to ensure protect | 8/8 in place | Cons 1. 1.1 1.2 2.1 | Safety of people Comments: An ignition sour containment could result in i radiation causing exposure to consequence zone. 5 yearly safety managem protection measures bas possible pipeline exposur surrounding environment Objectives: Reduce the consequence Many pipelines are locate Pipeline regulations requires structures within 3 to 6 m Pipeline Act requires licer approval for structures with objectives: Separation from housing a Property damage Comments: An ignition sour containment could result in radiation causing exposure to vicinity Emergency response and procedures Loss of supply | ontrols rce during loss of ignition and fire / heat to people within the eent study provides ed on location class re taking into accour t es of a pipeline failure ed within easements tire licensee approva tetres of a pipeline. I nsee and ministerial rithin 3 metres of a p place to reduce ne incident and population rce during loss of ignition and fire / heat to property in the of supply could restigations are | 2/2 in plac and and t the event if for the ipeline 1/1 in plac |

Confidential

| | technicians | | | | | |
|-----|--|----------|--|--|--|--|
| 1.7 | Inspection of transition sleeves & condition of | ~ | | | | |
| 1.0 | above ground pipework | | | | | |
| 1.8 | Third party liaison activities Cross Reference / Supporting Documents: | × | | | | |
| | 320-PL-HEL-0009 Third Party Pipeline Awareness Plan | | | | | |
| | Objectives: Pipeline hits may lead to corrosion | | | | | |
| 2. | Internal pipeline corrosion 6/6 in | | | | | |
| 2.1 | Monitor levels of corrosive contaminants and 💊 | | | | | |
| 2.2 | Cathodic protection systems | 0 🗸 | | | | |
| | Objectives: | | | | | |
| | Electrical current provides protection to steel structure from corrosive elements in locations where pipeline coating is damaged | | | | | |
| | Comments (optional): | | | | | |
| | 6 monthly CP surveys are used to ensure protection systems are operating effectively | | | | | |
| 2.3 | Gas quality | ~ | | | | |
| 2.4 | Pipeline inspections - intelligent pigging | 0 🗸 | | | | |
| | Objectives: High tech data tool which is used to accurately detect location of pipe metal loss and track deterioration rates | | | | | |
| 2.5 | Internal lining | | | | | |
| 2.6 | Competency and training of relevant personnel/ technicians | 0 🗸 | | | | |
| 3. | Stress corrosion cracking 5/5 in | place | | | | |
| 3.1 | SCC assessments conducted in the past, occurrence | · • | | | | |
| | is remote in factory coated pipe Comments (optional): | | | | | |
| | SCC can be caused by elevated temperature, tensile | | | | | |
| | stress on the pipeline and a corrosive environment and is a form of external corrosion not generally | | | | | |
| | detected by Intelligent pigging. No evidence within | | | | | |
| | VTS of SCC. There is no evidence of stress corrosion cracking on | | | | | |
| | the VTS. | | | | | |
| 3.2 | Leakage Detection | ~ | | | | |
| | Objectives: | - | | | | |
| | Look for visible signs of pinhole leaks | | | | | |
| 3.3 | High level assessment of SCC | ~ | | | | |
| | Comments (optional): No known SCC detected within VTS | | | | | |
| 3.4 | Factory coated pipeline | ~ | | | | |
| | Comments (optional): No known issues of SCC within factory coated pipe worldwide | | | | | |
| 3.5 | Thicker wall pipe downstream of compressor stations | ~ | | | | |
| | | | | | | |

Actions

No items found

| | Objectives: Isolation and repair of the pipeline will minimise time impact as a temporary by-pass can be constructed to ensure security of supply until a permanent repair is completed | | | | |
|-----|--|--|--|--|--|
| 3.2 | Interconnection of pipeline grid Objectives: Interconnection of grid will minimise the area of any supply loss | | | | |
| 4. | Bushfire 1/1 in place | | | | |
| 4.1 | Environmental Management Plan & Environmental 🧳 🛷 | | | | |
| | Cross Reference / Supporting Documents: Bushfire Management Procedure; EME-020 Emergency Response Procedure; MAN-368 Att 03 | | | | |

Environmental Risk Register

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| Risk | | SS UNIT/FUNCTION | register Victoriar | n Pipeline Safety Case | RISK REVIEW DATE 30/11/2019 | |
|--------------------------------|--|---|--|---|--|--|
| | TED AT UPDATED AT 07/2014 04/12/2014 | | | | | |
| Fai | lure of equipment or material | | | | | |
| | | Inherent | | Residual | Control Effectiven | |
| | | Hig Peoj | | Low | 4-Satisfact Control Effecti | |
| | | | pie | People | Control Effecti | veness |
| | | Target | | | | |
| | | Not yet ri | sk rated | | | |
| | | | | | | |
| DESCI | RIPTION | | | | | |
| Equ | ipment or materials not suitable to task | | | | | |
| | | | | | | |
| Loca [.] Victo | rion Action Window prian Transmission System 21/7/2014 - 4/8/20 | APPROVER 014 Albert Bro | ovedani | | | |
| 1000 | | | ovedani | | | |
| | STATUS | | | | | |
| Activ | /e | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | SES + Preventing Controls | in place controls | Cons | EQUENCES + Mitigating Co | 2 items 8/8 in ntrols | n place contr |
| | | in place controls 5/5 in place | | equences + Mitigating Co Safety issues Corrective repair / replace | ntrols | n place contr |
| 1. | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig | 5/5 in place | Cons | Safety issues Corrective repair / replace | ntrols | n place contro 4/4 in plac Ø |
| Caus 1.1 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) | 5/5 in place | Cons 1. 1.1 | Safety issues | ntrols | n place contro 4/4 in plac Ø |
| 1. | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project | 5/5 in place | Cons 1. 1.1 | Safety issues Corrective repair / replace Engineering review | ntrols ment | n place contro 4/4 in plac Ø |
| 1. | 565 + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: | 5/5 in place | Cons 1. 1.1 1.2 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed | ntrols ment | n place contro 4/4 in plac Ø Ø |
| 1. | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project | 5/5 in place | Cons 1. 1.2 1.3 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls | ntrols ment lback to design | n place contro 4/4 in plac Ø Ø |
| 1. | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: | 5/5 in place n 🗸 ct | Cons 1. 1.1 1.2 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed | ntrols ment lback to design | n place contro 4/4 in plac Ø Ø |
| 1. | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide | 5/5 in place n ✓ ct ct | Cons 1. 1.1 1.2 1.3 1.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent | ntrols ment lback to design | n place contro 4/4 in plac Ø Ø |
| 1. | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: | 5/5 in place n ✓ ct ct | Cons 1. 1.1 1.2 1.3 1.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt | ntrols ment lback to design | n place contro 4/4 in plac Ø Ø |
| 1. 1.1 | SGES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing | 5/5 in place n ✓ ct ct ction g TP | Cons 1. 1.1 1.2 1.3 1.4 2. | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply | ntrols ment lback to design | 4/4 in plac |
| 1. | SGES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspect and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment | 5/5 in place n ✓ ct ct | Cons 1. 1.1 1.2 1.3 1.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt | ntrols ment lback to design | n place contro 4/4 in plac Ø Ø Ø 4/4 in plac |
| 1. 1.1 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: | 5/5 in place n ✓ ct ct ction g TP | Cons 1. 1.1 1.2 1.3 1.4 2. | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review | ntrols ment Iback to design | n place contro 4/4 in plac Ø Ø 4/4 in plac |
| 1. 1.1 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide | 5/5 in place n ✓ ct ct ction g TP | Cons 1. 1.1 1.2 1.3 1.4 2. 2.1 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed | ntrols ment lback to design t reoccurence | n place contro 4/4 in plac Ø Ø 4/4 in plac |
| 1. 1.1 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: | 5/5 in place n ✓ ct ct ction g TP | Cons 1. 1.1 1.2 1.3 1.4 2.1 2.2 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace | ntrols ment lback to design t reoccurence | n place contro 4/4 in plac Ø Ø Ø 4/4 in plac Ø |
| 1. 1.1 1.2 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 | 5/5 in place n ✓ ct ct g TP Ø ✓ | Cons 1. 1.1 1.2 1.3 1.4 2. 2.1 2.2 2.3 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace Safety critical controls | ntrols ment lback to design t reoccurence lback to design ment | n place contro 4/4 in plac Ø Ø 4/4 in plac Ø Ø Ø |
| 1. 1.1 | SGES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 Design management including training & | 5/5 in place n ✓ ct ct ction g TP | Cons 1. 1.1 1.2 1.3 1.4 2.1 2.2 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace Safety critical controls Incident review to prevent | ntrols ment lback to design t reoccurence lback to design ment | n place contro 4/4 in plac Ø Ø 4/4 in plac Ø Ø Ø |
| 1. 1.1 1.2 1.3 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 Design management including training & competency of staff | 5/5 in place n ✓ ct ction g TP Ø ✓ | Cons 1. 1.1 1.2 1.3 1.4 2. 2.1 2.2 2.3 2.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace Safety critical controls | ntrols ment lback to design t reoccurence lback to design ment | n place contro 4/4 in plac Ø Ø 4/4 in plac Ø Ø Ø |
| 1. 1.1 1.2 | SGES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspe and testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 Design management including training & | 5/5 in place n ✓ ct ct g TP Ø ✓ | Cons 1. 1.1 1.2 1.3 1.4 2. 2.1 2.2 2.3 2.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace Safety critical controls Incident review to prevent Comments (optional): | ntrols ment lback to design t reoccurence lback to design ment | n place contro 4/4 in plac & & & & & & & & & & & & & & & & & & & |
| L.1 L.2 L.3 | SGES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspeand testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 Design management including training & competency of staff Engineering review | 5/5 in place n ✓ ct ction g TP Ø ✓ | Cons 1. 1.1 1.2 1.3 1.4 2. 2.1 2.2 2.3 2.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace Safety critical controls Incident review to prevent Comments (optional): | ntrols ment lback to design t reoccurence lback to design ment | n place contro 4/4 in plac Ø Ø 4/4 in plac Ø Ø Ø |
| L.1 1.2 1.3 | SES + Preventing Controls Inadequate / incorrect specification of equipment / materials Methodology & philosophy for system desig (Design Basis Manual) Cross Reference / Supporting Documents: ESD077 Design Management; ESD100 Project Management; HAZ238 Hazop study guiide Testing of equipment or material Cross Reference / Supporting Documents: ESD077 Design Management; ESD089 Inspeand testing; PIP299 Purging & Commissioning Pipeline: PIP339 Hydrostatic Testing Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 Design management including training & competency of staff Engineering review Comments (optional): | 5/5 in place n ✓ ct ction g TP Ø ✓ | Cons 1. 1.1 1.2 1.3 1.4 2. 2.1 2.2 2.3 2.4 | Safety issues Corrective repair / replace Engineering review Comments (optional): review specification & feed Safety critical controls Incident review to prevent Comments (optional): Including lessons learnt Security of supply Engineering review Comments (optional): review specification & feed Corrective repair / replace Safety critical controls Incident review to prevent Comments (optional): | ntrols ment lback to design t reoccurence lback to design ment | n place contr 4/4 in plac Ø Ø 4/4 in plac Ø Ø |

| 2.1 | Procedures for testing, sampling and inspection of all materials and parts Cross Reference / Supporting Documents: CSM312 Inspection of Materials; CSM313 Product Recall: ESD089 Inspection and Testing: STD247 Inspection & Testing of Electrical Equipment | • |
|-----|--|-----|
| 2.2 | Risk assessment Cross Reference / Supporting Documents: HAZ238 Hazop study guide Action window: 21/7/2014 - 4/8/2014 | Ø 🖌 |
| 2.3 | Materials and parts re-checked prior to installation Cross Reference / Supporting Documents: ESD085 Product Identification and Traceability Action window: 21/7/2014 - 4/8/2014 | ~ |
| 2.4 | Procedures for site testing and commissioning Cross Reference / Supporting Documents: ESD089 Inspection and testing; PIP250 Purging and Commissioning TP Pipeline Policy; PIP299 Purging and Commissioning TP Pipeline Procedure Action window: 21/7/2014 - 4/8/2014 | ~ |

Actions

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| risk id stat Sisk 1094 | TE Approved | DIVISION/BUSINESS UNIT/FUN Field Services | | Pipeline Safety Case | RISK REVIEW DATE 30/08/2019 |
|--|------------------------|--|--------------------|----------------------------|--------------------------------------|
| REATED AT UPDATE 9/07/2014 04/1 | ed at 2/2014 | | | | |
| Excavation or t | renching | g works - hazar | | | |
| | | Inhere | High | Residual | Control Effectiveness 4-Satisfactory |
| | | | People | People | Control Effectiveness |
| | | Target | | · copie | |
| | | N | lot yet risk rated | | |
| ESCRIPTION | | | | | |
| excavation, trenching a excavation equipment. | nd shoring n | ot completed properly o | can cause a danger | to workers and the public. | Pipeline could be hit by |
| осатіон ictorian Transmission S | | over ert Brovedani | | | |
| isk status Active | | | | | |
| | | | | | |

| Risk Owner Albert Brovedani | 1 Raised by Albert Brovedani |
|-----------------------------|-------------------------------------|
|-----------------------------|-------------------------------------|

| Cau | 3 items 10/10 in g SES + Preventing Controls | place controls |
|-----|--|----------------|
| 1. | Collapse of trench | 4/4 in place |
| 1.1 | Excavation procedure Comments (optional): Permit to work & JHA, work instruction | Ø 🖌 |
| 1.2 | Shoring and benching of all work to prevent collapse Cross Reference / Supporting Documents: PIP273 Pipeline excavation | ~ |
| 1.3 | Job Hazard Analysis | Ø 🗸 |
| 1.4 | Excavation training | Ø 🗸 |
| 2. | Demarcation zone unclear | 5/5 in place |
| 2.1 | Excavation procedure Comments (optional): Permit to work & JHA, work instruction | Ø 🖌 |
| 2.2 | Job Hazard Analysis | O 🗸 |
| 2.3 | Excavation training | 0 🗸 |
| 2.4 | Design to minimise exposure to risk Cross Reference / Supporting Documents: ESD077 Design Management; | ~ |
| 2.5 | Exclude the public from hazardous work area by fence/ barricade, warning signs, temporary cov security patrols Cross Reference / Supporting Documents: ESD355 Construction safety; PIP273 Pipeline | · · · |

2 items 2/2 in place controls

| Con | Sequences + Mitigating Controls | |
|-----|---------------------------------|---|
| 1. | Injury to staff or public | 1/1 in place |
| 1.1 | Emergency response plan | Image: A start of the start of |
| 2. | Damage to infrastructure | 1/1 in place |
| 2.1 | Emergency repair procedures | 1 |

Confidential

| | Excavation | |
|-----|---|--------------|
| з. | Pipeline struck by excavation equipment | 1/1 in place |
| 3.2 | Excavation procedure | |
| | Comments (optional): Permit to work & JHA, work instruction, superv | ision |

Actions

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| Risk | RISK ID 1093 | STATE Approved | DIVISION/BUSINESS | | REGISTER Victorian | Pipeline Safety Case | RISK REVIEW DATE 30/08/2019 | |
|-------|---|---|--|----------------------|-----------------------|--|--|--------------|
| | ed at 7/2014 | UPDATED AT 04/12/2014 | | | | | | |
| Cor | npresso | or Failure | | | | | | |
| | | | | Inherent | | Residual | Control Effectivene | |
| | | | | Intermo | | Low People | 4-Satisfacto Control Effectiv | - |
| | | | | Peo | pie | People | Control Effectiv | eness |
| | | | | Target Not yet n | isk rated | | | |
| | | | | | | | | |
| OCAT | | | ROVER | | | | | |
| /icto | rian Transmi | ssion System Alb | ert Brovedani | | | | | |
| ISK S | TATUS | | | | | | | |
| Activ | е | | | | | | | |
| | | | | | | | | |
| | | | | | | | | Doc. Control |
| | | | 2 items 9/9 i | n place controls | 5 | | 2 items 3/3 in | place contro |
| aus | es + Prever | nting Controls | | | | equences + Mitigating Co | | |
| | Componen | t failure | | 5/5 in place | 1. | Reduced pipeline capacity | , | 2/2 in plac |
| 1 | | aintenance - sched | | e 🖌 | 1.1 | Repair procedures | | ~ |
| | Cross Refe | ce Connection sys rence / Supporting | Documents: | | | Spare parts inventory Objectives: | | • |
| | | Brooklyn Compress CS023 - Gooding Co | | | | Enable quick repair and re | duce down time | |
| | Ooperation | & Maintenance Ma | anual; WCG276 - | | - | | | 1/1 : |
| | | & Maintenance Mar ce Policy; OPS509 - | | | | Safety issues | | 1/1 in plac |
| | Schedules | Le Policy; 0P5509 - | Maintenance | | | Emergency response plan | | |
| | Juiedules | | | | | | | ~ |
| | Objectives | | | | | Cross Reference / Suppor EME556 - Compressor Sta | ing Documents: | ~ |
| | Objectives Maintenand | ce Engineering Plar | | | | Cross Reference / Suppor EME556 - Compressor Sta Procedure | ing Documents: | • |
| | Objectives Maintenand | ce Engineering Plar lities are maintaine | | | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | v |
| 1.2 | Objectives Maintenand ensure faci | ce Engineering Plar lities are maintaine | | | | Cross Reference / Suppor EME556 - Compressor Sta Procedure Objectives: | ting Documents: tion Site Emergency | • |
| 1.2 | Objectives Maintenand ensure faci design star Design Cross Refe | ce Engineering Plar lities are maintaine | d in accordance v | with | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | • |
| 1.2 | Objectives Maintenand ensure faci design star Design Cross Refe ESD-077 D Objectives | ce Engineering Plar lities are maintaine ndards rence / Supporting esign Managemen | d in accordance v Documents: t - | with 🗸 | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | ~ |
| 1.2 | Objectives Maintenand ensure faci design star Design Cross Refe ESD-077 D Objectives Facilities ar and are ala | re Engineering Plar lities are maintaine ndards rence / Supporting esign Managemen : e designed to fail s rmed. Some facilitie | d in accordance of Documents: t - afe, have redund | with 🗸 | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | • |
| | Objectives Maintenand ensure faci design star Design Cross Refe ESD-077 D Objectives Facilities ar and are ala gas detect | ce Engineering Plar lities are maintaine ndards rence / Supporting esign Managemen : e designed to fail s rmed. Some facilitie ors | d in accordance of Documents: t - afe, have redund es are designed v | with ancy with | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | • |
| 1.2 | Objectives Maintenand ensure faci design star Design Cross Refe ESD-077 D Objectives Facilities ar and are ala gas detect Operationa Cross Refe | re Engineering Plar lities are maintaine ndards rence / Supporting esign Managemen : e designed to fail s rmed. Some facilitie | d in accordance of Documents: t - afe, have redund es are designed of managed by AEM | with ancy with | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | • |
| | Objectives Maintenance ensure faci design star Design Cross Refe ESD-077 D Objectives Facilities ar and are ala gas detect Operationa Cross Refe Service Env Objectives | rence / Supporting esign Managemen e designed to fail s rmed. Some facilitie ors al procedures are rence / Supporting relope Agreement | d in accordance of Documents: t - afe, have redund as are designed of managed by AEM Documents: | with ancy with | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | |
| | Objectives Maintenance ensure faci design star Design Cross Refe ESD-077 D Objectives Facilities ar and are ala gas detect Operationa Cross Refe Service Env Objectives | rence / Supporting esign Managemen e designed to fail s rmed. Some facilitie ors al procedures are f rence / Supporting velope Agreement : e pipeline within its | d in accordance of Documents: t - afe, have redund as are designed of managed by AEM Documents: | with ancy with | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | |
| 3 | Objectives Maintenand ensure faci design star Design Cross Refe ESD-077 D Objectives Facilities ar and are ala gas detect Operationa Cross Refe Service Env Objectives Operate the | rence / Supporting esign Managemen e designed to fail s rmed. Some facilitie ors al procedures are f rence / Supporting velope Agreement : e pipeline within its | d in accordance of Documents: t - afe, have redund es are designed of managed by AEM Documents: design limits | with ancy with | | Cross Reference / Support EME556 - Compressor Sta Procedure Objectives: Minimise any consequence | ting Documents: tion Site Emergency | |

L Risk Owner Albert Brovedani 👤 Raised by Albert Brovedani

| | damage or consequence of damage | |
|-----|---|--------------|
| 2. | Failure of auxiliary equipment Comments: Equipment feeding into compressor causes failure | 4/4 in place |
| 2.1 | Design Objectives: Facilities are designed to fail safe, have redundan and are alarmed. Some facilities are designed with gas detectors | - |
| 2.2 | Incorrect operation Cross Reference / Supporting Documents: Service Envelope Agreement Objectives: The pipeline facilities are designed to fail safe by managing pressure and temperature limits | ~ |
| 2.3 | Condition monitoring | Ø 🗸 |
| 2.4 | Regular maintenance Cross Reference / Supporting Documents: OPS509 Maintenance Schedules | ~ |

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| rype Ris I | | STATE Approved | DIVISION/BUSINESS UNIT ECG Engineerir | , | register Victoria | n Pipeline Safety Case | RISK REVIEW DATE 30/08/2019 | |
|----------------------|---|--|---|-------------------------------|--|---|--|---|
| | TED AT 07/2014 | UPDATED AT 04/12/2014 | | | | | | |
| ۶h | ysical da | amage to ab | ove ground ir | nfrastru | icture | | | |
| | | | Inf | herent | | Residual | Control Effectivenes | 55 |
| | | | | Interm | ediate | Low | 4-Satisfactor | у |
| | | | | Security o | of Supply | Security of Supply | Control Effective | ness |
| | | | Та | rget | | | | |
| | | | | Not yet n | isk rated | | | |
| ESC | RIPTION | | | | | | | |
| | | | | case scen | ario for this | risk, however vandalism or | vehicle damage could | be a |
| au | se of damag | e to above ground | intrastructure. | | | | | |
| оса | TION | APF | ROVER | | | | | |
| /ict | orian Transmi | ission System Alb | ert Brovedani | | | | | |
| | STATUS | | | | | | | |
| \cti | ve | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | Doc Contro |
| | | | | | | | | Doc. Contro |
| au | Ses + Preve | 3 nting Controls | items 10/10 in pl | lace controls | | Sequences + Mitigating Co | 4 items 5/5 in pontrols | |
| | Deliberate | nting Controls damage by intrud | ers to facilities 5 | lace controls 5/5 in place | Con: 1. | Damage to assets | ontrols | place contr |
| | Deliberate Comments | nting Controls | ers to facilities 5 tage & terrorism | | Con | Damage to assets Remote monitoring of site | ontrols | place contr |
| • | Deliberate Comments Fenced cor | nting Controls • damage by intrud • Could include sabo | ers to facilities 5 tage & terrorism buildings | | Con: 1. | Damage to assets | ontrols | place contr |
| | Deliberate Comments Fenced con Cross Refe OPS260 Se | nting Controls damage by intrud : Could include sabol mpounds & locked erence / Supporting | ers to facilities 5 tage & terrorism buildings | 5/5 in place | Con: 1. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detect pressure change could also | ontrols e ct damage to facilities, so be detected possibl | place contr 2/2 in plac |
| | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing | nting Controls damage by intrud : Could include sabor mpounds & locked rence / Supporting ecurity Around Asse | ers to facilities 5 tage & terrorism buildings Documents: | 5/5 in place | Con: 1. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detect | ontrols e ct damage to facilities, so be detected possibl | place contr 2/2 in plac |
| • | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives | nting Controls damage by intrud : Could include sabor mpounds & locked rence / Supporting ecurity Around Asse | ers to facilities 5 tage & terrorism buildings Documents: ets; SEC189 Security | 5/5 in place | Con: 1. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detect pressure change could also | ontrols ct damage to facilities, so be detected possibl ations or facilities | 2/2 in plac y |
| • | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments | nting Controls damage by intrud : Could include saboin mpounds & locked rence / Supporting ecurity Around Assect : ohysical barrier to end (optional): | ers to facilities 5 rage & terrorism buildings Documents: ets; SEC189 Security | 5/5 in place | Con: 1. 1.1 | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detec pressure change could als indicating a problem at sta Regular facility inspection damage | ontrols ct damage to facilities, so be detected possibl ations or facilities | 2/2 in plac y |
| • | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments | nting Controls damage by intrud : Could include saboi mpounds & locked erence / Supporting ecurity Around Asse : ohysical barrier to en | ers to facilities 5 rage & terrorism buildings Documents: ets; SEC189 Security | 5/5 in place | Con: 1. 1.1 | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detect pressure change could als indicating a problem at stat Regular facility inspection | ontrols t damage to facilities, to be detected possible ations or facilities to identify undetect | 2/2 in plac y |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h | nting Controls damage by intrud : Could include saboi mpounds & locked erence / Supporting ecurity Around Asse : ohysical barrier to en (optional): nave been identified | ers to facilities 5 rage & terrorism buildings Documents: ets; SEC189 Security | 5/5 in place | Con: 1. 1.1 1.2 2.1 | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detec pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect | ontrols t damage to facilities, to be detected possible ations or facilities to identify undetect | 2/2 in plac 2/2 in plac y ted 1/1 in plac |
| 1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Mat HAZOPS | nting Controls a damage by intrud : Could include sabor mpounds & locked arence / Supporting ecurity Around Asse : ohysical barrier to en (optional): nagement Studies/ | ers to facilities 5 tage & terrorism buildings Documents: ets; SEC189 Security htry. | 5/5 in place | Con: 1. 1.1 1.2 2. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption | ontrols t damage to facilities, so be detected possible ations or facilities is to identify undetect ion of pipeline | 2/2 in plac 2/2 in plac y ted 1/1 in plac |
| 1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Mat HAZOPS Cross Refe | nting Controls damage by intrud : Could include saboi mpounds & locked erence / Supporting ecurity Around Asse : ohysical barrier to en (optional): nave been identified | ers to facilities 5 tage & terrorism buildings Documents: ets; SEC189 Security htry. | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detec pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo | ontrols t damage to facilities, so be detected possible tions or facilities is to identify undetect ion of pipeline oast Grid reduces the ss over a greater area | 2/2 in plac 2/2 in plac y :ed 1/1 in plac |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Mat HAZOPS Cross Refe | nting Controls damage by intrud Could include saboin mpounds & locked rence / Supporting ecurity Around Asses : ohysical barrier to en (optional): have been identified magement Studies/ rence / Supporting acop Study Guide | ers to facilities 5 tage & terrorism buildings Documents: ets; SEC189 Security htry. | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of | ontrols t damage to facilities, so be detected possible tions or facilities is to identify undetect ion of pipeline oast Grid reduces the ss over a greater area | 2/2 in plac 2/2 in plac y :ed 1/1 in plac |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Man HAZOPS Cross Refe HAZ238 Ha Objectives Considerat | nting Controls damage by intrud Could include saboin mpounds & locked rence / Supporting ecurity Around Asse (optional): ave been identified nagement Studies/ rence / Supporting azop Study Guide : tion to surrounding | ers to facilities 5 tage & terrorism buildings Documents: ets; SEC189 Security ntry. Risk Assessment / Documents: environment and | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detec pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo | ontrols t damage to facilities, so be detected possible tions or facilities is to identify undetect ion of pipeline oast Grid reduces the ss over a greater area | 2/2 in plac 2/2 in plac y :ed 1/1 in plac |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Man HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und | nting Controls damage by intrud Could include saboin mpounds & locked rence / Supporting ecurity Around Asse (optional): ave been identified nagement Studies/ rence / Supporting azop Study Guide : tion to surrounding dertaken through S | ers to facilities tage & terrorism buildings Documents: ets; SEC189 Security htry. Risk Assessment / Documents: environment and MS / Risk Assessme | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. | ontrols t damage to facilities, so be detected possible tions or facilities is to identify undetect ion of pipeline oast Grid reduces the ss over a greater area or contained within a | 2/2 in plac 2/2 in plac y :ed 1/1 in plac |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Mau HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us | nting Controls damage by intrud Could include saboin mpounds & locked rence / Supporting ecurity Around Asse (optional): have been identified nagement Studies/ rence / Supporting azop Study Guide : cion to surrounding dertaken through S sed to ensure equi | ers to facilities tage & terrorism buildings Documents: ets; SEC189 Security htry. Risk Assessment / Documents: environment and MS / Risk Assessme | 5/5 in place | Con: 1.1 1.2 2.1 3.1 | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence | entrols t damage to facilities, so be detected possible tions or facilities is to identify undetect ion of pipeline oast Grid reduces the ss over a greater area or contained within a e of supply loss | 2/2 in plac 2/2 in plac y 1/1 in plac 1/1 in plac |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Mau HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us | nting Controls damage by intrud Could include saboin mpounds & locked rence / Supporting ecurity Around Asse (optional): ave been identified nagement Studies/ rence / Supporting azop Study Guide : tion to surrounding dertaken through S | ers to facilities tage & terrorism buildings Documents: ets; SEC189 Security htry. Risk Assessment / Documents: environment and MS / Risk Assessme | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. 3.1 4. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence Bushfire from gas released | e of supply loss | 2/2 in plac 2/2 in plac y 1/1 in plac 1/1 in plac |
| au 1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Mat HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us damaged of | nting Controls damage by intrud Could include saboin mpounds & locked rence / Supporting ecurity Around Asse (optional): have been identified nagement Studies/ rence / Supporting azop Study Guide : cion to surrounding dertaken through S sed to ensure equi | ers to facilities tage & terrorism buildings Documents: ets; SEC189 Security htry. Risk Assessment / Documents: environment and MS / Risk Assessme | 5/5 in place | Con: 1.1 1.2 2.1 3.1 | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence | e of supply loss | 2/2 in plac 2/2 in plac y 1/1 in plac 1/1 in plac |
| 1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Man HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us damaged of Critical equ | nting Controls damage by intrud : Could include saboin mpounds & locked rence / Supporting ecurity Around Asses : ohysical barrier to en- (optional): have been identified magement Studies/ erence / Supporting azop Study Guide : tion to surrounding dertaken through S sed to ensure equi- or malfunctions. uipment is locked encing at critical si | ers to facilities tage & terrorism buildings Documents: ets; SEC189 Security ntry. Risk Assessment / Documents: environment and MS / Risk Assessme pment is fail safe if | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. 3.1 4. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence Bushfire from gas release Bushfire Management Pro | e of supply loss | 2/2 in plac 2/2 in plac y 1/1 in plac 1/1 in plac |
| 1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Man HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us damaged of Critical equ | nting Controls a damage by intrud : Could include saboin impounds & locked arence / Supporting ecurity Around Assect : ohysical barrier to en- (optional): have been identified magement Studies/ acop Study Guide : cion to surrounding dertaken through S sed to ensure equi or malfunctions. uipment is locked encing at critical si arence / Supporting | ers to facilities tage & terrorism buildings pocuments: ets; SEC189 Security htry. Risk Assessment / pocuments: environment and MS / Risk Assessme pment is fail safe if tes pocuments: | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. 3.1 4. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence Bushfire from gas release Bushfire Management Pro response plan Cross Reference / Suppor 320-PR-HS-0007 Bushfire | entrols ct damage to facilities, so be detected possible ations or facilities is to identify undetect ion of pipeline oast Grid reduces the so over a greater area or contained within a e of supply loss b cedure - Emergency ting Documents: Management Procedu | 2/2 in plac y ted 1/1 in plac 1/1 in plac a, 1/1 in plac |
| • .1 .2 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Man HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us damaged of Critical equ | nting Controls damage by intrud : Could include saboin mpounds & locked rence / Supporting ecurity Around Asses : ohysical barrier to en- (optional): have been identified magement Studies/ erence / Supporting azop Study Guide : tion to surrounding dertaken through S sed to ensure equi- or malfunctions. uipment is locked encing at critical si | ers to facilities tage & terrorism buildings pocuments: ets; SEC189 Security htry. Risk Assessment / pocuments: environment and MS / Risk Assessme pment is fail safe if tes pocuments: | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. 3.1 4. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence Bushfire Management Pro response plan Cross Reference / Suppor 320-PR-HS-0007 Bushfire EME020 Emergency Manage | entrols ct damage to facilities, so be detected possible ations or facilities is to identify undetect ion of pipeline oast Grid reduces the so over a greater area or contained within a e of supply loss b cedure - Emergency ting Documents: Management Procedu | 2/2 in plac 2/2 in plac y ted 1/1 in plac 1/1 in plac a, 1/1 in plac |
| .1 | Deliberate Comments Fenced con Cross Refe OPS260 Se Fencing Objectives Provide a p Comments Key sites h Safety Man HAZOPS Cross Refe HAZ238 Ha Objectives Considerat threats und HAZOPS us damaged of Critical equ | nting Controls a damage by intrud : Could include saboin impounds & locked arence / Supporting ecurity Around Assect : ohysical barrier to en- (optional): have been identified inagement Studies/ acop Study Guide : tion to surrounding dertaken through S sed to ensure equi- por malfunctions. uipment is locked encing at critical si- rence / Supporting Gecurity Risk Manag | ers to facilities tage & terrorism buildings pocuments: ets; SEC189 Security htry. Risk Assessment / pocuments: environment and MS / Risk Assessme pment is fail safe if tes pocuments: | 5/5 in place | Con: 1. 1.1 1.2 2. 2.1 3. 3.1 4. | Damage to assets Remote monitoring of site Objectives: SCADA alarms could detee pressure change could als indicating a problem at sta Regular facility inspection damage Injury to people Equipment to isolate sect Supply interruption Interconnection of East C consequence of supply lo effects may be localised of specific area. Objectives: Minimise any consequence Bushfire from gas release Bushfire Management Pro response plan Cross Reference / Suppor 320-PR-HS-0007 Bushfire | e of supply loss e of s | 2/2 in pla 2/2 in pla y ted 1/1 in pla a, 1/1 in pla |

| | other work | |
|------------------|---|---|
| 2.1 | Work permit conditions | Image: A set of the set of the |
| | Cross Reference / Supporting Documents: OPS166 Safe Work Permit & Facilities Release S | ystem |
| 2.2 | Critical equipment is locked | Ø 🗸 |
| 2.3 | Operating and maintenance procedures / train | ning 🧹 |
| | Cross Reference / Supporting Documents: MAN236 Competency and Training Managemen | ıt |
| | | |
| 3. | Vehicle impact | 2/2 in place |
| 3. 3.1 | Vehicle impact Critical equipment is locked | 2/2 in place |
| | | 2/2 in place |
| 3.1 | Critical equipment is locked | 2/2 in place Ø ✓ |

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

👤 Risk Owner Albert Brovedani TYPE RISK ID STATE DIVISION/BUSINESS UNIT/FUNCTION REGISTER RISK REVIEW DATE Victorian Pipeline Safety Case 27/09/2019 Risk 0243 Approved Transmission CREATED AT UPDATED AT 21/02/2014 04/12/2014 Damage to pipeline caused by environmental factors Inherent Residual Control Effectiveness 4-Satisfactory High Low Security of Supply Security of Supply Control Effectiveness Target Not vet risk rated DESCRIPTION These instances may cause movement and stresses on the pipeline, erosion may expose pipe and subject the pipe to being hit. Wollert to Wodonga used as scenario for worst case rupture. LOCATION ACTION WINDOW APPROVER Albert Brovedani Victorian Transmission System 29/7/2014 - 12/8/2014 Doc. Control: 87 3 items 10/10 in place controls 3 items 9/9 in place controls Causes + Preventing Controls Consequences + Mitigating Controls 1. Pipeline damage due to flood, erosion, 7/7 in place 1. Coating damage leading to pipe damage 2/2 in place landslips, subsidence, earthquake or other 1.1 Remedial works for identified problems O V environmental factors ILI program, Cathodic protection 1.2 1 1.1 Design hazard / risk assessment **Cross Reference / Supporting Documents:** Pipeline movement / stress on pipe steel 4/4 in place 2. CVW203; Site drainage, CVW204: Prevention of soil Pipeline repair plan 2.1 OV erosion, ESD077: Design management, PIP220: **Objectives:** Vegetation within Corridor Reserves, PIP354: Pipeline Implement a by-pass to minimise downtime and then Route Selection, PIP384: Design of Special Crossings build permanent solution **Objectives:** Design policies and route selection are used to 2.2 **Design review** \checkmark minimise these exposures as much as possible. 2.3 **Patrolling and inspections** O V Choose the most desirable pipeline route through route surveys, soil surveys, earthquake studies, 2.4 **Environmental Management Plans** OV creek/river crossings з. Rupture / loss of containment 3/3 in place Pipelines designed to comply with AS2885 or 0 🗸 3.1 Remedial works for identified problems predecessor standard 3.2 Pipeline repair plan 0V Route selection to minimise exposure 1.2 \checkmark Objectives: **Cross Reference / Supporting Documents:** Implement a by-pass to minimise downtime and then PIP354 Pipeline Route Selection build permanent solution 1.3 Patrolling and inspections 0 🗸 3.3 **Bushfire Management Procedure - Emergency** 0 🗸 response plan 1.4 Remedial works for identified problems 0 🗸 **Cross Reference / Supporting Documents:** 1.5 5 yearly safety management study O 🗸 320-PR-HS-0007 Bushfire Management Procedure; **Cross Reference / Supporting Documents:** EME020 Emergency Management Manual HAZ238 Hazop study guide **Objectives:** Minimise any consequence of uncontrolled gas 1.6 **Design criteria and mitigation techniques** 0 🗸

Cross Reference / Supporting Documents:

release

PIP354 Pipeline route selection

Objectives:

consider stabilisation of pipeline through design criteria application such as depth under creeks/ rivers, concrete weight coating, reinforced banks/river beds, trench breakers, directional drills, independent support of structures

| 1.7 | Environmental Management Plans | Ø 🗸 |
|-----|--|---|
| 2. | Lightning Strike | 1/1 in place |
| 2.1 | Plant earthing / Surge protection Action window: 29/7/2014 - 12/8/2014 | ~ |
| 3. | Bushfire | 2/2 in place |
| 3.1 | Buried pipeline & cleared easement | Image: A start of the start of |
| 3.2 | Design criteria and mitigation techniques Cross Reference / Supporting Documents: PIP354 Pipeline route selection | Ø 🖌 |
| | Objectives: consider stabilisation of pipeline through design criteria application such as depth under creek rivers, concrete weight coating, reinforced bar | s/ |

Actions

No items found

support of structures

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| YPE Risk | RISK ID 1084 | state Approved | | SINESS UNIT/FUNCTION nstruction | register Victoriar | n Pipeline Safety Case | RISK REVIEW DATE 29/11/2019 | |
|----------------|--|--|---|---|--|--|--|--|
| | TED AT 07/2014 | UPDATED AT 04/12/2014 | | | | | | |
| na | adequate | e / Incorrec | t design i | input | | | | |
| | | | | Inherent | | Residual | Control Effectiver | |
| | | | | | nediate | Low | 4-Satisfact | |
| | | | | | ople | People | Control Effecti | iveness |
| | | | | Target | | | | |
| | | | | Not yet | risk rated | | | |
| | | | | | | | | |
| | RIPTION | | | | | | | |
| າad | equate desi | gn causes inabilit | y to function a | as desired | | | | |
| OCA. | TION | م | PPROVER | | | | | |
| icto | orian Transmi | ssion System 🛛 🖌 | Albert Brovedan | i | | | | |
| ISK S | STATUS | | | | | | | |
| cti | ve | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | 1 items 6 | 6 in place contro | | | 3 items 5/5 i | |
| | Inadequat Comments | nting Controls e brief : Project requireme | | 5/6 in place contro 6/6 in place arly | Cons | EQUENCES + Mitigating Co Supply restriction Comments: Breach of comm | nercial agreement if | in place contr |
| • | Inadequate Comments defined | e brief : Project requireme | ents are not cle | 6/6 in place arly | Cons | Supply restriction Comments: Breach of comm unable to fulfil delivery requir | ontrols nercial agreement if rements | in place contr 1/1 in plac |
| aus | Inadequate Comments defined Design bas | e brief : Project requireme sis manual/ FEED | ents are not cle study report | 6/6 in place arly | Cons 1. 1.1 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet | ontrols nercial agreement if rements | in place contr 1/1 in plac |
| | Inadequate Comments defined Design bas Cross Refe | e brief : Project requireme | ents are not cle study report ng Documents | 6/6 in place arly | Cons 1. 1.1 2. | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues | ontrols nercial agreement if rements t control rooms | in place contr 1/1 in plac Ø 1/1 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 De | e brief : Project requireme sis manual/ FEED rence / Supportin esign Manageme | ents are not cle study report ng Documents nt, | 6/6 in place arly | Cons 1.1 2.1 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet | ontrols nercial agreement if rements t control rooms | in place contr 1/1 in plac Ø 1/1 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 Des Training au | e brief : Project requireme sis manual/ FEED rence / Supporti esign Manageme nd competency o | ents are not cle study report ng Documents nt, | 6/6 in place arly | Cons 1.1 2.1 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures | ontrols nercial agreement if rements t control rooms | in place contr 1/1 in plac Ø 1/1 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 De Training au Design Rev | e brief : Project requireme sis manual/ FEED rence / Supporti esign Manageme nd competency o | ents are not cle study report ng Documents nt, f engineers | 6/6 in place arly | Cons 1. 1.1 2. 2.1 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and | ontrols mercial agreement if rements t control rooms | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 De Training au Design Rev Cross Refe | e brief : Project requireme sis manual/ FEED trence / Supportin esign Manageme nd competency o views | ents are not cle study report ng Documents nt, f engineers ng Documents | 6/6 in place arly | Cons 1.1 2.1 3.1 3.1 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lessor | ontrols mercial agreement if rements t control rooms | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 De Design Rev Cross Refe ESD077 De Objectives | e brief : Project requirements sis manual/ FEED rence / Supporting esign Management d competency of views rence / Supporting esign Manageme : | ents are not cle study report ng Documents nt, fengineers ng Documents nt | 6/6 in place arly | Cons 1. 1.1 2. 3. 3.1 3.2 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 De Training au Design Rev Cross Refe ESD077 De Objectives ensure des | e brief Project requirements sis manual/ FEED rence / Supporting esign Managements views rence / Supporting esign Managements sign meets specifi | ents are not cle study report ng Documents nt, fengineers ng Documents nt | 6/6 in place arly | Cons 1. 1.1 2. 3. 3.1 3.2 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lessor | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 | Inadequate Comments defined Design bas Cross Refe ESD077 De Design Rev Cross Refe ESD077 De Objectives | e brief Project requirements sis manual/ FEED rence / Supporting esign Managements views rence / Supporting esign Managements sign meets specifi | ents are not cle study report ng Documents nt, fengineers ng Documents nt | 6/6 in place arly | Cons 1. 1.1 2. 3. 3.1 3.2 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in place 0 1/1 in place 0 3/3 in place |
| .1 .2 .3 | Inadequate Comments defined Design bas Cross Refe ESD077 De Design Rev Cross Refe ESD077 De Objectives ensure des requiremen Safety Man | e brief Project requirements bis manual/ FEED prence / Supporting esign Management d competency of views prence / Supporting esign Management sign meets specifients magement Study | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur | 6/6 in place arly | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| | Inadequate Comments defined Design bas Cross Refe ESD077 De Training au Design Rev Cross Refe ESD077 De Objectives ensure des requiremen Safety Man assessmen | e brief Project requirement Sis manual/ FEED Prence / Supporting esign Management views Prence / Supporting esign Management sign meets specifients magement Study hts | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur & other risk | 6/6 in place arly | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 .2 .3 | Inadequate Comments defined Design bas Cross Refe ESD077 De Training at Design Rev Cross Refe ESD077 De Objectives ensure des requiremen Safety Man assessmen Cross Refe HAZ187 Ha | e brief Project requirement sis manual/ FEED rence / Supporting esign Management d competency of views rence / Supporting esign meets specifients magement Study nts rence / Supporting azardous Areas G | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur & other risk ng Documents uidelines for F | 6/6 in place arly :: :: nctionality :: ield | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 .2 .3 | Inadequate Comments defined Design bas Cross Refe ESD077 De Training au Design Rev Cross Refe ESD077 De Objectives ensure des requiremen Safety Man assessmen Cross Refe HAZ187 Ha Instrument | e brief Project requirement Sis manual/ FEED Frence / Supporting esign Management d competency of views Frence / Supporting esign meets specifients magement Study nts Frence / Supporting azardous Areas G mation & Electrical | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur & other risk ng Documents uidelines for F | 6/6 in place arly :: :: nctionality :: ield | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 .2 .3 | Inadequate Comments defined Design bas Cross Refe ESD077 De Design Rev Cross Refe ESD077 De Objectives ensure des requirement Safety Man assessment HAZ187 Ha Instrument Hazop Stud | e brief : Project requirement sis manual/ FEED rence / Supporting esign Management rence / Supporting sign meets specifients magement Study nts rence / Supporting azardous Areas G ration & Electrical dy Guide | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur & other risk ng Documents uidelines for F | 6/6 in place arly :: :: nctionality :: ield | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 .2 .3 | Inadequat Comments defined Design bas Cross Refe ESD077 De Design Rev Cross Refe ESD077 De Objectives ensure des requirement Safety Man assessment Cross Refe HAZ187 Ha Instrument Hazop Stud | e brief Project requirements sis manual/ FEED rence / Supporting esign Management rence / Supporting sign meets specifients nagement Study nts rence / Supporting azardous Areas G ration & Electrical dy Guide : ion on external th | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur & other risk ng Documents uidelines for F Equipment; H | 6/6 in place arly | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | in place contr 1/1 in plac Ø 1/1 in plac Ø 3/3 in plac |
| .1 .2 .3 | Inadequat Comments defined Design bas Cross Refe ESD077 De Design Rev Cross Refe ESD077 De Objectives ensure des requirement Safety Man assessment Cross Refe HAZ187 Ha Instrument Hazop Stud | e brief : Project requirement sis manual/ FEED rence / Supporting esign Management isign meets specified rence / Supporting isign meets specified isign meets specified rence / Supporting azardous Areas G ration & Electrical dy Guide : ion on external the rocess | ents are not cle study report ng Documents nt, f engineers ng Documents nt fication and fur & other risk ng Documents uidelines for F Equipment; H | 6/6 in place arly | Cons 1.1 2.1 3.1 3.2 3.3 | Supply restriction Comments: Breach of comm unable to fulfil delivery requir Alarms to AEMO & GasNet Safety issues Emergency response and procedures Asset integrity issues project close out & lesson Safety devices | ontrols mercial agreement if rements t control rooms pipeline isolation ns learnt | Doc. Control in place control 1/1 in plac 0 1/1 in plac 3/3 in plac |

and testing; PIP299 Purging & Commissioning TP Pipeline: PIP339 Hydrostatic Testing

Actions

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| Risk | RISK ID STATE | | VISION/BUSINESS UNIT/FUNCTION | REGISTER Victorian Pipeline Safety | RISK REVIEW DATE Case 30/11/2019 |
|---------|-------------------------------|-----------|-------------------------------|---------------------------------------|--|
| REATED | AT UPDATED A /2014 04/12/2 | | | | |
| Pigg | ing Operatio | ns - haza | rdous task Inherent | Residual | Control Effectiveness |
| | | | Intern | nediate Low | 4-Satisfactory |
| | | | Security | of Supply Security of S | upply Control Effectiveness |
| | | | Target | | |
| | | | | viele vete d | |
| | | | Not yet | risk rated | |
| LOCATIO | | APPROVE | 3 | risk fateo | |
| | an Transmission Syste | | | risk fateo | |

Doc. Control: 6

2 items 3/3 in place controls

| Cau | 3 items 3/3 565 + Preventing Controls | in place controls |
|-----|---|-------------------|
| 1. | Stuck pig due to lack of flow | 1/1 in place |
| 1.1 | Operating procedure Comments (optional): Specific pigging procedures are developed to pipeline system | ✓ suit the |
| 2. | Stuck pig due to pipe characteristics | 1/1 in place |
| 2.1 | Design of pipeline / pig bars, radius of bends Cross Reference / Supporting Documents: PIP382 Designing Pipelines to Accommodate Intelligent pigging | • |
| 3. | Velocity of pig under pressure could cause damage at catching end | 1/1 in place |
| 3.1 | Pig traps designed to safely catch pig at end operation | lof 🗸 |

Consequences + Mitigating Controls

| 1. | Restriction of supply Comments: If pig is stuck and cannot be retrieved | 1/1 in place |
|-----|--|--------------|
| 1.1 | Pig tracking and pig recovery procedure | ~ |
| 2. | People or property damage Comments: At catching end due to pig under pressure | 2/2 in place |
| 2.1 | Job safety procedures | ~ |
| 2.2 | Emergency response procedures | ~ |
| | | |

Risk Owner Albert Brovedani Praised by Albert Brove

Confidential

Actions

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| YPE lisk | RISK ID 1092 | state Approved | DIVISION/BUSINESS | UNIT/FUNCTION TRE Construct | REGISTER Victor | rian Pipeline Safety Case | RISK REVIEW DATE 30/08/2019 | |
|--------------------|--|--|---|---------------------------------|---------------------------------|--|--|--------------------------|
| | TED AT 07/2014 | UPDATED AT 04/12/2014 | | | | | | |
| Pip | eline le | aks | | Inherent | | Residual | Control Effectiveness | |
| | | | | Intermedi | ate | Low | 4-Satisfactory | |
| | | | | People | • | People | Control Effectiven | 255 |
| | | | | Target | | | | |
| | | | | Not yet risk | rated | | | |
| Activ | status /e | ssion System All | pert Brovedani 1 items 6/6 i | in place controls | Cons | Equences + Mitigating Con | 1 items 7/7 in pla | Doc. Contro ace contr |
| | | | | | | | | |
| | Failure of j | oints, flanges or v | velds | 6/6 in place | 1. | Ignition source & possible f | ire 7 | /7 in plac |
| .1 | - | oints, flanges or v g policies for joint | | 6/6 in place | 1. 1.1 | Ignition source & possible f Emergency response proce | | /7 in plac |
| | Engineerin Cross Refe ESD077 De Area Guide Equipment Transmissi | g policies for joint rence / Supporting esign managemen lines for Field Instr ;; HAZ238 Hazop S on Welding Proces gn; PIP234 Flanges | ing; J Documents: t; HAZ187 Hazard umentation & Ele tudy Guide; PIP1! lures; PIP212 Pip | dous ectrical 55 eline | | | dures ng Documents: ock Out & Tag Out | • |
| | Engineerin Cross Refe ESD077 De Area Guide Equipment Transmissi Valve Desig PIP340 We Objectives Use of mor Avoidance Use of fire | g policies for joint rence / Supporting esign managemen lines for Field Instr ; HAZ238 Hazop S on Welding Procec gn; PIP234 Flanged Iding | ing; g Documents: t; HAZ187 Hazarc umentation & Ele tudy Guide; PIP1! lures; PIP212 Pip l Joints - Installatio ground, | dous ectrical 55 eline | 1.1 | Emergency response proce Isolation Plan Cross Reference / Supportin 320-GD-HS-0001 Isolation L Objectives: Isolate and de-pressurise se | dures ng Documents: ock Out & Tag Out ection of pipeline to lim | it. |
| | Engineerin Cross Refe ESD077 De Area Guide Equipment Transmissi Valve Desig PIP340 We Objectives Use of mor Avoidance Use of fire Use of weld | g policies for joint rence / Supporting esign managemen lines for Field Instr ; HAZ238 Hazop S on Welding Procec gn; PIP234 Flanged Iding : nolithic joints, of split-body valves safe valves above | ing; g Documents: t; HAZ187 Hazarc umentation & Ele tudy Guide; PIP1! lures; PIP212 Pip l Joints - Installatio ground, | dous ectrical 55 eline | 1.1 | Emergency response proce Isolation Plan Cross Reference / Supportin 320-GD-HS-0001 Isolation L Objectives: Isolate and de-pressurise se gas escape & enable repair Pipeline repair plan Objectives: Implement a by-pass to mini | dures ng Documents: ock Out & Tag Out ection of pipeline to lim | it. |
| .1 | Engineerin Cross Refe ESD077 Dd Area Guide Equipment Transmissi Valve Desig PIP340 We Objectives Use of mor Avoidance Use of fire Use of weld Gasket ma | g policies for joint rence / Supporting esign managemen lines for Field Instr ; HAZ238 Hazop S on Welding Procee gn; PIP234 Flanged Iding : nolithic joints, of split-body valves safe valves above ded valves where p | ing; g Documents: t; HAZ187 Hazarc umentation & Ele tudy Guide; PIP1! lures; PIP212 Pip I Joints - Installation ;, ground, practical, ndancy | dous ectrical 55 eline | 1.1 1.2 | Emergency response proce Isolation Plan Cross Reference / Supportin 320-GD-HS-0001 Isolation L Objectives: Isolate and de-pressurise se gas escape & enable repair Pipeline repair plan Objectives: Implement a by-pass to mini build permanent solution | dures ng Documents: ock Out & Tag Out ection of pipeline to lim mise downtime and th eak monitoring & 3 | it. |
| | Engineerin Cross Refe ESD077 D Area Guide Equipment Transmissi Valve Desig PIP340 We Objectives Use of mor Avoidance Use of fire Use of weld Gasket ma Designed f | g policies for joint rence / Supporting esign managemen lines for Field Instr ; HAZ238 Hazop S on Welding Proces gn; PIP234 Flanged Iding : nolithic joints, of split-body valves safe valves above ded valves where p terial selection | ing; g Documents: t; HAZ187 Hazarc umentation & Ele tudy Guide; PIP1! lures; PIP212 Pip I Joints - Installation ground, ground, iractical, ndancy g Documents: | dous ectrical 55 eline | 1.1 1.2 1.3 | Emergency response proce Isolation Plan Cross Reference / Supportin 320-GD-HS-0001 Isolation L Objectives: Isolate and de-pressurise se gas escape & enable repair Pipeline repair plan Objectives: Implement a by-pass to mini build permanent solution Leak identification All metering pits have gas I monthly check of other pits Pipeline awareness | dures ng Documents: ock Out & Tag Out ection of pipeline to lim mise downtime and th eak monitoring & 3 | it |
| .1 | Engineerin Cross Refe ESD077 De Area Guide Equipment Transmissi Valve Desig PIP340 We Objectives Use of mor Avoidance Use of fire Use of weld Gasket ma Designed fi Cross Refe ESD077 De | g policies for joint rence / Supporting esign managemen lines for Field Instr ; HAZ238 Hazop S on Welding Procee gn; PIP234 Flanged Iding : nolithic joints, of split-body valves safe valves above ded valves where p terial selection for isolation / redu | ing; g Documents: t; HAZ187 Hazarc umentation & Ele tudy Guide; PIP1! lures; PIP212 Pip I Joints - Installation g, ground, iractical, ndancy g Documents: es and welded ve tests | dous ectrical 55 eline | 1.1 1.2 1.3 1.4 1.5 | Emergency response proce Isolation Plan Cross Reference / Supportin 320-GD-HS-0001 Isolation L Objectives: Isolate and de-pressurise se gas escape & enable repair Pipeline repair plan Objectives: Implement a by-pass to mini build permanent solution Leak identification All metering pits have gas I monthly check of other pits | dures ng Documents: ock Out & Tag Out ection of pipeline to lim mise downtime and th eak monitoring & 3 | it |

| 1.5 | Quality assurance on production welds Cross Reference / Supporting Documents: ESD085 Product Identification and Traceability; PIP340 Welding | ~ |
|-----|---|---|
| 1.6 | Leak testing during commissioning Cross Reference / Supporting Documents: PIP339 Hydrostatic Testing | ~ |

No items found

Issues

No items found

Learnings

No items found

Assurance Functions / Notes

No items found

Attachments

| Risk | RISK ID 1091 | STATE Approved | division/Business Transmissic | s UNIT/FUNCTION On Operations | REGISTER Victor | ian Pipeline Safety Case | RISK REVIEW DATE 30/08/2019 | |
|----------------|---|--|---|---|--|--|--|---|
| | TED AT 07/2014 | UPDATED AT 04/12/2014 | | | | | | |
| Οv | erpressu | ure | | | | | | |
| | | | | Inherent | | Residual | Control Effectivene | 255 |
| | | | | Intermedi | | Low | 4-Satisfacto | |
| | | | | People | • | People | Control Effectiv | eness |
| | | | | Target | | | | |
| | | | | Not yet risk | rated | | | |
| | | | | | | | | |
| | RIPTION | | | | | | | |
|)ve | rpressure of | downstream syste | m | | | | | |
| OCA | TION | APPRO | IVER | | | | | |
| roc | klyn Compre | ssor Station Albei | t Brovedani | | | | | |
| | STATUS | | | | | | | |
| Activ | ve | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | Doc. Control |
| | | nting Controls | items 14/14 | | | equences + Mitigating Contr | | place contr |
| | Inappropri Operating | nting Controls ate valve operation and maintenance (| n procedures and | 7/7 in place | 1. | Damage to downstream equ Comments: May result in a leaf | rols ipment | place contr |
| | Inappropri Operating training (e | nting Controls ate valve operation and maintenance p specially for contro | n procedures and ol equipment & S | 7/7 in place | 1. (1.1 | Damage to downstream equ Comments: May result in a leal Isolation plans | rols ipment | place contr 1/1 in plac |
| • | Inappropri Operating training (e Cross Refe BCS544 Br | nting Controls ate valve operation and maintenance (specially for contro rence / Supporting rooklyn Compresso | orocedures and ol equipment & S Documents: r Station Operato | 7/7 in place SCADA) | 1. 1. 1.1 1. 2. 1. | Damage to downstream equ Comments: May result in a leak Isolation plans Loss of supply | rols ipment | place contr 1/1 in plac |
| • | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresson CS023 Gooding Cor | n procedures and ol equipment & S Documents: r Station Operato npressor Station | 7/7 in place SCADA) | 1. 1 1.1 1 2. 1 | Damage to downstream equ Comments: May result in a lead Isolation plans Loss of supply Repair procedures | rols ipment | place contr 1/1 in plac 1/1 in plac |
| | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Competent | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manag | orocedures and ol equipment & S Documents: r Station Operato npressor Station bual; MAN236 gement; WCG27 | 7/7 in place SCADA) | 1. 1 1.1 1 2. 1 3. 2 | Damage to downstream equ Comments: May result in a lead Isolation plans Loss of supply Repair procedures Safety issue | rols ipment | place contr 1/1 in plac 1/1 in plac |
| | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Competent Operating a | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresso CS023 Gooding Cor & Maintenance Mar cy & Training Manag & Maintenance mar | orocedures and ol equipment & S Documents: r Station Operato npressor Station bual; MAN236 gement; WCG27 | 7/7 in place SCADA) | 1. 1. 1.1 1 2. 1 2.1 1 3. 2 3.1 1 | Damage to downstream equ Comments: May result in a lead Isolation plans Loss of supply Repair procedures | rols ipment < ures | place contr 1/1 in plac 1/1 in plac |
| | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Competent Operating a Objectives | nting Controls ate valve operation and maintenance (specially for contro rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manae & Maintenance mar | orocedures and ol equipment & S Documents: r Station Operato npressor Station bual; MAN236 gement; WCG27 | 7/7 in place SCADA) | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 | Damage to downstream equ Comments: May result in a lead Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced | rols ipment ures g Documents: | place contr 1/1 in plac 1/1 in plac |
| | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Competent Operating a Objectives | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresso CS023 Gooding Cor & Maintenance Mar cy & Training Manag & Maintenance mar | orocedures and ol equipment & S Documents: r Station Operato npressor Station bual; MAN236 gement; WCG27 | 7/7 in place SCADA) | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |
| 1 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Competen Operating a Objectives Pipeline is o Liaise with | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresso CS023 Gooding Cor & Maintenance Mar cy & Training Manay & Maintenance mar : operated by AEMO | Documents: Station Operator Pressor Station Jual; MAN236 gement; WCG27 Jual - Wollert | 7/7 in place SCADA) | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equi Comments: May result in a lead Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Manage | ipment < ures g Documents: ment Manual | place contr 1/1 in plac 1/1 in plac |
| 1 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating & Operating & Objectives Pipeline is o Liaise with Cross Refe | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresso CS023 Gooding Cor & Maintenance Mar cy & Training Manag & Maintenance mar : operated by AEMO | Documents: Station Operator Pressor Station Jual; MAN236 gement; WCG27 Jual - Wollert | 7/7 in place SCADA) Or's 1 76 | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |
| 1 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Competen Operating a Objectives Pipeline is o Liaise with Cross Refe Service Env | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compresso CS023 Gooding Cor & Maintenance Mar cy & Training Manag & Maintenance mar : operated by AEMO supplier / AEMO prence / Supporting | Documents: Station Operator Nual; MAN236 gement; WCG27 Nual - Wollert | 7/7 in place | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contr 1/1 in plac 1/1 in plac |
| 2 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Operating a Objectives Pipeline is o Liaise with Cross Refe Service Env 24 hour ma | nting Controls ate valve operation and maintenance p specially for contro rence / Supporting rooklyn Compressou CS023 Gooding Cor & Maintenance Mar cy & Training Manag & Maintenance mar : operated by AEMO supplier / AEMO rence / Supporting velope Agreement | Documents: Station Operator Documents: Station Operator Documents: MAN236 gement; WCG27 Dual - Wollert Documents: | 7/7 in place | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | Doc. Control: place control 1/1 in plac 1/1 in plac 1/1 in plac |
| 2 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Operating a Objectives Pipeline is Liaise with Cross Refe Service Erm 24 hour ma alarms Overpress | nting Controls ate valve operation and maintenance p specially for control rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manae & Maintenance mar : operated by AEMO rence / Supporting velope Agreement anned control room ure protection systemets arence / Supporting | Documents: Documents: Station Operator Station Operator pressor Station pual; MAN236 gement; WCG27 pual - Wollert Documents: with overpress cems Documents: | 7/7 in place SCADA) Or'S 76 | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |
| au: 1 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Objectives Pipeline is Cross Refe Service Env 24 hour ma alarms Overpress Cross Refe ESD077 De | nting Controls ate valve operation and maintenance p specially for control rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manag & Maintenance mar : operated by AEMO rence / Supporting velope Agreement anned control room ure protection systemet | Documents: Documents: Station Operator Station Operator pressor Station pual; MAN236 gement; WCG27 pual - Wollert Documents: swith overpress cems Documents: STD222 Standa | 7/7 in place SCADA) or's 76 Sure or's ard for | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |
| 2 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Objectives Pipeline is Cross Refe Service Env 24 hour ma alarms Overpress Cross Refe ESD077 De pressure R | nting Controls ate valve operation and maintenance p specially for control rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manae & Maintenance mar : operated by AEMO rence / Supporting velope Agreement anned control room ure protection systemets rence / Supporting esign Managements | Documents: Station Operator Station Operator Station Operator pressor Station pual; MAN236 gement; WCG27 pual - Wollert Documents: Station Operator with overpress Station Operator Station Operator | 7/7 in place SCADA) or's 76 76 sure or v | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |
| 1 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Objectives Pipeline is Liaise with Cross Refe Service Env 24 hour ma alarms Overpress Cross Refe ESD077 De pressure R Critical valu | nting Controls ate valve operation and maintenance p specially for control rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manae & Maintenance mar : operated by AEMO rence / Supporting velope Agreement anned control room ure protection systemets rence / Supporting esign Management; tegulating Facility - I ves that could cause i dentified rence / Supporting | Documents: Station Operator Station Operator Station Operator pressor Station pressor | 7/7 in place SCADA) or's 76 Sure Image: Sure of the second | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |
| .1 .2 .3 | Inappropri Operating training (e Cross Refe BCS544 Br Manual; GC Operating a Objectives Pipeline is Liaise with Cross Refe Service Env 24 hour ma alarms Overpress Cross Refe ESD077 De pressure R Critical value locked and Cross Refe | nting Controls ate valve operation and maintenance p specially for control rence / Supporting rooklyn Compresson CS023 Gooding Cor & Maintenance Mar cy & Training Manage & Maintenance mar : operated by AEMO a supplier / AEMO rence / Supporting velope Agreement anned control room ure protection systemets rence / Supporting esign Managements tegulating Facility - I ves that could cause I identified | Documents: Station Operator Station Operator Station Operator pressor Station pressor | 7/7 in place SCADA) or's 76 76 sure ard for ruction are all Valves; | 1. 1 1.1 1 2. 1 2.1 1 3. 2 3.1 1 0 1 | Damage to downstream equ Comments: May result in a leaf Isolation plans Loss of supply Repair procedures Safety issue Emergency response proced Cross Reference / Supporting EME020 Emergency Managel Objectives: Minimise any consequence o | ipment < ures g Documents: ment Manual | place contro 1/1 in plac 1/1 in plac |

| 1.6 | Design of pipeline system | ~ |
|-----|---|----------|
| 1.7 | Work instructions Objectives: Work instruction are issued within the maintenance scheduling system and permitting / JHA requirements are in place for performance of the work | 5 |
| 2. | Failure of valves to operate when required 7/7 | in place |
| 2.1 | Methodology and philosophy for system design (Design Basis Manual) Cross Reference / Supporting Documents: | ~ |
| | ESD077 Design Management; ESD110 Project Management; STD222 Standard for Pressure Regulating facility - Design & construction | |
| 2.2 | Maintain SCADA and equipment to isolate and emergency shutdown / failsafe | ~ |
| | Cross Reference / Supporting Documents: BCS544 Brooklyn Compressor Station Operator's Manual; GCS023 Gooding Compressor Station Operating & Maintenance Manual; PIP286 Pipeline Valves - Inspection Operation and Maintenance; PIP269 Regulator & Over Pressure Protection Systems - Inspection Operation & maintenance Procedure; WCG276 Operating & Maintenance manual - Wollert | |
| 2.3 | Alarms to AEMO & GasNet control rooms | 0 🗸 |
| 2.4 | 24 hour manned control room with overpressure alarms | Ø 🗸 |
| 2.5 | Change Management procedures Cross Reference / Supporting Documents: MAN232 Change Management | ~ |
| 2.6 | Maintenance program on assets | ~ |
| 2.7 | 5 yearly safety management study | 0 🗸 |
| | Cross Reference / Supporting Documents: HAZ238 Hazop study guide | |

| No items found | | |
|----------------|--|--|
| Issues | | |
| No items found | | |
| Learnings | | |
| No items found | | |

Assurance Functions / Notes

No items found

Attachments

| TYPE Risk | RISK ID 1085 | STATE Approved | DIVISION/BUSINESS UN | NIT/FUNCTION Strategy & En | ngineeı | REGISTER Victorian Pipeline Sa | afety Case | RISK REVIEW DATE 30/11/2019 |
|--------------|---|---|---|--------------------------------|---|--|--|--|
| | TED AT 07/2014 | UPDATED AT 04/12/2014 | | | | | | |
| Le | gislative | / regulatory | change - fa | ilure to cor | mply | | | |
| | | | I | nherent | | Residual | Control Effecti | |
| | | | | Intermediat | | Low | 4-Satisf | - |
| | | | | Security of Su | ipply | Security of Supply | Control Effe | ectiveness |
| | | | ו | Target | | | | |
| | | | | Not yet risk ra | ated | | | |
| | | | | | | | | |
| | Failure to change Comments | nting Controls recognise material : Positive regulatory of | - | place controls 6/6 in place | Cons 1. | EQUENCES + Mitigating Con Legal prosecution and fine: Comments: Legislation specif regulatory breaches | itrols s | Doc. Control 5 in place contro 2/2 in plac |
| L. | Failure to a change Comments missed | recognise material | legislative | 6/6 in place | 1. | Legal prosecution and fine Comments: Legislation specif | itrols s | 5 in place contro |
| | Failure to r change Comments missed Subscription news servit Objectives Access to o | recognise material Positive regulatory of to legal and Sta ces | legislative obligation is ndards update an | 6/6 in place | 1. 1.1 1.2 | Legal prosecution and fine Comments: Legislation specif regulatory breaches | ntrols s ies penalties for ument for specified for achieving and Standards | 5 in place contro 2/2 in plac Ø fying |
| 1 | Failure to in change Comments missed Subscription news servit Objectives Access to of including con- regulatory Objectives ESV issue of | recognise material Positive regulatory of to legal and Sta- ces changed legislation onsultation phase ntact and briefing authorities guideline documen | legislative obligation is ndards update an and Standards with relevant tation on material | 6/6 in place | 1. 1.1 1.2 | Legal prosecution and fine Comments: Legislation specif regulatory breaches Internal auditing program Safety Case is the key docu procedures and actions use compliance to Regulations Objectives: | atrols s ies penalties for ument for specified for achieving and Standards d to achieve cor ly only occur in e wilful negligent | 5 in place contro 2/2 in plac Ø fying |
| 1 | Failure to r change Comments missed Subscription news servit Objectives Access to of including con- Regular co- regulatory Objectives ESV issue of issues to a submission | recognise material Positive regulatory of to legal and Sta- ces Changed legislation onsultation phase ntact and briefing authorities guideline documen ssist Licensee's co of documentation ations will likely trig | legislative obligation is ndards update an and Standards with relevant tation on material mpliance with . Changes to Pipel | 6/6 in place | 1.1 1.2 2. 2.1 | Legal prosecution and fine Comments: Legislation specif regulatory breaches Internal auditing program Safety Case is the key docu procedures and actions use compliance to Regulations Objectives: Provides key measures use Loss of operating licence Comments: this would possib severe circumstances or where | atrols s ies penalties for ument for specified for achieving and Standards d to achieve cor ly only occur in e wilful negligent is take place ng Documents: | 5 in place contro 2/2 in plac Ø fying mpliance 2/2 in plac |
| 1 | Failure to r change Comments missed Subscription news servit Objectives Access to of including con- Regular cor regulatory Objectives ESV issue of issues to a submission Act / Regula Safety Case APA complit Objectives | recognise material Positive regulatory of the legal and Sta- ces thanged legislation posultation phase ntact and briefing authorities guideline document ssist Licensee's co the of documentation ations will likely trigger. | legislative obligation is ndards update an and Standards with relevant tation on material mpliance with . Changes to Pipel ger a change to th | 6/6 in place | 1.1 1.2 2.1 | Legal prosecution and fine: Comments: Legislation specif regulatory breaches Internal auditing program Safety Case is the key docu procedures and actions use compliance to Regulations Objectives: Provides key measures use Loss of operating licence Comments: this would possib severe circumstances or where conduct or repeated breaches Stakeholder relationship Cross Reference / Supportin | strols s ies penalties for ument for specified for achieving and Standards d to achieve cor ly only occur in e wilful negligent take place ng Documents: ents | 5 in place contro 2/2 in plac gring mpliance 2/2 in plac |
| L. | Failure to r change Comments missed Subscription news servit Objectives Access to of including con- Regular co- regulatory Objectives ESV issue of issues to a submission Act / Regula Safety Case APA complit Objectives Consultation | recognise material recognise material Positive regulatory of the legal and Sta- ces changed legislation posultation phase ntact and briefing authorities guideline documen ssist Licensee's co of documentation ations will likely trig- ance team meeting | legislative obligation is ndards update an and Standards with relevant tation on material mpliance with . Changes to Pipel ger a change to th gs ff on changing | 6/6 in place nd 🖌 | 1.1 1.2 2.1 | Legal prosecution and fine: Comments: Legislation specif regulatory breaches Internal auditing program Safety Case is the key docu procedures and actions use compliance to Regulations Objectives: Provides key measures use Loss of operating licence Comments: this would possib severe circumstances or where conduct or repeated breaches Stakeholder relationship Cross Reference / Supportin Regulator guideline docume Objectives: Regular meetings and corre regulators to ensure expect Resourcing of professional regulatory requirements an | atrols s ies penalties for ument for specified for achieving and Standards d to achieve cor ly only occur in e wilful negligent is take place ng Documents: ents espondence with ations are unde staff to advise nd technical/ope | 5 in place control 2/2 in plac fying mpliance 2/2 in plac Ø v rstood |
| 1 | Failure to r change Comments missed Subscription news servit Objectives Access to of including of Regular cor regulatory Objectives ESV issue of issues to a submission Act / Regul Safety Case APA complit Objectives Consultation legislative r | recognise material Positive regulatory of the legal and Sta- ces thanged legislation posultation phase ntact and briefing authorities guideline documen ssist Licensee's co of documentation ations will likely trig- ance team meeting in amongst key sta | legislative obligation is ndards update an and Standards with relevant tation on material mpliance with . Changes to Pipel ger a change to th gs ff on changing nsistency of proce | 6/6 in place nd 🖌 | 1.1 1.2 2.1 | Legal prosecution and fine: Comments: Legislation specific regulatory breaches Internal auditing program Safety Case is the key docu- procedures and actions used compliance to Regulations Objectives: Provides key measures user Loss of operating licence Comments: this would possibil severe circumstances or where conduct or repeated breaches Stakeholder relationship Cross Reference / Supportin Regulator guideline docume Objectives: Regular meetings and corre regulators to ensure expect Resourcing of professional regulatory requirements an staff to ensure requirements | atrols s ies penalties for ument for specified for achieving and Standards d to achieve cor ly only occur in e wilful negligent is take place ng Documents: ents espondence with ations are under staff to advise ng technical/opents ts are met | 5 in place control 2/2 in plac fying mpliance 2/2 in plac Ø v rstood |
| 1 | Failure to r change Comments missed Subscription Personal formation Objectives Access to of including of Regular cor regulatory Objectives ESV issues to a submission Act / Regul Safety Case APA complit Objectives Consultation legislative in | recognise material Positive regulatory of the legal and Sta- ces thanged legislation posultation phase mtact and briefing authorities guideline document ssist Licensee's co the of documentation ations will likely trigger ance team meeting in amongst key sta- equirements for co | legislative obligation is ndards update an and Standards with relevant tation on material mpliance with . Changes to Pipel ger a change to th gs ff on changing nsistency of proce | 6/6 in place nd 🖌 | 1.1 1.2 2.1 | Legal prosecution and fine: Comments: Legislation specif regulatory breaches Internal auditing program Safety Case is the key docu procedures and actions use compliance to Regulations Objectives: Provides key measures use Loss of operating licence Comments: this would possib severe circumstances or where conduct or repeated breaches Stakeholder relationship Cross Reference / Supportin Regulator guideline docume Objectives: Regular meetings and corre regulators to ensure expect Resourcing of professional regulatory requirements an | atrols s ies penalties for ument for specified for achieving and Standards d to achieve cor ly only occur in e wilful negligent is take place ng Documents: ents espondence with ations are under staff to advise ng technical/opents ts are met | 5 in place control 2/2 in plac fying mpliance 2/2 in plac Ø v rstood |

| 3. | Reputational impacts Comments: Could cause added layer of complication in regard to approval applications | 1/1 in place |
|-----|---|--------------|
| 3.1 | Stakeholder relationship Cross Reference / Supporting Documents: Regulator guideline documents Objectives: Regular meetings and correspondence with regulators to ensure expectations are understa | Ø ✔ |
| 4. | Delays in receiving operational consent | 0/0 in place |

| No items found | |
|----------------|--|
| Issues | |
| No items found | |
| Learnings | |
| No items found | |

Assurance Functions / Notes

| ID | Comment/Note | Owner | Created at |
|----|--|------------------|-------------------------|
| 1 | Internal auditing program is designed to pick up key legislative / AS2885 requirements as they relate to the Safety Case or Pipeline Management System | Albert Brovedani | 21/Jul/2014 14:28 PM |

Attachments

| No Attachments found | |
|----------------------|--|
| | |



ENVIRONMENTAL RISK ASSESSMENT

REPORT

TRANSMISSION – VICTORIA

HSE Group

Alice Rawlinson Environment Manager

16 April 2014



Table of Contents

| 1. | Executive summary | 3 |
|-----|--|---|
| 2. | Introduction | 3 |
| 3. | Background | 3 |
| 4. | Scope of works | 3 |
| 5. | Methodology | 4 |
| 6. | Risk assessment | |
| 7. | Attendees | 4 |
| | 7.1 Risk register7.2 Recommendations | 5 |
| | 7.2 Recommendations | 5 |
| | 7.1 Limitations | 5 |
| 8. | Review | 5 |
| 9. | Definitions | 5 |
| 10. | Appendix 1 - APA Environmental Risk Matrix | 6 |
| 11. | Appendix 2 – Victoria Transmission : Environmental Risk Register | 9 |



1. Executive summary

This report presents the findings from the March 2014 environmental risk assessment workshop conducted on activities associated with APA's transmission business in Victoria.

Only environmental risks were considered in the risk assessment (i.e. other risks such as those affecting reputation, personnel and financial were excluded).

The workshop was conducted in accordance with the Terms of Reference document.

General environmental aspects were evaluated as well as aspects associated with specific activities.

Of the 40 items considered:

- 3 risks were considered to be not credible
- 0 residual risks were assessed to be extreme
- 1 residual risk was assessed to be high; and
- 9 residual risks were assessed to be moderate.

Although the majority of risks were ranked low and moderate, a number of action items were identified. All risks and actions for close out should be subject to ongoing review and monitoring by APA.

2. Introduction

This report describes the environmental risk assessment for the Victorian transmission business. The workshop was held at the APA office in Dandenong on March 16, 2014. This report details the scope of work, methodology applied and the workshop results and findings.

The workshop was conducted in accordance with the workshop Terms of Reference.

3. Background

APA own and/or operate assets in multiple Australian states. There are inherent risks associated with APA's activities (i.e. operations, maintenance, construction, commissioning and general personnel activities in the office and field) as well as risks related to pipeline contents. It is those risks that have the potential to lead to environmental impacts that are of relevance to this assessment.

Environmental risk assessments are being conducted across transmission, networks and infrastructure development within APA, allowing the business to:

- Better understand its environmental risk profile;
- Develop a more rigorous basis for strategic planning;
- Improve compliance with relevant legislation;
- Manage proactively rather than reactively;
- Continually improve on environmental performance; and
- Operate with greater openness and transparency with environmental decision making.

4. Scope of works

The scope of this workshop was to consider the aspects and impacts associated with APA's activities identified in section 3.

Specifically included in the scope of works are all environmental issues, including land access and cultural heritage.

Specifically excluded are occupational health and safety issues, reputational, security and financial implications.

5. Methodology

safequard

The risk assessment process applied was consistent with ISO 14001:2004 Environmental Management Systems, ISO 31000:2009 Risk Management Systems and AS2885 the Australian Pipeline Standard.

The workshop considered the cause/aspect, impact, assessment and mitigation measures.

A summary of the process is as follows:

- Review of workshop purpose, scope, objectives and stakeholders;
- Identify activities, cause, aspects and impacts using existing list and brainstorming;
- Evaluate the likelihood and consequence of each risk to determine a risk ranking;
- Treat the risk by identifying existing and additional control or mitigating measures;
- Re-evaluate the risk to determine a residual risk ranking; and
- Assign actions and actionees person/people accountable for closing out actions.

6. Risk assessment

Risk rankings were assigned to consequence and likelihood using the APA risk matrix shown in Appendix 1.

In assigning a level of likelihood, the working group took into consideration the likelihood of the consequence being realised given the existing controls in place. The risk matrix likelihood criteria includes both quantitative and qualitative wording and both were used to help guide the assignment of a relevant frequency/likelihood to the identified consequence.

Consequence and likelihood were combined to produce an estimated level of risk associated with a particular hazardous activity.

7. Attendees

The following employees attended the risk assessment:

- Albert Brovedani Technical Regulations Manager
- Alice Rawlinson Environment Manager
- Andrew Adams Manager Measurement
- Brynne Jayatilaka Environment Officer
- Carlo Corso Operations Support Manager
- Darren Flaus Manager Field Services South East
- Ian Johnson Regional Manager Gippsland
- Shane Matthews Regional Manager Otways

The following employees attended to provide input regarding risks associated with weeds and cultural heritage:

Colin Mason – Lands Projects Coordinator



• Melissa Dunk – Team Leader, Land Services

7.1 Risk register

The results of the workshop have been documented in the risk register, attached (refer to Appendix 2).

7.2 Recommendations

A number of actions were recommended by the workshop team, as contained in the risk register.

Recommendations (or actions) fall into 2 categories:

- 1. The risk was deemed to be low but an action was raised to clarify or re-enforce some aspect.
- 2. The risk was deemed to be too high and so an action was raised in direct relation to reducing the risk rating.

It is recommended that all actions be closed out prior to the next review.

7.1 Limitations

The risk assessment did not consider reputational and financial impacts as a result of environmental legislative and license non-compliance, which means the risk register is not exhaustive

8. Review

A review of this risk register should occur within 2 years (as a minimum) or as required (e.g. following an incident, legislative or license non compliance, or material system change).

9. Definitions

| Term | Definition |
|--|---|
| Hazard | The potential of something to cause harm. |
| Aspect | Feature of an activity which interacts with the environment and has the potential to result in impact (e.g. oil spill) or is currently occurring. |
| Impact | Potential changes to the environment resulting from the aspect (e.g. soil contamination) |
| Significant environmental aspect | Aspects of particular significance to an organisation, based on risk ranking, compliance risks and business values. |



10.Appendix 1 - APA Environmental Risk Matrix

| | | | | CONSEQUENCE Degree of Potential Harm | | | | | | | | | | | | | |
|--|--|---------------|--|---|---|--|---|---|--|--|--|--|--|--|--|--|--|
| | | Environment | Limited effect of low significance to minimal area | Short-term temporary impairment to localised area | Prolonged but reversible impairment to localised area and does not affect ecosystem function | Uncontrolled, long term but reversible impairment to localised area and does not affect ecosystem function | Uncontrolled, long term but reversible environmental impairment of ecosystem function | Uncontained, long term serious environmental degradation OR permanent impairment to ecosystem function. | | | | | | | | | |
| | Description | Descriptor | Insignificant -1 | Minor -2 | Medium -3 | Significant -4 | Major -5 | Catastrophic -6 | | | | | | | | | |
| sure, | Is currently occurring, or will almost definitely occur | Frequent -6 | Low (7) | Moderate (13) | High (21) | Extreme (31) | Extreme (33) | Extreme (36) | | | | | | | | | |
| HOOD Frequency of exposure, evidence | Can be expected to occur in most circumstances | Likely -5 | Low (6) | Moderate (12) | High (20) | High (24) | Extreme (32) | Extreme (35) | | | | | | | | | |
| | Can be expected to occur in certain circumstances | Occasional -4 | Low (5) | Low (10) | Moderate (16) | High (23) | High (27) | Extreme (34) | | | | | | | | | |
| LIKELI Probability, Historica | May occur in certain circumstances | Possible -3 | Negligible (3) | Low (9) | Moderate (15) | High (22) | High (26) | High (30) | | | | | | | | | |
| Possibility, F | Not expected to occur but may occur in abnormal circumstances | Unlikely -2 | Negligible (2) | Low (8) | Moderate (14) | Moderate (18) | High (25) | High (29) | | | | | | | | | |
| | Conceivable but only in exceptional circumstances | Rare -1 | Negligible (1) | Negligible (4) | Low (11) | Moderate (17) | Moderate (19) | High (28) | | | | | | | | | |

Risk Matrix Supplementary Information

Likelihood Descriptions

safeguard

| Likelihood Descriptor | Likelihood Description | Likelihood Explanation |
|--------------------------|---|---|
| Rare | Conceivable but only in exceptional circumstances | Either is not known to have occurred or has not occurred in many 'exposures' to the potential risk. |
| Unlikely | Not expected to occur but may occur in abnormal circumstances | Aware that the event has occurred occasionally either within APA or externally. However, it is not something that would be classed as a common occurrence and would only occur in certain remote circumstances. |
| Possible | May occur in certain circumstances | Occurs either within APA or known environment on an irregular basis but frequently enough to be more than a remote possibility. |
| Occasional | Can be expected to occur in certain circumstances | Knowledge/evidence either within APA or externally suggests this event/risk occurs occasionally from time to time but not regularly. |
| Likely | Can be expected to occur in most circumstances | Knowledge/evidence either within APA or externally suggests this event/risk occurs at regular intervals. |
| Frequent | Is currently occur ring, or will almost definitely occur | Knowledge/evidence either within APA or externally suggests this event/risk occurs almost all of the time. The occurrence of this risk is common and expected. |

Consequence – Environment Descriptions

| Consequence Environment Descriptor | Consequence Description - Environment | Consequence – Environment Explanation |
|--|--|--|
| Insignificant | Limited effect of low significance to minimal area | Short-term (less than 12 months) temporary impairment to the biological or physical environment of a very localised area (<0.1ha). Isolated, easily contained, minor harm e.g. noise complaint. |
| Minor | Short-term temporary impairment to localised area | Temporary short-term (< 12 months) impairment to the biological or physical environment of a very localised area (<0.1ha) |
| Medium | Prolonged but reversible impairment to localised area and does not affect ecosystem function | Prolonged (more than 12 months but less than 2 years) reversible impairment to the biological or physical environment of a localised area (<1ha) which is easily rectified and which does not affect ecosystem function. |
| Significant | Uncontrolled, long term but reversible impairment to localised area and does not affect ecosystem function | An uncontrolled off-site release or event resulting in reversible prolonged (more than 2 years but less than 5 years) impairment to the environment but which does not affect ecosystem function. |
| Major | Uncontrolled, long term but reversible environmental impairment of ecosystem function | An uncontrolled off-site release or event in wide area resulting in reversible long-term environmental impairment of ecosystem function. |
| Catastrophic | Uncontained, long term serious environmental degradation OR permanent impairment to ecosystem | Uncontained, long-term serious environmental degradation OR permanent impairment to ecosystem function or habitat. |



function.

Risk Management Action Descriptions

| Risk Level | Description | Key Actions |
|------------|-----------------|---|
| Extreme | Extreme risk | Do not proceed with work. Immediate action required to mitigate or reduce risk to ALARP. If not reasonably practicable to do so all appropriate control measures must be applied and risk escalated to Executive Group Manager of the relevant business for resolution before work starts. Monitor changes which could affect the risk classification. |
| High | High risk | Do not proceed with work without management approval. Immediate action required to mitigate or reduce risk to ALARP. If not reasonably practicable to do so all appropriate control measures must be applied and risk escalated to General Manager of the relevant business for approval to proceed and/or resolution before work starts. Monitor changes which could affect the risk classification. |
| Moderate | Moderate Risk | Work can proceed once supervisor has confirmed process has been adequately followed and risk controls identified and implemented. Management instructions must be specified before work commences and must be followed. Proper diligence must be exercised and reasonable steps / precautions must be taken to ensure the risk level is controlled to as low as reasonably practicable. Periodic monitoring required. |
| Low | Low risk | Manage by routine plans and procedures. Proper diligence must be exercised and reasonable steps / precautions must be taken to ensure the risk level is controlled to as low as reasonably practicable. Monitor changes which could affect the risk classification. |
| Negligible | Negligible Risk | |



11.Appendix 2 – Victoria Transmission : Environmental Risk Register

| Activity | Sub-Activity | Cause | Aspect | Impact | Cred (Y/N) | | | | Existing controls | Residual Risk Analysis | | k | Action | Actionee | Remarks |
|----------------------------------|---|--|-----------------------------------|--|---------------|---|---|-----------|--|------------------------------|---|-----------|---|--------------------|--|
| | | | | | | L | С | RR | | L | С | RR | | | |
| General | | | | | | | | | | | | | | | |
| General - driving vehicles | Driving on easement and off road only | Service vehicles contaminated with weeds accessing easement e.g. off road (APA and Sea Gas) | Weeds | * Remnant vegetation destruction * loss of native flora * ecosystem impacts * public complaints. * Water quality and catchment related impacts * loss to agricultural productivity * erosion issues | Y | 5 | 4 | 24 (H) | OEMP CEMP's Weed spray training Stakeholder interaction (councils) Limited easement driving Weed identification material | 3 | 3 | 15 (M) | * Review spread/location of existing noxious weeds * OEMP review * Review existing weed management procedures and manuals * Improve training and awareness (implementation) | HSE and HELM | * Limited easement driving * Impacts largely to agricultural productivity and landowners |
| | | | Disease (bovine disease) | * agricultural productivity * community * fauna impacts | Y | 3 | 4 | 22 (H) | OEMP CEMP Public signage Process (SEA Gas) e.g. animal awareness | 3 | 4 | 22 (H) | * Review spread/location (Colin Mason and Andrew Mills) * OEMP review * Review existing procedures * Improve training and awareness | HSE and HELM | West of Portland |
| | | Accidental collision with fauna/livestock | Fauna fatalities | * loss of protected fauna and livestock | Y | 6 | 1 | 07 (L) | Shu roo Driver training | 6 | 1 | 07 (L) | | | |
| | | Pipeline survey/maintenance | Soil erosion and compaction | Loss of topsoil, compaction, formation of erosion channels, disturbance of vegetation | Y | 2 | 2 | 08 (L) | N/A | 2 | 2 | 08 (L) | Soil integrity procedures | HSE | |



| - | | | | | | | | | | | | | | | |
|-----------------------|-----|--|--------------------------------------|--|---|---|---|-----------|---|---|---|-----------|---|------|--|
| | | Vehicle exhausts | Emissions | localised air quality and GHG emissions, community | Y | 6 | 1 | 07 (L) | Vehicle maintenance and replacement program Vehicle selection criteria Risk assessment (safeguard requirement) | 6 | 1 | 07 (L) | | | |
| | | No cultural heritage assessment and employee / contractor awareness; inadvertent disturbance | Cultural and European heritage | * Cultural heritage disturbance * Loss of heritage value * Community complaints | Y | 2 | 3 | 14 (M) | OEMP | 2 | 3 | 14 (M) | * Cultural heritage procedures * Training and awareness * Alignment sheets | HSE | |
| General - hot work | N/A | Smoking, welding, grinding, vehicles and machinery, flaring (Regional/paddock/ vegetated areas) | Uncontrolled fire | * Flora and fauna * Biodiversity * Habitat * Agriculture and productivity * Community/landown ers | Y | 4 | 5 | 27 (H) | Permit to work JHA/hot work Procedures Fire response training Emergency response training Competent personnel Fire response equipment (water trailer etc.) Fire services notification and/or attendance High fire danger period permits requests Corporate HSE inductions | 1 | 5 | 19 (M) | * Review fire break requirements | HELM | |

| APA Safeguard | | | | | | | | | | | | | | | |
|--|---|--|-------------------------------------|---|---|---|---|-----------|---|---|---|-----------|---|-----|---|
| | | Smoking, welding, grinding, vehicles and machinery, flaring (facility/stations) | Uncontrolled fire | * Flora and fauna* Biodiversity* Habitat* Agriculture and productivity* Community* Pollution/emissions | Y | 2 | 4 | 18 | Permit to work JHA/hot workProcedures Fire response training Emergency response training Competent personnel Fire response equipment (water trailer etc.) Fire services notification and/or attendance High fire danger period permits | 1 | 5 | 19 (M) | | | Refer to Station Design Hazops, Hazard Registers. |
| O&M - Compressor, MLV and Meter Station General Operation and Management | And Maintenance Vehicle/people movements | * Personnel unaware of cultural heritage site significance * Inadvertent contact with site * Deliberate contact with site * Grading of ROW * Lack of baseline data | Cultural heritage disturbance | * Cultural heritage disturbance * Loss of heritage value * Community complaints | Y | 2 | 3 | 14 (M) | OEMP | 2 | 3 | 14 (M) | * Cultural heritage procedures * Training and awareness * Alignment sheets | HSE | |
| | Ground breaking maintenance activities | * People unaware of site significance * Inadvertent contact * Deliberate contact * Grading of ROW | Cultural heritage disturbance | * Cultural heritage disturbance * Loss of heritage value * Community complaints | Y | 3 | 3 | 15 (M) | National Excavation Procedure and Guidelines Implementation (training and awareness) National Working Group (communication) OEMP | 2 | 3 | 14 (M) | * Review existing Excavation Procedure to account for approvals * Implementation of procedure | HSE | |



| | | | | | | | | | A33C33IIICIIL | | | | | | |
|-----|--------------------------------|--|---|--|---|---|---|-----------|---|---|---|-----------|---|--------------------|--|
| | | ROW disturbance | Recontourin g of waterway banks, erosion | Sedimentation, drainage, compaction, waterway turbidity/ecosystems | Y | 3 | 3 | 15 (M) | Management of transmission pipeline easements Excavation Procedure (not adequately implemented) OEMP General awareness | 2 | 3 | 14 (M) | * Development of or improvement of environmental procedures (water and soil management) * Improved training and awareness of existing procedure * Additional corporate training/awareness * Identify competencies | HSE | |
| | egetation anagement | Slashing, clearing and pruning of ROW | Loss of local flora and fauna | Habitat, biodiversity, protected species, migratory species. | Y | 5 | 1 | 06 (L) | OEMP General awareness | 5 | 1 | 06 (L) | * Review Victorian regulations * Develop Vegetation procedures * Training | HSE and HELM | |
| exc | peline cavation tivities | Inadequate restoration of soil profile, inadequate containment of top or subsoil | Loss of top soil/incorrect managemen t soil profile | Impacts to vegetation and soil integrity. | Y | 5 | 2 | 12 (M) | National Excavation Procedure and Guidelines Implementation (training and awareness) Pipeline awareness (See above) | 2 | 2 | 08 (L) | | | |
| | | Open excavation | Fauna disturbance, entrapment of fauna in trench and pipe, | Fauna fatalities (livestock and native fauna) | Y | 2 | 1 | 02 (N) | National Excavation Procedure and GuidelinesOEMP | 2 | 1 | 02 (N) | | | |
| | | Grit /sand blasting operations | Noise/vibrati on and dust | Community concerns | Y | 1 | 1 | 01 (N) | Use of plastic lining to prevent dispersal | 1 | 1 | 01 (N) | | | |



| | | | | E11 | 111011 | mone | ui i tioi | Assessment | | | | | | |
|---|--|--|---|-----|--------|------|-----------|---|---|---|-----------|---|--------------------|--|
| | | Debris | Soil contamination | Y | 6 | 1 | 07 (L) | Plastic lining to contain debris Canopy to prevent dispersal for coal tar Licenced carriers for waste removal | 6 | 1 | 07 (L) | | | |
| | Backfill inadequately compacted, backfill material inappropriate (DIG UPS) | Soil managemen t (inversion, subsidence and compaction) | Erosion channels, vegetation regrowth (grass, aesthetics, community/landown er complaints | Y | 4 | 3 | 16 (M) | Excavation Procedure and Guidelines OEMP Patrolling and monitoring Landowner liaison erosion control structures | 2 | 2 | 08 (L) | * Soil integrity procedures to reference Excavation Procedure. * Training and awareness of soil integrity issues | HSE and HELM | |
| | | Drainage to waterways | Surface water (creeks, streams) - increased sedimentation, turbidity, aquatic ecosystems | Y | 3 | 3 | 15 (M) | Excavation Procedure and Guidelines OEMP Patrolling and monitoring Landowner liaison Sediment control structures | 2 | 2 | 08 (L) | * Soil integrity procedures to reference Excavation Procedure. * Training and awareness of soil integrity issues | HSE and HELM | |
| | | Acid Sulphate Soil | soil and vegetation, fauna | Y | 2 | 2 | 08 (L) | N/A | 2 | 2 | 08 (L) | * Identify presence of Acid Sulphate Soils (diagram) * Account for acid sulphate processes | | |
| Use of herbicides/pes ticides for weed control (contractor and in-house activity) | Overspray, spillage | Overspray | Vegetation, soil contamination | Y | 2 | 1 | 02 (N) | Landholder liaison Weed spray and chemical training | 1 | 1 | 01 (N) | | | |



| | | | | En | viron | mer | ntal Ris | k Assessment | | | | | |
|---|--|--|--|----|-------|-----|-----------|---|---|---|-----------|--|---|
| Corrosion protection | Deep anode well drilling | Waste material and land disturbance | NC | NC | | | | | | | | | |
| General operation of equipment | * General operation of equipment* Maintenance, service vehicles* Valve calibration* Station ESD* Changing filter* Venting | Noise/vibrati on | Community concerns | Y | 3 | 2 | 09 (L) | Pipeline awareness and/orStakeholder consultation | 2 | 2 | 08 (L) | | |
| Ablutions mismanageme nt/leak | Sewage and grey water spill | Sewage and grey water spill | | NC | | | | | | | | | |
| Odorant handling, storage, transport | Release of odorant to air (Longford) | Odorant spill/leak | Community concerns/public outcry | Y | 3 | 2 | 09 (L) | Odorant Procedure OEMP Training Competent personnel Bunding Specialist machinery for transfers Emergency response manual and training (longford local) Charcoal filters Odorant flare | 2 | 2 | 08 (L) | | refer to hazard register Vic transmission |

| ŝafeg | Environmental Risk Assessment | | | | | | | | | | | | | |
|-------|--|---|----------------------------------|--|---|---|---|-----------|--|---|---|-----------|--|--|
| | | Release of odorant to air (Dandenong) | Odorant spill/leak | Community concerns/public outcry | Y | 3 | 2 | 09 (L) | CAssessment Odorant Procedure OEMP Training Competent personnel Bunding Specialist machinery for transfers Emergency response manual and training (longford local) Charcoal filters Odorant flare | 2 | 2 | 08 (L) | | |
| | | Release of odorant to land | Odorant spill/leak to land | Soil and groundwater contamination, vegetation growth | Y | 3 | 2 | 09 (L) | Odorant Procedure OEMP Training Competent personnel Bunding Specialist machinery for transfers Emergency response manual and training (longford local) Charcoal filters Odorant flare Spill kits | 2 | 2 | 08 (L) | | |
| | Compressor station, MLV and meter station general operations | * General operation of equipment * Maintenance, service vehicles * Valve calibration * Station ESD * Changing filter * Venting major pipeline section | Noise | Community concerns | Y | 3 | 2 | 09 (L) | Pipeline awareness and/or Stakeholder consultation | 2 | 2 | 08 (L) | | |



| Grey water drainage | Run off water containing oil or other contaminants (e.g. storm water) * Inadequate containment of drained material* Inadequate/lack of drainage | Contaminate d run-off water | Soil, groundwater and/or surface water contamination - insignificant | Y | 2 | 3 | 14 (M) | Interceptor systemsInternal bunding Inspection processesWork program | 1 | 3 | 11 (L) | | | |
|---|--|--|---|---|---|---|-----------|--|---|---|-----------|--|-----|--|
| Compressor, GEA and heater operation | General operation of equipment | Exhaust emissions | N20, CH4 and CO2 release. Reduction in local and regional air quality (with respect to NOx, SOx, CO2 and PM10). Global warming impacts - moderate | Y | 6 | 1 | 07 (L) | Maintenance regime Inspections Combustion analyses | 6 | 1 | 07 (L) | | | |
| Hazardous liquid materials storage/loss of containment(e. g. coolant, oil, chemicals) | * a/g tank inadequate bund capacity or leaching of oil through bund walls or floor * Flooding of bund (any oil in storage area washed out and enters surface water) * Spill during transfer to/from tanks (a/g) * Container damage Inadequate containment of materials (no bunding) | Hazardous liquid spill/leak (800L maximum) | soil and groundwater contamination | Y | 4 | 3 | 16 (M) | Work program (bunding inspections) Spill kits Training and awareness MSDS registers Chemical audits | 2 | 2 | 08 (L) | Review haz substances procedures and develop if required Training and awareness | HSE | |



| | | Environmental Risk Assessment | | | | | | | | | | | | | |
|-------------------------------------|--|--|---|--|---|---|---|-----------|---|---|---|-----------|---|-----|--|
| | General waste management (solid/liquid domestic waste (on-site) | Improper management of inert waste e.g. * Excessive build-up of waste * Inadequate or lack of containment * Damaged containers | General waste accumulatio n and/or spill | Aesthetics, hygiene and odour, vermin, fire risk | Y | 5 | 2 | 12 (M) | Contractor disposal Work program (housekeeping) Adequate containment | 3 | 2 | 09 (L) | Review waste management protocols and develop if required Training and awareness | HSE | |
| | handling of hazardous materials (e.g. coolant, waste oil, fuel, chemicals) | Mishandling of hazardous materials (e.g. coolant, waste oil, fuel, chemicals) or transport accident Inadequate containment of materials, or container damage | Hazardous liquid spill | soil and groundwater contamination | Y | 4 | 3 | 16 (M) | Work program (bunding inspections) Spill kits Training and awareness MSDS registers Chemical audits | 2 | 2 | 08 (L) | Review haz substances procedures and develop if required Training and awareness | HSE | |
| | Storage/handli ng of hazardous waste (e.g. lead acid batteries, paint containers, filter elements etc) | Improper management of regulated wastes e.g. * Poor containment or container damage, or no bunding * Mishandling of materials or transport accident | Hazardous waste | soil and groundwater contamination | Y | 4 | 3 | 16 (M) | Work program (bunding inspections) Spill kits Training and awareness MSDS registers Chemical audits Procedure | 2 | 3 | 14 (M) | Review hazardous waste disposal procedure (VIC) | HSE | |
| O&M - Gas pipeline management | Maintenance and operation of pipeline | Release of methane gas from* Corrosion* Equipment, pipeline and mechanical failure (e.g. valve leaks and joints)* Operator error* Third party damage | GHG emissions | localised air quality and GHG emissions, community | Y | 5 | 2 | 12 (M) | Cathodic protection Asset Management PlanWorks ProgramLandowner liaisonDBYDPipeline awarenessPIMPSCADA system/monitoringTrained and competent personnel | 2 | 2 | 08 (L) | | | |



| | Pipeline pigging | * Inadequate containment of waste material * Inappropriate disposal of waste material * Mishandling of waste material | Pipeline waste material spill | Soil and groundwater contamination | Y | 5 | 2 | 12 (M) | Pigging procedures Design catchment facilities Certified waste removalists Trained/competent people Risk assessments | 3 | 2 | 09 (L) | Review waste management protocols and develop if required Training and awareness | HSE | |
|----------------------|--|--|--|--|----|---|---|-----------|--|---|---|-----------|---|------|---------------------------------------|
| | Natural gas release (unplanned, controlled) | * Operator error * Station ESD | GHG emissions | localised air quality and GHG emissions, community | Y | 5 | 2 | 12 (M) | Asset Management Plan SCADA system Trained and competent people | 3 | 2 | 09 (L) | | | |
| | Natural gas venting (planned) | Routine maintenance/testing | GHG emissions | localised air quality and GHG emissions, community | Y | 6 | 1 | 07 (L) | Blow down procedure ENV 014 Trained/competent personnel Job specific risk assessment/work instruction | 6 | 1 | 07 (L) | | | |
| | Pipeline coating coal enamel | Repairing activities and new work (e.g. tap in) | Releases of asbestos containing enamel | soil and groundwater contamination | Y | 6 | 1 | 07 (L) | Plastic lining to contain debris Canopy to prevent dispersal for coal tar Licenced carriers for waste removal | 6 | 1 | 07 (L) | | | |
| | Pipeline hydraulic testing | Release of hydro test water | Water release | | NC | | | | | | | | | | Potable/clear water in workshop |
| Third party works | Third party works (e.g. grading) | Third party interference with easement | Soil integrity (compaction/ erosion etc) cultural, weed spread | Biodiversity, habitat, community nuisance | Y | 4 | 3 | 16 (M) | Pipeline awareness DBYD Works agreements Patrols Signage | 3 | 3 | 15 (M) | Improvement of third party awareness | HELM | |