



---

# **AusNet Transmission Group Pty Ltd**

## **Transmission Revenue Review 2017-2022**

### **XA09 – RTS Redevelopment Project: Business Case (Public)**

**Submitted: 30 October 2015**



# Business Case Application for Approval - REVISION 1

## XA09 Richmond Terminal Station (RTS) redevelopment project

<b>CAP #:</b>	T0435
<b>Project Initiator:</b>	[C-I-C]
<b>Contact No:</b>	[C-I-C]
<b>Initiating Dept / Div:</b>	NSD
<b>Prepared By ;</b>	[C-I-C]
<b>Date of Submission:</b>	March 2012
<b>Target Project Start Date:</b>	March 2010
<b>Target Project Completion Date:</b>	December 2016

## 1. RECOMMENDATION

In its meeting No. 02/10 on 26 March 2010 the Board passed a resolution to proceed with redevelopment of Richmond Terminal Station (RTS) with an estimated capital expenditure of \$137.3 million.

Acknowledging the planning and design criteria established for the Brunswick Terminal Station (BTS) augmentation project a detailed re-assessment of the RTS redevelopment project was undertaken. Focussing in particular on the urban design and environmental matters under the provisions of City of Yarra's planning scheme a design (**Concept Design**) for RTS re-development project was developed. This Concept Design has been confirmed through community consultation, assessment against planning scheme requirements and extensive engineering studies.

The Concept Design is significantly different to the initial design for this project. This project has been re-estimated and benchmarked to reflect current market conditions.

Approval is sought to:

- continue with redevelopment of Richmond Terminal Station (RTS), and
- increase the approved capital outlay from \$137.3 million to \$219.6 million.

## 2. FINANCIAL SUMMARY

### 2.1. PREVIOUSLY APPROVED

Program / Project Expenditure Forecasts	2010 / 11	2011 / 12	2012 / 13	2013 / 14	2014 / 15	2015 / 16	2016 / 17	Total
Program / Project Direct Expenditure	10,533	28,427	34,385	17,462	25,908	7,229		123,943
Program / Project Total Expenditure	11,408	30,891	37,995	20,678	28,812	7,562		137,347
Revenue	1,510	3,529	6,907	9,766	12,354	14,519	14,047	681,428
NPV								5,481
Payback Period (Discounted)								
Corporate WACC (Post Tax Nominal)								[C-I-C]

### 2.2. REVISED SUMMARY

Program / Project Expenditure Forecasts	2010 / 11	2011 / 12	2012 / 13	2013 / 14	2014 / 15	2015 / 16	2016 / 17	Total
Program / Project Direct Expenditure	2,277	2,747	36,844	55,520	43,999	35,392	1,451	178,229
Program / Project Total Expenditure	2,544	3,925	42,581	65,855	56,284	46,234	2,264	219,686
Revenue	1,119	1,411	3,516	8,451	12,959	16,998	19,081	890,813
NPV								7,147
Payback Period (Discounted)								36.8
Corporate WACC (Post Tax Nominal)								[C-I-C]

### 2.3. VARIANCE TO PREVIOUS APPROVAL

Program / Project Expenditure Forecasts	2010 / 11	2011 / 12	2012 / 13	2013 / 14	2014 / 15	2015 / 16	2016 / 17	Total
Program / Project Direct Expenditure	(8,255)	(25,680)	2,459	38,058	18,092	28,162	1,451	54,287
Program / Project Total Expenditure	(8,865)	(26,966)	4,585	45,177	27,471	38,672	2,264	82,339
Revenue	(391)	(2,117)	(3,391)	(1,316)	605	2,478	5,034	209,385
NPV								1,666

## 3. ENDORSEMENTS

Manager PMO  
Kerry Karafotias  
Date:

Network Owner  
Andrew Maticka  
Date:

Finance Manager  
Mark Campbell  
Date:

## 4. APPROVALS

Group General Manager,  
Networks Strategy and  
Development  
Charles Popple

Date: 29 May 2012

Chief Financial Officer  
Geoff Nicholson  
Date:

Managing Director  
Nino Ficca  
Date:

---

Project Initiator  
Herman De Beer  
Date:

Director, Regulation and Network Strategy  
Alistair Parker  
Date:

---

## 5. REASON FOR REVISION

<b>Revision Raised by:</b>	[C-I-C]
<b>Current Status of this Project:</b>	Delivery
<b>Trigger for Change:</b>	Scope
<b>Effects of Change on:</b>	
Strategic Alignment	No Change
Benefit	Community benefits are greatly increased as the proposed design would better integrate with the surrounding.
Scope	The proposed design of the project is significantly different from the initial design. The proposed design has also been influenced by extensive engineering studies undertaken to address site subsidence and soil contamination. The project scope is further defined in document "Richmond Terminal Station Rebuild – Scope of Works, Rev 2.1 dated 15 February 2012.
Work to be undertaken	The proposed design will require installation of gas insulated switchgear housed inside architecturally treated buildings, increased buffer zones and landscaping.
Cost	<p>Estimated cost increase from initial approval is \$82.25 million. Major contributing factors and associated cost increase are:</p> <ul style="list-style-type: none"> <li>- \$16.07 million to meet more stringent planning and environmental requirements which have led to design changes,</li> <li>- \$28.67 million to accommodate outcome of extensive engineering studies to inform the Concept Design and re estimation of project cost,</li> <li>- \$20.28 million to account for price escalation,</li> <li>- \$1.72 million to account for introduction of carbon tax on usage of SF<sub>6</sub> insulating gas, and</li> <li>- \$15.51 million to account for increase in overhead and financing cost.</li> </ul>
Risks	<ul style="list-style-type: none"> <li>- Significantly reduced OH&amp;S risks for civil works.</li> <li>- Reduced constructability risk as extensive engineering studies have been undertaken to inform the proposed design.</li> </ul>
<b>Impact Assessment File Name:</b>	Not applicable.
<b>Initial Approved Business Case File Name:</b>	

## 6. WORK TO BE UNDERTAKEN/DESCRIPTION OF WORK REQUIRED TO COMPLETE THE CHANGE

Initial:

The initial project scope broadly includes following:

- replacement of 150 MVA 220/66 kV transformers with standard 225 MVA transformers,
- replacement of 22 kV switchyard with GIS equipment,
- replacement of 220 kV switchyard with GIS equipment,
- replacement of 66 kV switchyard with AIS/GIS equipment,
- replacement of 66 kV protection and control, and
- replacement of 22 kV protection and control.

Change:

Below are the changes to the initial scope of the project:

- replacement of the 150 MVA 220/66 kV transformers with high impedance transformers,
- replacement of 66 kV switchyard with GIS equipment, and
- larger 220 kV and 66 kV buildings to accommodate the GIS equipment.

<b>Strategic Procurement</b>	Initial: The 220/66 kV transformers and GIS equipment are long lead items that require consideration when planning for delivery of this project.		
	Change: No change.		
<b>Program Timing</b>	Initial: Project completion in financial year 2015/16.		
	Change: Project completion in financial year 2016/17.		
<b>Composition of projects within the program</b>	Initial: Not applicable		
	Change: No change.		
<b>Other Associated Projects</b>	<b>Project Number/Title</b>	<b>Approved (Yes/No)</b>	<b>Cost</b>
	ZB12	Yes	\$17.26 million

## 7. OPTIONS CONSIDERED

Following options have been considered:

- Option 1: Redevelopment with GIS and 225 MVA 220/66 kV Transformers
- Option 2: Redevelopment with 66 kV AIS/GIS and 225 MVA transformers
- Option 3: Redevelopment with GIS and 150 MVA 220/66 kV Transformers
- Option 4: Staged Asset Renewal
- Option 5: Do Nothing

### *7.1. REDEVELOPMENT WITH GIS AND 225 MVA 220/66 KV TRANSFORMERS - PREFERRED OPTION*

This redevelopment option offers all of the construction efficiency and reliability advantages inherent with a compact indoor GIS redevelopment with circuit outages only required for cutover purposes. It minimises the supply risks during the redevelopment project and takes into account the importance of the CBD load supplied from RTS, and the concurrence of redevelopment projects at BTS and WMTS.

Community consultation and specialist studies undertaken to inform the Concept Design of RTS redevelopment highlighted the need to provide a design which is characterised by the land use and spatial forms of the local area. In February 2012 City of Yarra made a decision to grant a planning permit to the Concept Design presented in Attachment 1. Further extensive engineering studies have been undertaken to address site subsidence, constructability and management of contaminants present in RTS. Outcome of these studies has been included in the Concept Design of the project.

The Concept Design is significantly different to the initial design for this project. This project has been re-estimated and benchmarked to reflect current market conditions. Estimated cost increase of \$82.25 million is presented in section 5 of this paper.

This option provides for efficient future augmentation, allows for the ultimate plan for RTS and is economically justified by 2016 based on the community benefits delivered with more reliable transformers and 220 kV, 66 kV and 22 kV switchgear.

Sensitivity studies for discount rate and load growth scenarios confirmed that this is a robust, and the most economic credible option.

This option also models establishment of an additional transformer at RTS in 2027/28 to meet transformation capacity needs.

### *7.2. OPTION 2: REDEVELOPMENT WITH 66 KV AIS/GIS AND 225 MVA TRANSFORMERS*

In March 2010 this design option was approved by the Board.

In June 2010 a similar hybrid air-insulated-switchgear / gas-insulated-switchgear design for the BTS augmentation project was not supported by Moreland City Council and local community as:

- the proposal for the BTS project did not conform with local or state government planning requirements; and
- the design compromised environmental values; and was visually intrusive.

Further under the Planning and Environmental Act 1987 Moreland City Council had referred the planning permit application for BTS augmentation project to City of Yarra as a referral authority. City of Yarra had formally objected to the proposed design as it considered the design had detrimental impact on the visual amenity of the Merri Creek environment.

The site context and spatial form around RTS is similar to BTS.

Acknowledging the planning decision of this design option for BTS and considering the similarity of site context of both RTS and BTS, hybrid design option for RTS will not satisfy the provision of state and City of Yarra's planning scheme, nor would it be supported by the community and thus could not be implemented.

This hybrid AIS/GIS design option is no longer the preferred option.

### *7.3. OPTION 3: REDEVELOPMENT WITH GIS AND 150 MVA 220/66 KV TRANSFORMERS*

This option is similar to the preferred option except it employs 150 MVA 220/66 kV transformers instead of 225 MVA transformers. This option is not recommended for following reasons:

- the PV cost is higher than Option 1 due to the need to augment the 220/66 kV transformers more often to provide the same transformation capacity,
- the restricted RTS site limits the ultimate transformation capacity possible with this option resulting in the establishment of a new site in 2027/28 for subsequent capacity increases.
- GIS transformer switching cost at 220 kV and 66 kV are higher than AIS transformer switching cost, and
- it provides a less secure switching arrangement in the ultimate stage when five or six 150 MVA transformers are required compared with four units in Option 1.

The increase in project costs for the preferred option will also impact this option and thus the relative ranking has not changed – this option remains the second lowest PV cost.

#### *7.4. OPTION 4: STAGED ASSET RENEWAL*

This option proposes replacement of assets as a series of discrete projects undertaken over a number of years, targeting the replacement of the highest risk assets. This option is no longer a credible option for following reasons:

- the age and condition of the assets at RTS suggest that little deferment of capital expenditure would be possible,
- it will not meet the state and local planning scheme requirements for the site and will not be approved by the Council, and
- the uncertainty regarding the timing of the completion of the BTS augmentation project to allow load to be transferred from RTS to BTS.

Apart from the technical and planning approval aspects, this option also has a higher PV cost as shown in the economic analysis undertaken for the RTS Redevelopment Business Case. New information on the load demand forecast for RTS and the revised schedule for the BTS completion shows that the community cost of this option has increased and the ranking of third position, in the original submission, remains unchanged.

This option also models establishment of a new site in 2027/28 to meet transformation capacity needs.

#### *7.5. DO NOTHING \*MANDATORY*

The PV cost of this option has increased commensurate with the increase in the latest load demand forecast for RTS over the load demand forecast used in the 2009/10 assessments. A high level assessment of the incremental benefits provided by more reliable transformers shows that capital expenditure of up to \$240 M (real 2012) is economic in 2016 to avoid the probability weighted risk of supply interruptions to customers supplied from RTS 66 kV circuits.

Further this option is not consistent with SP AusNet's obligations to meet network performance and reliability standards under the National Electricity Rules (NER) and the accepted Electricity Safety Management Scheme and is used for economic comparison only.

NPV analysis of the options in the initial paper is presented below:



Options	\$'000	PV Capital Cost	PV Opex Costs	PV Community Benefits / Costs	PV Proceeds from sales	Total PV Cost	NPV including Regulatory Return
Do Nothing		(\$59,853)	(\$9,127)	(\$85,267)	-	(\$154,247)	\$1,736
225 MVA Transformers		(\$112,611)	-	-	-	(\$112,611)	\$5,481
150 MVA Transformers		(\$115,365)	-	-	-	(\$115,365)	\$5,611
Staged Asset Renewal		(\$117,087)	(\$727)	(\$2,416)	-	(\$120,230)	\$5,856
-		-	-	-	-	-	\$3,593

All figures are in \$000's unless otherwise stated.  
(nominal and discounted)

Changed NPV analyses of the options are:

Economic Analysis of Options (\$'000s)	PV Capital Cost	PV Opex Costs	PV Community Benefits	PV Proceeds From Sales	Total PV Cost	NPV including Reg Return
Do Nothing	(86,267)	(9,359)	(88,347)	-	(183,974)	5,659
225 MVA Transformers	(142,276)	(3,072)	-	-	(145,348)	7,147
150 MVA Transformers	(143,677)	(3,072)	-	-	(146,749)	7,908
Staged Asset Renewal	(145,901)	(10,118)	(2,515)	-	(158,534)	7,608
-	-	-	-	-	-	-

All figures are in \$000's unless otherwise stated.  
(nominal and discounted)

## 8. BENEFITS

### 8.1. INITIAL BENEFITS

<b>Business Driver</b>	Strengthen	Regulated Network Reliability and Resilience	Strong
<b>Benefit &amp; Measure</b>	o By replacing these high risk assets, that are in poor condition, network reliability and availability will be enhanced		
<b>Business Driver</b>	Strengthen	Compliance	Strong
<b>Benefit &amp; Measure</b>	o The proposed redevelopment project will ensure continued compliance with the network performance and reliability requirements defined in the NER		
<b>Business Driver</b>	Transform	Customer and Community	Strong
<b>Benefit &amp; Measure</b>	o Customer service is improved by reducing the risk of their supply being adversely impacted.		
<b>Business Driver</b>	Transform	Sustainability	Strong
<b>Benefit &amp; Measure</b>	<ul style="list-style-type: none"> <li>o The new transformer will have lower losses than the existing transformers, allowing power to be transmitted more efficiently.</li> <li>o Removal of health and safety risk associated with older plant, particularly the 22 kV switch board.</li> </ul>		
<b>Business Driver</b>	Modernise	New Technologies	Low
<b>Benefit &amp; Measure</b>	o The new 220 kV and 66 kV GIS will reduce the terminal station's footprint.		

## 8.2. NEW BENEFITS

<b>Business Driver</b>	Transform	Community	Strong
<b>Benefit &amp; Measure</b>	<ul style="list-style-type: none"> <li>○ Complete migration of the 66 kV switchyard inside a building will greatly increase community benefits as the proposed design would better integrate with the surrounding.</li> </ul>		

## 9. RISK OF REVISION NOT BEING APPROVED

### 9.1. INITIAL

<b>Business Driver</b>	Strengthen	Regulated Network Reliability and Resilience	Strong
<b>Identified Risk of NOT being approved</b>	<ul style="list-style-type: none"> <li>○ The community cost due to the increased frequency and duration of service disruptions will exceed the cost of funding improvements in the reliability of electricity supplies from RTS.</li> </ul>		

<b>Business Driver</b>	Strengthen	Compliance	Strong
<b>Benefit &amp; Measure</b>	<ul style="list-style-type: none"> <li>○ Non-compliance with the network performance and reliability requirements stated in the National Electricity Rules.</li> </ul>		

<b>Business Driver</b>	Strengthen	Safety and Environment	Strong
<b>Benefit &amp; Measure</b>	<ul style="list-style-type: none"> <li>○ Non compliance with the accepted Electricity Safety Management Scheme.</li> <li>○ Increased risk of transformer failure</li> </ul>		

### 9.2. NEW

There is no change since initial approval.

## 10. DELIVERY OF PROJECT RISKS (KNOWN)

<b>Risk</b>	<b>What could occur</b>
Health Environment and safety	SP AusNet's standard health and safety procedures will be followed for the project including development and implementation of site specific construction, environment and safety plan. Assessment of noise emissions and EMF associated with the Concept Design has been undertaken and both are well below the prescribed levels.
Construction	The redevelopment of RTS is considered a complex project and allowances have been made to manage the design and construction risk of the recommended lowest project risk option. The complexity of the project will be taken into account at all stages of the project and accredited external service providers will be used to carry out design and construction activities. In-house engineering services staff will review these services using

	established processes to monitor work quality, compliance, performance and risk. A detailed Construction and Environment Management Plan (CEMP) will be developed to plan and manage construction activities. The CEMP will also outline the process of information sharing with the community and City of Yarra.
Network outage	The construction sequence and work scope for each element of the project has been developed to minimise the requirement for sustained line outages and hence the risk exposure which they present to the overall program.

## 11. FINANCIAL IMPACTS

### 11.1. EXPEND CAT / WORK CODE:

CG1R.

### 11.2. ECONOMIC EVALUATION OPTIONS

For the full Financial Evaluation of the options considered and supporting financial details refer to the attached RTS NPV Model.

**TABLE: Financial Analysis of Preferred Option**

Financial Forecasts (\$'000s)	2010 / 11	2011 / 12	2012 / 13	2013 / 14	2014 / 15	2015 / 16	2016 / 17	Total
Revenue								
Expenses								
Capital								
Savings								
Working Capital								
Residual Revenue								
Tax								
Net Cash Flow (excludes financing)								
NOPAT (EVA, excludes interest)								
Capital Charge								
EBITDA								
EBIT								
NPAT								
Earnings / (Loss) per Share cents								
NPV								[C-I-C]
WACC (Post Tax Nominal)								

All figures are in \$000's unless otherwise stated. (nominal)

**TABLE: Economic Analysis of Options**

Economic Analysis of Options (\$'000s)	PV Capital Cost	PV Opex Costs	PV Community Benefits	PV Proceeds From Sales	Total PV Cost	NPV including Rea Return
Do Nothing	(86,267)	(9,359)	(88,347)	-	(183,974)	5,659
225 MVA Transformers	(142,276)	(3,072)	-	-	(145,348)	7,147
150 MVA Transformers	(143,677)	(3,072)	-	-	(146,749)	7,908
Staged Asset Renewal	(145,901)	(10,118)	(2,515)	-	(158,534)	7,608
	-	-	-	-	-	-

All figures are in \$000's unless otherwise stated. (nominal and discounted)

**TABLE: Project Expenditure Forecasts**

Project Expenditure Forecasts (\$'000s)	2010 / 11	2011 / 12	2012 / 13	2013 / 14	2014 / 15	2015 / 16	2016 / 17	Total
Design								
Internal Labour								
Materials								
Plant & Equipment								
Contracts								
Meter Costs								
Other								
Project Direct Expenditure (P50)	2,277	2,747	36,844	55,520	43,999	35,392	1,451	178,229
Delivery Risk Adjustment =(P90-P50)								
Project Direct Expenditure plus risk (P90)								
Overheads								
Finance Charges								
Operating Costs / (Savings)								
WDV (Written Down Value) of Assets to be retired								
Total Estimated Expenditure for Approval	2,544	3,925	42,581	65,855	56,284	46,234	2,264	219,686
NPV								[C-I-C]
Corporate WACC (Post Tax Nominal)								

**TABLE: Contribution of Projects to Key Business Metrics**

Contribution of Projects to Key Business Metrics	2010 / 11	2011 / 12	2012 / 13	2013 / 14	2014 / 15	Post 2014 / 15
Opex (Costs) / Savings	-	\$103	\$211	\$540	\$887	\$12,796
OH&S	-	-	-	-	-	-
System Capacity	-	-	-	-	\$18,524	\$185,081
Environmental Risk	-	-	-	-	-	-
Regulatory Compliance	-	-	-	-	-	-
Bushfire Mitigation	-	-	-	-	-	-
Corporate Image	-	-	-	-	-	-
Reliability	-	-	-	-	-	-
Incentive Revenue	-	-	-	-	-	-
Asset Failure Risk	-	-	-	-	-	-
Gas Mains Renewal	-	-	-	-	-	-

All figures are in \$000's unless otherwise stated.  
(nominal)

**TABLE: Capitalised Finance Charges (Interest During Construction)**

Financial Year (\$'000s)	Month	Project Direct Expenditure				Net Monthly Expenditure	Cummulative WIP Balance	Transferred into RAB (Sarcode)	Customer Contribution Received into Trust	Finance Charges	Total Finance Charges	Cumulative Finance Charges
		Project Direct Expenditure \$Real	Project Direct Expenditure \$Nominal	Overheads	Totals							
2010 / 2011	Apr-10	-	-	-	-	-	-	-	-	-	-	
	May-10	1	1	0	1	1	-	-	-	-	-	
For A to P:	Jun-10	745	745	52	797	804	-	-	-	-	-	
Direct	Jul-10	114	114	8	122	932	-	-	-	-	5	
Overheads	Aug-10	159	159	11	167	1,105	-	-	-	-	6	
Finance Charges	Sep-10	154	154	11	165	1,280	-	-	-	-	12	
	Oct-10	49	49	3	52	1,341	-	-	-	-	16	
Error checks (\$Real)	Nov-10	298	298	21	319	1,671	-	-	-	-	28	
Direct	Dec-10	82	82	6	87	1,771	-	-	-	-	37	
Overheads	Jan-11	98	98	7	105	1,899	-	-	-	-	49	
	Feb-11	419	419	20	440	2,354	-	-	-	-	61	
	Mar-11	162	162	11	173	2,544	-	-	-	-	74	
	Apr-11	228	234	16	260	2,914	-	-	-	-	90	
	May-11	307	315	22	337	3,172	-	-	-	-	107	
For A to P:	Jun-11	218	224	16	240	3,435	-	-	-	-	126	
Direct	Jul-11	165	169	12	181	3,641	-	-	-	-	146	
Overheads	Aug-11	131	134	9	144	3,811	-	-	-	-	163	
Finance Charges	Sep-11	243	249	17	267	4,105	-	-	-	-	171	
	Oct-11	366	376	26	402	4,539	-	-	-	-	196	
Error checks (\$Real)	Nov-11	212	218	15	233	4,805	-	-	-	-	222	
Direct	Dec-11	78	80	6	85	4,924	-	-	-	-	250	
Overheads	Jan-12	201	207	14	221	5,180	-	-	-	-	281	
	Feb-12	374	384	27	411	5,629	-	-	-	-	314	
	Mar-12	153	157	11	168	5,837	-	-	-	-	348	
	Apr-12	1,241	1,307	91	1,306	7,285	-	-	-	-	383	
For A to P:	May-12	1,113	1,172	82	1,254	8,598	-	-	-	-	422	
Direct	Jun-12	1,133	1,193	84	1,277	9,942	-	-	-	-	462	
Overheads	Jul-12	3,540	3,727	261	3,988	14,028	-	-	-	-	511	
Finance Charges	Aug-12	5,594	5,889	412	6,301	20,466	-	-	-	-	570	
	Sep-12	6,624	6,973	488	7,461	28,119	-	-	-	-	638	
Error checks (\$Real)	Oct-12	2,477	2,807	182	2,790	31,121	-	-	-	-	703	
Direct	Nov-12	2,523	2,656	186	2,842	34,197	-	-	-	-	773	
Overheads	Dec-12	2,499	2,631	184	2,815	37,266	-	-	-	-	833	
	Jan-13	3,183	3,330	233	3,563	41,110	-	-	-	-	893	
	Feb-13	2,492	2,624	164	2,807	44,219	-	-	-	-	953	
	Mar-13	2,599	2,736	192	2,926	47,471	-	-	-	-	1,005	
	Apr-13	3,381	3,651	256	3,907	51,731	-	-	-	-	1,055	
For A to P:	May-13	12,309	13,294	931	14,225	66,409	-	-	-	-	1,105	
Direct	Jun-13	3,398	3,670	257	3,927	70,820	-	-	-	-	1,151	
Overheads	Jul-13	3,398	3,670	257	3,927	75,251	-	-	-	-	1,201	
Finance Charges	Aug-13	5,339	5,766	404	6,170	81,786	30,000	-	-	-	1,251	
	Sep-13	4,198	4,534	317	4,851	87,026	-	-	-	-	1,301	
Error checks (\$Real)	Oct-13	3,752	4,053	284	4,336	91,784	-	-	-	-	1,351	
Direct	Nov-13	2,988	3,205	224	3,430	95,663	-	-	-	-	1,401	
Overheads	Dec-13	3,235	3,494	245	3,738	99,878	-	-	-	-	1,451	
	Jan-14	3,235	3,484	245	3,738	104,110	-	-	-	-	1,501	
	Feb-14	3,264	3,525	247	3,772	108,431	-	-	-	-	1,551	
	Mar-14	2,929	3,184	221	3,385	112,379	-	-	-	-	1,601	
	Apr-14	3,345	3,706	280	3,968	116,715	30,000	-	-	-	1,651	
For A to P:	May-14	6,540	7,254	508	7,762	121,899	-	-	-	-	1,701	
Direct	Jun-14	3,396	3,764	263	4,027	126,990	-	-	-	-	1,751	
Overheads	Jul-14	3,396	3,764	263	4,027	132,091	-	-	-	-	1,801	
Finance Charges	Aug-14	2,896	3,209	225	3,434	137,330	-	-	-	-	1,851	
	Sep-14	2,896	3,209	225	3,434	142,600	-	-	-	-	1,901	
Error checks (\$Real)	Oct-14	5,396	5,960	419	6,398	148,000	-	-	-	-	1,951	
Direct	Nov-14	2,396	2,655	186	2,841	153,441	-	-	-	-	2,001	
Overheads	Dec-14	2,396	2,655	186	2,841	158,882	40,000	-	-	-	2,051	
	Jan-15	2,346	2,600	182	2,792	164,434	-	-	-	-	2,101	
	Feb-15	2,346	2,600	182	2,792	170,000	-	-	-	-	2,151	
	Mar-15	2,346	2,600	182	2,792	175,666	-	-	-	-	2,201	
	Apr-15	2,888	3,281	230	3,511	181,357	-	-	-	-	2,251	
For A to P:	May-15	2,386	2,713	190	2,902	187,333	-	-	-	-	2,301	
Direct	Jun-15	2,386	2,713	190	2,902	193,333	-	-	-	-	2,351	
Overheads	Jul-15	4,736	5,384	377	5,761	200,034	-	-	-	-	2,401	
Finance Charges	Aug-15	2,336	2,656	186	2,842	206,838	-	-	-	-	2,451	
	Sep-15	2,336	2,656	186	2,842	213,686	-	-	-	-	2,501	
Error checks (\$Real)	Oct-15	2,336	2,656	186	2,842	220,600	60,000	-	-	-	2,551	
Direct	Nov-15	2,336	2,656	186	2,842	227,588	-	-	-	-	2,601	
Overheads	Dec-15	2,302	2,617	183	2,800	234,617	-	-	-	-	2,651	
	Jan-16	3,327	3,783	265	4,047	241,707	-	-	-	-	2,701	
	Feb-16	1,888	2,258	158	2,416	249,123	-	-	-	-	2,751	
	Mar-16	1,778	2,021	141	2,163	256,992	-	-	-	-	2,801	
	Apr-16	1,244	1,451	102	1,552	264,544	16,047	-	-	-	2,851	
For A to P:	May-16	-	-	-	-	-	-	-	-	-	2,901	
Direct	Jun-16	-	-	-	-	-	-	-	-	-	2,951	
Overheads	Jul-16	-	-	-	-	-	-	-	-	-	3,001	
Finance Charges	Aug-16	-	-	-	-	-	-	-	-	-	3,051	
	Sep-16	-	-	-	-	-	-	-	-	-	3,101	
Error checks (\$Real)	Oct-16	-	-	-	-	-	-	-	-	-	3,151	
Direct	Nov-16	-	-	-	-	-	-	-	-	-	3,201	
Overheads	Dec-16	-	-	-	-	-	-	-	-	-	3,251	
	Jan-17	-	-	-	-	-	-	-	-	-	3,301	
	Feb-17	-	-	-	-	-	-	-	-	-	3,351	
	Mar-17	-	-	-	-	-	-	-	-	-	3,401	
Total					190,705				18,342	18,342		
Cash flow amount should equal the total direct as shown on page 1 of the A to P											2	
Total Including Finance Charges											209,047	

**11.3. BUDGET PROVISION**

There is an allowance within the company initiated transmission budget to fund this project in the financial years from 2010/11 to 2016/17.

**11.4. REVENUE**

NER Schedule 6A.2.1 "Establishment of opening regulatory asset base for a regulatory control period" Clause (f) (1) requires that:

*"The previous value of the regulatory asset base **must be increased by the amount of all capital expenditure incurred** during the previous control period, including any capital expenditure determined for that period under clause 6A.8.2(e)(1)(i) in relation to contingent projects where the revenue determination has been amended by the AER in accordance with clause 6A.8.2(h) (regardless of whether such capital expenditure is above or below the forecast capital expenditure for the period that is adopted for the purposes of the transmission determination (if any) for that period)." (Emphasis added)*

Furthermore, the AER recognises that it does not approve individual projects. For example, in the January 2008 SP AusNet Revenue Determination:

*"... the AER reiterates that the total forecast capex approved is an allowance only, and is not tied to a fixed, project specific, work program. Within the approved allowance, SP AusNet retains the discretion regarding the allocation and expenditure of capex, and is expected to be responsive to changing conditions in order to meet the prescribed capex objectives."*

On this basis it is reasonable to assume that all costs incurred in this project will be included in the Regulated Asset Base (**RAB**) and generate revenue accordingly.

### 11.5. FINANCIAL RISKS

This project will be completed in the next regulatory control period and will be subject to approval of the capital expenditure allowance set at the next Transmission Revenue Reset (TRR) by the AER. Noting that the AER does not approve individual capital projects and SP AusNet has the ability to prioritise works within the period, it is unlikely SP AusNet would be required to fund a capital shortfall due to redevelopment of RTS. Any shortfall in funding would at worst be limited to the financing cost incurred until the end of the period, as the National Electricity Rules (NER) require that "the value of the regulatory asset base must be increased by the amount of all capital expenditure incurred regardless of whether such capital expenditure is above or below the forecast capital expenditure for the period".

The AER will be most likely to approve the associated capital expenditure allowance if an approved business case is available at the next regulatory review, funding is committed and construction is underway.

The new assets will roll into the RAB at the end of the next regulatory period at their depreciated constructed value.

The financial risks are being treated as follows:

- AEMO (the Australian Energy Market Operator) and the two Distribution Businesses (CitiPower and United Energy Distribution) supplied from RTS have confirmed the ongoing need of the RTS facilities in accordance with the proposed redevelopment,
- a detailed Project Execution Plan will minimise the number and duration of outages, limiting the associated rebate cost;
- the project has been carefully estimated to cover the additional cost that may arise because this is a brown field development, and
- capital efficiency will be targeted by a combination of foreign exchange hedging, period order purchasing, fixed-price subcontracts and in-house project execution processes.

### 11.6. ASSET RETIREMENTS, CONTRIBUTED (GIFTED) ASSETS, CUSTOMER CONTRIBUTION REVENUE

The fixed assets accounting team were consulted regarding the Write Down Value (**WDV**) of the assets to be retired. The total WDV is \$5.1 million.

### 11.7. CORPORATE ACCOUNTING AND TAX ADVICE

The project is a usual business transaction and does not require any special corporate accounting, tax advice, or sign off.



## ATTACHMENT 1 CONCEPT DESIGN



View from Allan Bain Reserve – Existing




View from Allan Bain Reserve – Concept Design

"This view location is from Monash Freeway, taken from in bound lane to the city. It is a significant view shed of RTS as it is experienced by over 100,000 motorists per day."

Fleeting distant view from the Freeway. The skyline is dominated by RTS racks and the Machine Building in the distance. The existing vegetation partially filters the views into site.

RTS Machine Building in the background.



View from Monash Freeway – Existing



The proposed mitigation of the 220kV buildings involves an outer skin of perforated metal that produces a pattern or graphic according to the varying size of the holes. The outer skin extends up beyond the building behind to create a parapet that reduces the strong outline of the building and blends it into the skyline. The broad south elevation is split into two cubes to break up the visual mass and diminish visual bulk. The metal outer skin creates an attractive and active interface with the public domain, and is accentuated by the moving observer of the freeway with play of light and depth.

The pattern (illustrated abstract clouds) is indicative only. The image/graphic is to be developed in consultation with stakeholders.

View from Monash Freeway – Concept Design



This view location is from McConchie Reserve, taken directly in front of Mary Street. It has been identified as a significant view shed as it is close proximity to the vine grain residential area of Mary Street, along the pathway linking Allen Basin to McConchie Reserve.

RTS Machine Building and structures are visible to the southern elevation of the site and are partially filtered by the established landscape of the McConchie Reserve.

McConchie Reserve and Wetlands

View from McConchie Reserve – Existing



The perforated outer skin blends the edges of the 220kV switch building into the skyline.

The proposed is a more legible and transparent built form that makes a positive and attractive contribution to the landscape and skyline.

View from McConchie Reserve – Concept Design